

**TOWN OF MILLIS**  
**Monday January 8<sup>th</sup> 2023 6:00 PM**  
**Remote -Hybrid**  
<https://us02web.zoom.us/j/85909246761>

- 6:00 p.m. Open BOH Meeting.
- 6:10 p.m. Nurse Report
- 6:15 p.m. EHIR Well #3 DPW Kleinfelder
- 6:30 p.m. Richardson Dr. Toll Brothers RGE issue continued
- 6:40 p.m. Discussion Wetlands flooding
- 7:00 p.m. Discussion 121 Norfolk Rd wireless station
- 7:15p.m. Approval of Meeting Minutes
- 7:30 p.m. Discussion

**Director's report**  
**Nurse's report**  
**Payables Sign-off**

- Approval of minutes ( November 13<sup>th</sup> December 4<sup>th</sup> 2023)
- Food Recalls (website)
- Review of Monthly Activity
- Correspondence

*Tentative Date of Next Meeting:*  
*February 5<sup>th</sup> 2024*

<b>TOWN OF MILLIS</b> <b>Notice of Meeting</b>
<b><u>The BOARD OF HEALTH</u></b>
<b>Will Remote -Hybrid Meet at 6:00 P.M.</b>
<b>On Monday January 8<sup>th</sup> 2024</b>
<b>Zoom Online meeting.</b>
<hr style="width: 20%; margin: auto;"/> <b>Assistant Town Clerk</b>
<b>Posted _____, 2024</b>

Topic: Board of Health Meeting  
Time: Jan 8, 2024 06:00 PM Eastern Time (US and Canada)  
<https://us02web.zoom.us/j/85909246761>  
Meeting ID: 859 0924 6761  
+13126266799,,85909246761# US (Chicago)

+16469313860,,85909246761# US





**Millis Board of Health**

900 Main Street  
Millis, MA 02054

**SUBJECT: Well 3 Water Treatment Plant, Millis, MA.**

To Whom it may concern:

The Town of Millis Department of Public Works and Kleinfelder are currently working on the design of a new drinking water treatment facility at the Well 3 site off Birch Street. The new treatment plant is needed to remove per- and polyfluoroalkyl substances (PFAS) and provide clean drinking water to Millis residents. This project will require the export of approximately 1,400 cubic yards of soil as needed for the construction of stormwater detention systems, building foundations, and subsurface utilities. As such, this project requires an EHIR to be submitted to the Millis Board of Health.

A Notice of Intent (NOI) was filed with the Millis Conservation Commission and the project was subsequently issued an Order of Conditions (DEP File #225-0442). Per the Millis of Board Public and Environmental Health Review Regulations and Standards an NOI filed with the Conservation Commission may be accepted as the EHIR if deemed appropriate by the Board of Health. We believe that the NOI filing provided herein provides adequate detail for the Board of Health Review including a project narrative, stormwater design report, construction plans, and information regarding wetland resources adjacent to the construction area.

If you have any additional questions or need additional details to complete the review, feel free to reach me at 617-498-4772 or by email at [tbernier@kleinfelder.com](mailto:tbernier@kleinfelder.com)

Thank you for your time.

Sincerely,

**KLEINFELDER**

Tyler Bernier  
Project Manager

cc: Mr. James McKay, Director, Millis Department of Public Works  
File

January 3, 2023

Mr. John McVeigh  
Health Director  
Board of Health  
Town of Millis  
900 Main Street  
Millis, MA 02054

**RE: Peer Review – EHIR Well #3 Treatment Plant PFAS Upgrades**

Dear Mr. McVeigh:

As requested, GCG has reviewed the EHIR submittal for improvements proposed at the Town of Millis Well #3 adjacent to Birch Street for compliance with Millis Board of Health Public and Environmental Health Review Regulations and Standards. The submittal prepared by Kleinfelder dated October 30, 2023 included the following component which were reviewed under the EHIR.

- Notice of Intent (reviewed with respect to EHIR only)
- Project Plans, Town of Millis, Massachusetts, Well 3 Water Treatment Facility dated October 2023.
- Stormwater Report, dated October 2023

The project involves the construction of a new building to accommodate the proposed PFAS treatment system which includes four 10,000-pound GAC filters for the well. Site improvements for the new building include paving, regrading, demolition of existing building, stormwater improvements, sewage tite tank and water treatment improvements.

Based upon our review of the above information, we offer the following comments with respect to compliance with Millis Board of Health Public and Environmental Health Review Regulations and Standards. The numerical section of the regulations is referenced at the beginning of each comment as it relates to the regulations.

**SECTION VII – WATER SUPPLY**

The proposed improvements to the existing Millis water supply are required based upon meeting current PFAS standards. The system appears to be designed to follow current standards and regulations with respect to water treatment of PFAS. The Town has hired Kleinfelder as their consultant to design this system. GCG did not review the actual design for compliance.

**SECTION VIII – SEWAGE DISPOSAL**

The project is in a Zone 1 for the existing water supply and disposal of wastewater is not permitted in a Zone 1. The applicant proposes a 2000-gallon tank with no discharge of sewage. The plan set references sewer plans which were not found in the application. Sewage flows and design should be provided for review.

## SECTION XII. - DRAINAGE

The stormwater drainage systems is designed for storm events up to a 100 year storm event. In general, the design meets the goals of the drainage regulations with the following exceptions.

1. The cover over the 8" drain is less than one foot in the paved area of the stormwater forebay in front of the building.
2. The drain from the forebay to forebay should be extended so that it is at the bottom of the infiltration basin.
3. The rip rap area at the end of the pipe connecting the forebays should be shown at the toe of the slope. It is not necessary to place rip rap on the slope.
4. MassDEP Stormwater Handbook recommends a 10-foot area around the basin to allow access. The current basin has a three-foot strip for the top of the berm.
5. The stormwater report shows that the rate of flow does not increase. A table should be provided to show the volume does not increase as required under the regulations.
6. Calculations should be provided showing the drain time of the infiltration basin. Seventy-two hours are recommended in the Stormwater Handbook.
7. The regulations require 4 to 1 slope for basins. The design has 3 to 1 slope.
8. A test hole should be performed in the basin to confirm the 2-foot groundwater separation is met or provide other documentation. The adjacent wetlands are at elevation 121 which may be indicative of the water table elevation. The bottom of the basin is at elevation 122.
9. The basin should have one foot of freeboard during a 100-year event.

## SECITON XIII – EARTH REMOVAL STANDARDS

The volume of material removed was not provided to allow for a determination if review under this regulation is required. In general, the design appears to comply with the intent of the standard under this section.

If you have any questions regarding these matters, please contact our office.

Respectfully Submitted,  
GCG Associates

*Michael J. Carter*

Michael J. Carter, P.E.  
Project Manager

**Camille Standley**

---

**From:** CERO\_NOI@MassMail.state.ma.us  
**Sent:** Monday, November 13, 2023 12:18 PM  
**To:** gary.dulmaine@mass.gov  
**Cc:** cero\_noi@state.ma.us; camille.standley@comcast.net; Camille Standley; cero\_noi@state.ma.us  
**Subject:** MassDEP NOI File Number

**CAUTION:** This email originated from outside of the Town of Millis mail system. Do not click links or open attachments unless you recognize the sender and know the content is safe.

COMMONWEALTH OF MASSACHUSETTS  
EXECUTIVE OFFICE OF ENERGY & ENVIRONMENTAL AFFAIRS  
**DEPARTMENT OF ENVIRONMENTAL PROTECTION**  
CENTRAL REGIONAL OFFICE  
8 NEW BOND STREET, WORCESTER, MA 01606 508-792-7650

Date: 11/13/2023 Municipality MILLIS

RE: **NOTIFICATION OF WETLANDS PROTECTION ACT FILE NUMBER**

The Department of Environmental Protection has received a Notice of Intent filed in accordance with the Wetlands Protection Act (M.G.L. c. 131, §40):

<b>Applicant</b> TOWN OF MILLIS		
<b>Address</b> 900 MAIN STREET, MILLIS MA 02054		<b>Owner Address</b>
<b>Locus</b> VILLAGE STREET , MILLIS MA 02054		

This project has been assigned the following file # : **CE 225-0442**  
ISSUANCE OF A FILE NUMBER INDICATES ONLY COMPLETENESS OF SUBMITTAL, NOT APPROVAL OF APPLICATION  
Although a file # is being issued, please note the following:

Regards,  
for MassDEP,  
  
(508)-767-2713  
Gary.Dulmaine@mass.gov



October 30, 2023

Town of Millis Conservation Commission  
900 Main Street  
Millis, MA 02054

RE: Notice of Intent  
Well #3 Water Treatment Plant PFAS Upgrades  
Birch Street, Millis

Dear Commission Members:

The Town of Millis Department of Public Works (DPW) is proposing to demolish existing water infrastructure and construct a new treatment / PFAS plant and associated infrastructure to Well #3 of Birch Street in Millis, MA. The Town of Millis well is currently offline due to the elevated PFAS levels, and requires additional treatment before it can be brought back online. The size and number of the filtration units will require a significant footprint. Adding on to the current building is not feasible, so DPW is proposing to construct a new building on the site.

A Wetland Resource Area protected under the Wetland Protection Act (WPA) (310 CMR 10.0) is located within 100 feet of the proposed limit of work. In accordance with the requirements of the WPA, please find enclosed copies of the Notice of Intent and reduced plan copies (11"x17") of the project site plans for your review.

Federal Emergency Management Agency (FEMA) floodplain mapping for the Town of Millis shows the limits of work within the 100-year floodplain; however proposed activities within this area propose to maintain or lower existing ground surface elevation.

We respectfully request the Commission to schedule a public hearing for the Conservation Commission meeting on November 13, 2023. Please contact the DPW or myself at the below number if you have any questions regarding this project. Thank you for your consideration on this matter.

Respectfully yours,

Tyler Bernier  
Kleinfelder

cc: James McKay, Millis Department of Public Works



## **Table of Contents**

### **Notice of Intent Forms**

WPA Form 3 – Notice of Intent  
NOI Wetland Fee Transmittal Form

### **Notice of Intent Figures**

Figure 1 – Tax Parcel Map  
Figure 2 – USGS Locus Map  
Figure 3 – Aerial Map  
Figure 4 – NHESP Map  
Figure 5 – Flood Zone Map


**Attachment A – NOI Narrative**

**Attachment B – Abutter Information**

**Attachment C – Wetland Data Forms**

**Attachment D – Project Plans**

**Attachment E – Stormwater Report**



Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

**WPA Form 3 – Notice of Intent**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

MassDEP File Number
Document Transaction Number
Millis
City/Town

**Important:**  
When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



Note:  
Before completing this form consult your local Conservation Commission regarding any municipal bylaw or ordinance.

**A. General Information**

1. Project Location (**Note:** electronic filers will click on button to locate project site):

Village Street	Millis	02054
a. Street Address	b. City/Town	c. Zip Code
Latitude and Longitude:	42.1690	-71.3400
	d. Latitude	e. Longitude
Map 28	41	
f. Assessors Map/Plat Number	g. Parcel /Lot Number	

2. Applicant:

Jim	McKay	
a. First Name	b. Last Name	
Town of Millis		
c. Organization		
900 Main St		
d. Street Address		
Millis	MA	02054
e. City/Town	f. State	g. Zip Code
508-376-7040		
h. Phone Number	i. Fax Number	j. Email Address

3. Property owner (required if different from applicant):  Check if more than one owner

_____	_____	
a. First Name	b. Last Name	
_____		
c. Organization		
_____		
d. Street Address		
_____	_____	_____
e. City/Town	f. State	g. Zip Code
_____	_____	_____
h. Phone Number	i. Fax Number	j. Email address

4. Representative (if any):

Gregory	Avenia	
a. First Name	b. Last Name	
Kleinfelder		
c. Company		
1 Beacon Street		
d. Street Address		
Boston	MA	02108
e. City/Town	f. State	g. Zip Code
617 497 7800	GAvenia@kleinfelder.com	
h. Phone Number	i. Fax Number	j. Email address

5. Total WPA Fee Paid (from NOI Wetland Fee Transmittal Form):

\$0		
a. Total Fee Paid	b. State Fee Paid	c. City/Town Fee Paid



Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

# WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:
MassDEP File Number
Document Transaction Number
Millis
City/Town

## A. General Information (continued)

6. General Project Description:

Implementation of PFAS groundwater treatment facility

7a. Project Type Checklist: (Limited Project Types see Section A. 7b.)

- 1.  Single Family Home
- 2.  Residential Subdivision
- 3.  Commercial/Industrial
- 4.  Dock/Pier
- 5.  Utilities
- 6.  Coastal engineering Structure
- 7.  Agriculture (e.g., cranberries, forestry)
- 8.  Transportation
- 9.  Other

7b. Is any portion of the proposed activity eligible to be treated as a limited project (including Ecological Restoration Limited Project) subject to 310 CMR 10.24 (coastal) or 310 CMR 10.53 (inland)?

1.  Yes  No If yes, describe which limited project applies to this project. (See 310 CMR 10.24 and 10.53 for a complete list and description of limited project types)

2. Limited Project Type

If the proposed activity is eligible to be treated as an Ecological Restoration Limited Project (310 CMR10.24(8), 310 CMR 10.53(4)), complete and attach Appendix A: Ecological Restoration Limited Project Checklist and Signed Certification.

8. Property recorded at the Registry of Deeds for:

a. County	b. Certificate # (if registered land)
	Deed not found, plan 377 of 1973
c. Book	d. Page Number

## B. Buffer Zone & Resource Area Impacts (temporary & permanent)

- 1.  Buffer Zone Only – Check if the project is located only in the Buffer Zone of a Bordering Vegetated Wetland, Inland Bank, or Coastal Resource Area.
- 2.  Inland Resource Areas (see 310 CMR 10.54-10.58; if not applicable, go to Section B.3, Coastal Resource Areas).

Check all that apply below. Attach narrative and any supporting documentation describing how the project will meet all performance standards for each of the resource areas altered, including standards requiring consideration of alternative project design or location.





Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

**WPA Form 3 – Notice of Intent**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number

Millis

City/Town

**B. Buffer Zone & Resource Area Impacts (temporary & permanent) (cont'd)**

For all projects affecting other Resource Areas, please attach a narrative explaining how the resource area was delineated.

Resource Area	Size of Proposed Alteration	Proposed Replacement (if any)
a. <input type="checkbox"/> Bank	1. linear feet	2. linear feet
b. <input type="checkbox"/> Bordering Vegetated Wetland	1. square feet	2. square feet
c. <input type="checkbox"/> Land Under Waterbodies and Waterways	1. square feet	2. square feet
	3. cubic yards dredged	

Resource Area	Size of Proposed Alteration	Proposed Replacement (if any)
d. <input checked="" type="checkbox"/> Bordering Land Subject to Flooding	1661	N/A
	1. square feet	2. square feet
	0	4. cubic feet replaced
e. <input type="checkbox"/> Isolated Land Subject to Flooding	1. square feet	
	2. cubic feet of flood storage lost	3. cubic feet replaced
f. <input type="checkbox"/> Riverfront Area	1. Name of Waterway (if available) - <b>specify coastal or inland</b>	
	2. Width of Riverfront Area (check one):	

- 25 ft. - Designated Densely Developed Areas only
- 100 ft. - New agricultural projects only
- 200 ft. - All other projects

3. Total area of Riverfront Area on the site of the proposed project: \_\_\_\_\_ square feet

4. Proposed alteration of the Riverfront Area:

a. total square feet	b. square feet within 100 ft.	c. square feet between 100 ft. and 200 ft.
----------------------	-------------------------------	--

5. Has an alternatives analysis been done and is it attached to this NOI?  Yes  No

6. Was the lot where the activity is proposed created prior to August 1, 1996?  Yes  No

3.  Coastal Resource Areas: (See 310 CMR 10.25-10.35)

**Note:** for coastal riverfront areas, please complete **Section B.2.f.** above.



Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

**WPA Form 3 – Notice of Intent**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number

Millis

City/Town

**B. Buffer Zone & Resource Area Impacts (temporary & permanent) (cont'd)**

Check all that apply below. Attach narrative and supporting documentation describing how the project will meet all performance standards for each of the resource areas altered, including standards requiring consideration of alternative project design or location.

Online Users:  
Include your document transaction number (provided on your receipt page) with all supplementary information you submit to the Department.

<u>Resource Area</u>	<u>Size of Proposed Alteration</u>	<u>Proposed Replacement (if any)</u>
a. <input type="checkbox"/> Designated Port Areas	Indicate size under Land Under the Ocean, below	
b. <input type="checkbox"/> Land Under the Ocean	_____	
	1. square feet	
	_____	
	2. cubic yards dredged	
c. <input type="checkbox"/> Barrier Beach	Indicate size under Coastal Beaches and/or Coastal Dunes below	
d. <input type="checkbox"/> Coastal Beaches	_____	_____
	1. square feet	2. cubic yards beach nourishment
e. <input type="checkbox"/> Coastal Dunes	_____	_____
	1. square feet	2. cubic yards dune nourishment

	<u>Size of Proposed Alteration</u>	<u>Proposed Replacement (if any)</u>
f. <input type="checkbox"/> Coastal Banks	_____	
	1. linear feet	
g. <input type="checkbox"/> Rocky Intertidal Shores	_____	
	1. square feet	
h. <input type="checkbox"/> Salt Marshes	_____	_____
	1. square feet	2. sq ft restoration, rehab., creation
i. <input type="checkbox"/> Land Under Salt Ponds	_____	
	1. square feet	
	_____	
	2. cubic yards dredged	
j. <input type="checkbox"/> Land Containing Shellfish	_____	
	1. square feet	
k. <input type="checkbox"/> Fish Runs	Indicate size under Coastal Banks, inland Bank, Land Under the Ocean, and/or inland Land Under Waterbodies and Waterways, above	
	_____	
	1. cubic yards dredged	
l. <input type="checkbox"/> Land Subject to Coastal Storm Flowage	_____	
	1. square feet	

4.  Restoration/Enhancement  
If the project is for the purpose of restoring or enhancing a wetland resource area in addition to the square footage that has been entered in Section B.2.b or B.3.h above, please enter the additional amount here.

\_\_\_\_\_ a. square feet of BVW \_\_\_\_\_ b. square feet of Salt Marsh

5.  Project Involves Stream Crossings

\_\_\_\_\_ a. number of new stream crossings \_\_\_\_\_ b. number of replacement stream crossings



Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

# WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number

Millis

City/Town

## C. Other Applicable Standards and Requirements

- This is a proposal for an Ecological Restoration Limited Project. Skip Section C and complete Appendix A: Ecological Restoration Limited Project Checklists – Required Actions (310 CMR 10.11).

### Streamlined Massachusetts Endangered Species Act/Wetlands Protection Act Review

1. Is any portion of the proposed project located in **Estimated Habitat of Rare Wildlife** as indicated on the most recent Estimated Habitat Map of State-Listed Rare Wetland Wildlife published by the Natural Heritage and Endangered Species Program (NHESP)? To view habitat maps, see the *Massachusetts Natural Heritage Atlas* or go to [http://maps.massgis.state.ma.us/PRI\\_EST\\_HAB/viewer.htm](http://maps.massgis.state.ma.us/PRI_EST_HAB/viewer.htm).

- a.  Yes  No **If yes, include proof of mailing or hand delivery of NOI to:**

**Natural Heritage and Endangered Species Program  
Division of Fisheries and Wildlife  
1 Rabbit Hill Road  
Westborough, MA 01581**

GIS viewer checked  
9/28/23

If yes, the project is also subject to Massachusetts Endangered Species Act (MESA) review (321 CMR 10.18). To qualify for a streamlined, 30-day, MESA/Wetlands Protection Act review, please complete Section C.1.c, and include requested materials with this Notice of Intent (NOI); *OR* complete Section C.2.f, if applicable. *If MESA supplemental information is not included with the NOI, by completing Section 1 of this form, the NHESP will require a separate MESA filing which may take up to 90 days to review (unless noted exceptions in Section 2 apply, see below).*

- c. Submit Supplemental Information for Endangered Species Review\*

1.  Percentage/acreage of property to be altered:
  - (a) within wetland Resource Area \_\_\_\_\_ percentage/acreage
  - (b) outside Resource Area \_\_\_\_\_ percentage/acreage


2.  Assessor's Map or right-of-way plan of site

2.  Project plans for entire project site, including wetland resource areas and areas outside of wetlands jurisdiction, showing existing and proposed conditions, existing and proposed tree/vegetation clearing line, and clearly demarcated limits of work \*\*
  - (a)  Project description (including description of impacts outside of wetland resource area & buffer zone)
  - (b)  Photographs representative of the site

\* Some projects **not** in Estimated Habitat may be located in Priority Habitat, and require NHESP review (see <https://www.mass.gov/endangered-species-act-mesa-regulatory-review>).

Priority Habitat includes habitat for state-listed plants and strictly upland species not protected by the Wetlands Protection Act.

\*\* MESA projects may not be segmented (321 CMR 10.16). The applicant must disclose full development plans even if such plans are not required as part of the Notice of Intent process.



**Massachusetts Department of Environmental Protection**  
 Bureau of Resource Protection - Wetlands  
**WPA Form 3 – Notice of Intent**  
 Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

---

MassDEP File Number

---

Document Transaction Number

---

Millis

---

City/Town

**C. Other Applicable Standards and Requirements (cont'd)**

(c)  MESA filing fee (fee information available at <https://www.mass.gov/how-to/how-to-file-for-a-mesa-project-review>).  
 Make check payable to “Commonwealth of Massachusetts - NHESP” and **mail to NHESP** at above address

*Projects altering 10 or more acres of land, also submit:*

- (d)  Vegetation cover type map of site
- (e)  Project plans showing Priority & Estimated Habitat boundaries
- (f) OR Check One of the Following

1.  Project is exempt from MESA review.  
 Attach applicant letter indicating which MESA exemption applies. (See 321 CMR 10.14, <https://www.mass.gov/service-details/exemptions-from-review-for-projectsactivities-in-priority-habitat>; the NOI must still be sent to NHESP if the project is within estimated habitat pursuant to 310 CMR 10.37 and 10.59.)

2.  Separate MESA review ongoing. a. NHESP Tracking # \_\_\_\_\_ b. Date submitted to NHESP \_\_\_\_\_

3.  Separate MESA review completed.  
 Include copy of NHESP “no Take” determination or valid Conservation & Management Permit with approved plan.

3. For coastal projects only, is any portion of the proposed project located below the mean high water line or in a fish run?
- a.  Not applicable – project is in inland resource area only      b.  Yes     No

If yes, include proof of mailing, hand delivery, or electronic delivery of NOI to either:

South Shore - Cohasset to Rhode Island border, and the Cape & Islands:

North Shore - Hull to New Hampshire border:

Division of Marine Fisheries -  
 Southeast Marine Fisheries Station  
 Attn: Environmental Reviewer  
 836 South Rodney French Blvd.  
 New Bedford, MA 02744  
 Email: [dmf.envreview-south@mass.gov](mailto:dmf.envreview-south@mass.gov)

Division of Marine Fisheries -  
 North Shore Office  
 Attn: Environmental Reviewer  
 30 Emerson Avenue  
 Gloucester, MA 01930  
 Email: [dmf.envreview-north@mass.gov](mailto:dmf.envreview-north@mass.gov)

Also if yes, the project may require a Chapter 91 license. For coastal towns in the Northeast Region, please contact MassDEP’s Boston Office. For coastal towns in the Southeast Region, please contact MassDEP’s Southeast Regional Office.

- c.  Is this an aquaculture project?      d.  Yes     No

If yes, include a copy of the Division of Marine Fisheries Certification Letter (M.G.L. c. 130, § 57).



Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

**WPA Form 3 – Notice of Intent**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number

Millis

City/Town

**Online Users:**  
Include your document transaction number (provided on your receipt page) with all supplementary information you submit to the Department.

**C. Other Applicable Standards and Requirements (cont'd)**

- 4. Is any portion of the proposed project within an Area of Critical Environmental Concern (ACEC)?  
 a.  Yes  No      If yes, provide name of ACEC (see instructions to WPA Form 3 or MassDEP Website for ACEC locations). **Note:** electronic filers click on Website.  
 b. ACEC

---

- 5. Is any portion of the proposed project within an area designated as an Outstanding Resource Water (ORW) as designated in the Massachusetts Surface Water Quality Standards, 314 CMR 4.00?  
 a.  Yes  No
- 6. Is any portion of the site subject to a Wetlands Restriction Order under the Inland Wetlands Restriction Act (M.G.L. c. 131, § 40A) or the Coastal Wetlands Restriction Act (M.G.L. c. 130, § 105)?  
 a.  Yes  No
- 7. Is this project subject to provisions of the MassDEP Stormwater Management Standards?  
 a.  Yes. Attach a copy of the Stormwater Report as required by the Stormwater Management Standards per 310 CMR 10.05(6)(k)-(q) and check if:
  - 1.  Applying for Low Impact Development (LID) site design credits (as described in Stormwater Management Handbook Vol. 2, Chapter 3)
  - 2.  A portion of the site constitutes redevelopment
  - 3.  Proprietary BMPs are included in the Stormwater Management System.
 b.  No. Check why the project is exempt:
  - 1.  Single-family house
  - 2.  Emergency road repair
  - 3.  Small Residential Subdivision (less than or equal to 4 single-family houses or less than or equal to 4 units in multi-family housing project) with no discharge to Critical Areas.

**D. Additional Information**

- This is a proposal for an Ecological Restoration Limited Project. Skip Section D and complete Appendix A: Ecological Restoration Notice of Intent – Minimum Required Documents (310 CMR 10.12).

Applicants must include the following with this Notice of Intent (NOI). See instructions for details.

**Online Users:** Attach the document transaction number (provided on your receipt page) for any of the following information you submit to the Department.

- 1.  USGS or other map of the area (along with a narrative description, if necessary) containing sufficient information for the Conservation Commission and the Department to locate the site. (Electronic filers may omit this item.)
- 2.  Plans identifying the location of proposed activities (including activities proposed to serve as a Bordering Vegetated Wetland [BVW] replication area or other mitigating measure) relative to the boundaries of each affected resource area.



Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

# WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:
MassDEP File Number
Document Transaction Number
Millis
City/Town

## D. Additional Information (cont'd)

3.  Identify the method for BVW and other resource area boundary delineations (MassDEP BVW Field Data Form(s), Determination of Applicability, Order of Resource Area Delineation, etc.), and attach documentation of the methodology.

4.  List the titles and dates for all plans and other materials submitted with this NOI.

Millis, Massachusetts Well 3 Water Treatment Facility	
a. Plan Title	
Kleinfelder	Gregory Avenia, P.E.
b. Prepared By	c. Signed and Stamped by
10/27/2023	1"=20'
d. Final Revision Date	e. Scale
f. Additional Plan or Document Title	g. Date

5.  If there is more than one property owner, please attach a list of these property owners not listed on this form.

6.  Attach proof of mailing for Natural Heritage and Endangered Species Program, if needed.

7.  Attach proof of mailing for Massachusetts Division of Marine Fisheries, if needed.

8.  Attach NOI Wetland Fee Transmittal Form

9.  Attach Stormwater Report, if needed.

## E. Fees

1.  Fee Exempt: No filing fee shall be assessed for projects of any city, town, county, or district of the Commonwealth, federally recognized Indian tribe housing authority, municipal housing authority, or the Massachusetts Bay Transportation Authority.

Applicants must submit the following information (in addition to pages 1 and 2 of the NOI Wetland Fee Transmittal Form) to confirm fee payment:

2. Municipal Check Number	3. Check date
4. State Check Number	5. Check date
6. Payor name on check: First Name	7. Payor name on check: Last Name





Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands

Provided by MassDEP:

# WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

MassDEP File Number

Document Transaction Number

Millis

City/Town

## F. Signatures and Submittal Requirements

I hereby certify under the penalties of perjury that the foregoing Notice of Intent and accompanying plans, documents, and supporting data are true and complete to the best of my knowledge. I understand that the Conservation Commission will place notification of this Notice in a local newspaper at the expense of the applicant in accordance with the wetlands regulations, 310 CMR 10.05(5)(a).

I further certify under penalties of perjury that all abutters were notified of this application, pursuant to the requirements of M.G.L. c. 131, § 40. Notice must be made by Certificate of Mailing or in writing by hand delivery or certified mail (return receipt requested) to all abutters within 100 feet of the property line of the project location.

*James G. McKinley*  
1. Signature of Applicant

10/30/2023  
2. Date

3. Signature of Property Owner (if different)  
*[Signature]* Gregory Avenia, PE (Kleinfelder)

4. Date  
10/30/2023

5. Signature of Representative (if any)

6. Date

### For Conservation Commission:

Two copies of the completed Notice of Intent (Form 3), including supporting plans and documents, two copies of the NOI Wetland Fee Transmittal Form, and the city/town fee payment, to the Conservation Commission by certified mail or hand delivery.

### For MassDEP:

One copy of the completed Notice of Intent (Form 3), including supporting plans and documents, one copy of the NOI Wetland Fee Transmittal Form, and a **copy** of the state fee payment to the MassDEP Regional Office (see Instructions) by certified mail or hand delivery.

### Other:


If the applicant has checked the "yes" box in any part of Section C, Item 3, above, refer to that section and the Instructions for additional submittal requirements.

The original and copies must be sent simultaneously. Failure by the applicant to send copies in a timely manner may result in dismissal of the Notice of Intent.



**Massachusetts Department of Environmental Protection**  
 Bureau of Resource Protection - Wetlands  
**NOI Wetland Fee Transmittal Form**  
 Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

**Important:** When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



**A. Applicant Information**

1. Location of Project:

Village St	Millis
a. Street Address	b. City/Town
_____	_____
c. Check number	d. Fee amount
_____	_____

2. Applicant Mailing Address:

Jim	McKay	
a. First Name	b. Last Name	
_____	_____	
Town of Millis		
c. Organization		
900 Main Street		
d. Mailing Address		
_____		
Millis	MA	02054
e. City/Town	f. State	g. Zip Code
_____	_____	_____
508-376-7040		
h. Phone Number	i. Fax Number	j. Email Address
_____	_____	_____

3. Property Owner (if different):

_____	_____	
a. First Name	b. Last Name	
_____	_____	
_____		
c. Organization		
_____		
_____		
d. Mailing Address		
_____		
_____	_____	_____
e. City/Town	f. State	g. Zip Code
_____	_____	_____
_____	_____	_____
h. Phone Number	i. Fax Number	j. Email Address

**B. Fees**

Fee should be calculated using the following process & worksheet. **Please see Instructions before filling out worksheet.**

**Step 1/Type of Activity:** Describe each type of activity that will occur in wetland resource area and buffer zone.

**Step 2/Number of Activities:** Identify the number of each type of activity.

**Step 3/Individual Activity Fee:** Identify each activity fee from the six project categories listed in the instructions.

**Step 4/Subtotal Activity Fee:** Multiply the number of activities (identified in Step 2) times the fee per category (identified in Step 3) to reach a subtotal fee amount. Note: If any of these activities are in a Riverfront Area in addition to another Resource Area or the Buffer Zone, the fee per activity should be multiplied by 1.5 and then added to the subtotal amount.

**Step 5/Total Project Fee:** Determine the total project fee by adding the subtotal amounts from Step 4.

**Step 6/Fee Payments:** To calculate the state share of the fee, divide the total fee in half and subtract \$12.50. To calculate the city/town share of the fee, divide the total fee in half and add \$12.50.

To calculate filing fees, refer to the category fee list and examples in the instructions for filling out WPA Form 3 (Notice of Intent).





**Massachusetts Department of Environmental Protection**  
 Bureau of Resource Protection - Wetlands  
**NOI Wetland Fee Transmittal Form**  
 Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

**B. Fees** (continued)

Step 1/Type of Activity	Step 2/Number of Activities	Step 3/Individual Activity Fee	Step 4/Subtotal Activity Fee
No fee, Town Project	1	0	0
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

**Step 5/Total Project Fee:** \_\_\_\_\_

**Step 6/Fee Payments:**

Total Project Fee:	\$0
State share of filing Fee:	\$0
City/Town share of filing Fee:	\$0

a. Total Fee from Step 5  
 b. 1/2 Total Fee **less** \$12.50  
 c. 1/2 Total Fee **plus** \$12.50

**C. Submittal Requirements**

- a.) Complete pages 1 and 2 and send with a check or money order for the state share of the fee, payable to the Commonwealth of Massachusetts.

Department of Environmental Protection  
 Box 4062  
 Boston, MA 02211

- b.) **To the Conservation Commission:** Send the Notice of Intent or Abbreviated Notice of Intent; a **copy** of this form; and the city/town fee payment.

**To MassDEP Regional Office** (see Instructions): Send a copy of the Notice of Intent or Abbreviated Notice of Intent; a **copy** of this form; and a **copy** of the state fee payment. (E-filers of Notices of Intent may submit these electronically.)



# Village Street Property Map

Millis, MA

1 inch = 300 Feet



www.cai-tech.com


October 27, 2023



Water-poly	Right of Way	Property Hook	Private Road
Wet Areas	Utility	Right of Way	Property Line
WaterLines	PropNotPar	Wetland	Public Road

Data shown on this map is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this map.





# Village Street USGS Map


Millis, MA

1 inch = 2000 Feet



[www.cai-tech.com](http://www.cai-tech.com)

October 27, 2023



Data shown on this map is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this map.





# Village Street Aerial Map

Millis, MA

1 inch = 300 Feet



[www.cai-tech.com](http://www.cai-tech.com)

October 27, 2023



Data shown on this map is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this map.





# Village Street NHESP Map

Millis, MA

1 inch = 300 Feet



www.cai-tech.com

October 27, 2023



	Water-poly		Right of Way		Property Hook		Private Road
	Wet Areas		Utility		Right of Way		Property Line
	WaterLines		PropNotPar		Wetland		Public Road

Data shown on this map is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this map.





# Village Street Flood Map

Millis, MA

1 inch = 300 Feet



www.cai-tech.com

October 27, 2023



1% Annual Chance Flood Hazard	Right of Way	Wetland
0.2% Annual Chance Flood Hazard	Utility	Private Road
Water-poly	PropNotPar	Property Line
Wet Areas	Property Hook	Public Road
WaterLines	Right of Way	

Data shown on this map is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this map.



**ATTACHMENT A**  
**NOI Narrative**

---



## **Attachment A – Notice of Intent Narrative**

This Notice of Intent (NOI) is filed pursuant to the Massachusetts Wetlands Protection Act (WPA) (MGL Chapter 131, Section 40) and its implementing regulations (310 CMR 10.00). This narrative presents wetland resource areas associated with the Project area, a description of the proposed work, proposed mitigation measures, and how the Project meets the performance standards of the WPA regulations. Refer to the accompanying Project plans included as Attachment D for a plan layout and details of the Project components.

### **Introduction**

The Town of Millis (Millis) operates a water system with six overburden groundwater wells and four treatment plants, serving approximately 8,600 residential customers. The Massachusetts Department of Environmental Protection (MassDEP) recently adopted a drinking water standard limiting six per- and poly-fluoroalkyl substances (PFAS) levels to no more than 20 nanograms per liter (ng/L), and as part of the new drinking water regulations, all public water systems are required to sample for PFAS levels.

Since the discovery of PFAS in Millis' water supply, the Town has worked to improve water quality through the design and construction of the PFAS treatment upgrades at the D'Angelis Water Treatment Facility (WTF). However, the remaining Wells 3 through 6 also have PFAS detections for compounds subject to regulations from Massachusetts Department of Environmental Protection (DEP) and some of which may also be subject to the proposed regulations by United States Environmental Protection Agency (EPA). While the new D'Angelis WTF will be capable of meeting average daily demands on its own, the Town must install additional PFAS treatment to meet peak demands.

The Town of Millis Department of Public Works (DPW) has conducted pilot testing and a thorough site investigation to obtain the most effective treatment for removing PFAS from drinking water with the least environmental impact. The DPW proposes to construct a new building housing granular activated carbon (GAC) filters, chemical feed equipment, and associated infrastructure at the existing Well 3 site for treatment of public drinking water.

Portions of the land near the Project area contain Bordering Vegetated Wetlands (BVW), a resource area subject to the jurisdiction of the WPA. Proposed work for the Project will occur only in the 100-foot Buffer Zone of the BVW. The Project meets or exceeds all performance standards for Buffer Zone under the WPA. Portions of the Project area are also shown on the Flood Insurance Rate Map (FIRM) as located within Zone AE (100-year floodplain, regulated as Bordering Land Subject to Flooding [BLSF]). However, within the Project area, base flood elevation (BFE) is mapped as 123 feet NAVD88 and recently the DPW obtained survey information collect by a Professional Land Surveyor (PLS) registered in the Commonwealth of Massachusetts that shows a small portion of the limit of disturbance for this Project is located within BFE and/or inside of regulated floodplain areas. More information on the position of the project footprint relative to Zone AE is provided below.

### **Site Description**

The Project area is located on one parcel of land off Birch Street in Millis, Massachusetts. The Project area currently contains wooded land and existing water system infrastructure. Wooded area borders the site to the south, the gravel driveway and wetland to the west, existing Well 3 infrastructure to the north, and a grassed field to the east past a loop in the gravel driveway. Refer to Figure 1 for a Tax Parcel map of the Project area, and Figures 2 and 3 for a USGS map and aerial map of the Project area.

According to the most recently available data provided by the Massachusetts Natural Heritage and Endangered Species Program (NHESP), no Priority Habitats for Rare Species or Estimated Habitats for Rare Wildlife have been mapped in the vicinity of the Project area. No certified or potential vernal pools have been mapped in the Project area (Figure 4). The Project Area is not located within or near an Area of





Critical Environmental Concern (ACEC). According to the Massachusetts Department of Environmental Protection (DEP), the Project area is not located within an Outstanding Resource Water area, but it is designated as a Zone I and Zone II Wellhead Protection Area. According to the Natural Resources Conservation Service (NRCS) soil survey, soils in the Project area are mapped as Swansea and Hinkley.

## **Wetland Resource Areas**

Wetland Resource areas in or near the Project Area were identified and delineated by environmental scientists from Basbanes Wetland Consulting on July 19, 2023, in accordance with methods developed by the DEP and U.S. Army Corps of Engineers. Resource areas are shown on the accompanying Project plans and wetland data forms are included in Attachment C. One BVW was delineated in the Project Area, as was Land Subject to Flooding. BVW is defined under the WPA Regulations (310 CMR 10.00) as: “freshwater wetlands that border on creeks, rivers, streams, ponds, and lakes.” The boundary of a BVW is determined by the presence of 50 percent or more of wetland indicator plants and saturated or inundated conditions. Bordering Land Subject to Flooding is defined under the WPA Regulations (310 CMR 10.00) as: “an area which floods from a rise in a bordering waterway or water body. Such areas are likely to be significant to flood control and storm damage prevention.”

The delineated wetland is located west of the Project Area. Dominant vegetation within the wetland includes beech, maple, oak, pine, buckthorn, highbush and lowbush blueberry, Canada mayflower, fern cinnamon, fern wood, partridgeberry, sphagnum moss, starflower, and poison ivy. The wetland was delineated with flags 1A through 23A (See Project plans). The wetland is regulated as BVW under the WPA.

A 100-foot Buffer Zone extends horizontally outward from the BVW boundary described above, as defined in 310 CMR 10.02(2)(b). The Buffer Zone is not considered a resource area under the WPA, but areas within the Buffer Zone are under the jurisdiction of the issuing authority. Millis has an additional wetlands protection bylaw preventing structures within the inner 50-foot Buffer Zone from the edge of a wetland resource. Within the Project area, the Buffer Zone of the wetland contains an existing gravel drive, paved parking, existing infrastructure, and proposed utilities.

The FIRM for the area indicates a portion of the Project is within as within Zone AE, regulated as BLSF, with an elevation of 123 feet NAVD88. A civil survey conducted within the Project area in September 2022 and July 2023 shows that all Project impacts occur outside of this area, except for demolition activities associated with the existing chemical feed building that proposed to maintain or lower existing grades. Proposed demolition activities encompass 1,661 square feet of Bordering Land Subject to Flooding. The project is subject to regulation under the WPA.

## **Proposed Activities**

The project includes installation of four (4) 10,000 lb. GAC filters at the Well 3 site, which will require additional building footprint to accommodate the infrastructure. The DPW proposes to construct a new building on the site, adjacent to existing Well 3 infrastructure. A small existing chemical treatment building on the parcel will be demolished and the new building housing the PFAS treatment system and chemicals will be built nearby, on land outside the 100-year floodplain. The existing gravel access road leading to the new building will be reconstructed to provide safe access for vehicles and maintenance personnel. The proposed building footprint is located outside the 100-foot Buffer Zone of a BVW, however portions of construction activities are located within the Millis 100-foot and 50-foot Buffer Zones.

### **Activities Within Buffer Zone**

Project work within the Buffer Zone will include demolition of an existing water infrastructure building, as well as reconstruction of existing gravel driveway areas, installation of new paved driveways, and installation of a new building with associated parking and utilities. All work will take place outside of the



BVW, but demolition of the chemical feed building, restoration of the gravel access drive, and installing pavement, will be within the 100-foot Buffer Zone as shown on the attached plans in Attachment D. Within the area of disturbance associated with the demolition of the chemical feed building, approximately 2,140 square feet of wetland buffer restoration is proposed in a previously developed location.

Sedimentation barriers will be placed around the perimeter of the work area to prevent migration of excavated material from entering the BVW.

## **Mitigation**

The new building has been sited to reduce impacts to wetland resources to the greatest extent practicable by locating it outside of the buffer zone and restoring 2,140 square feet of buffer zone that was previously developed. An erosion and sedimentation control program will be implemented to minimize temporary impacts to wetland resource areas during the construction phase of the project. The program incorporates Best Management Practices (BMPs) specified in guidelines developed by the DEP and the U.S. Environmental Protection Agency (EPA).

Proper implementation of the erosion and sedimentation control program will:

- › Minimize exposed soil areas through sequencing and temporary stabilization;
- › Place structures to manage stormwater runoff and erosion; and
- › Establish a permanent vegetative cover or other forms of stabilization as soon as practicable.

## **Non-Structural Practices**

Non-structural practices to be used during construction include temporary stabilization, temporary seeding, permanent seeding, pavement sweeping, and dust control. These practices will be initiated as soon as practicable in appropriate areas within the Project Area.

### **Temporary Stabilization**

Any areas of exposed soil or stockpiles that will remain inactive for more than 14 days will be surrounded by erosion control devices and covered with polyurethane sheeting.

### **Temporary Seeding**

If conditions allow, a temporary vegetative cover will be established on areas of exposed soils (including stockpiles) that remain unstabilized for a period of more than 60 days. The seeded surfaces will be covered with a layer of straw mulch or bonded fiber matrix as described above. The seed mix shall include a blend of rapid germinating grasses that are indigenous to eastern Massachusetts.

### **Permanent Seeding**

Upon completion of final grading, any areas not covered by pavement, other forms of stabilization, or other methods of landscaping will be seeded with a native seed mix. The mix will be applied at a rate specified by the manufacturer and will be covered with mulch or bonded fiber matrix as described above.

### **Pavement Sweeping**

The interior roads (once paved) and the portion of the street that fronts the Project Area shall be swept as needed during construction. The sweeping program will remove sediment and other contaminants directly from paved surfaces before their release into stormwater runoff. Pavement sweeping has been demonstrated to be an effective initial treatment for reducing pollutant loading into stormwater. A street sweeper shall be kept at the site or at a nearby location to facilitate this practice. Once construction has been completed, sweeping at the Project Area will occur as required under the Operation and Maintenance Plan.

### **Dust Control**



The erosion and sediment control program includes provisions to minimize the generation of dust during dry and windy conditions. When necessary, larger areas of exposed soil will be wetted to prevent wind borne transport of fine-grained sediment. Enough water shall be applied to wet the upper 0.5 inches of soil. The water will be applied as a fine spray to prevent erosion. A water truck will be kept on the property (or at a nearby location) to facilitate this practice.

## **Structural Practices**

Structural erosion and sedimentation controls to be used on the Project Area include barriers, catch basin inlet protection, and dewatering filters.

### **Erosion Control Barriers**

Prior to any ground disturbance, an approved erosion control barrier will be installed at the downgradient limit of work. As construction progresses, additional barriers will be installed around the base of stockpiles and other erosion prone areas. The barriers will be entrenched into the substrate to prevent underflow.

If sediment has accumulated to a depth which impairs proper functioning of the barrier, it will be removed by hand or by machinery operating upslope of the barriers. This material will be either reused in the Project Area or disposed of at a suitable offsite location. Any damaged sections of the barrier will be repaired or replaced immediately upon discovery.

### **Dewatering Filters**

If necessary, sediment laden water that collects in trenches or excavated areas will be pumped into straw bale basins or filter bags. The basins will consist of a ring of staked straw bales overlain by non-woven geotextile filter fabric and crushed stone. Discharge water will be pumped into the basin and allowed to drain through the fabric onto relatively flat stabilized surfaces. Dewatering filter bags may be used in place of straw bale basins. The bags will be placed on relatively flat terrain, free of brush and stumps, to avoid ruptures and punctures. A maximum of one six-inch discharge hose will be allowed per filter bag. To help prevent punctures, geotextile fabric will be placed beneath the filter bag when used in wooded locations. Unattended filter bags will be encircled with a straw bale and silt fence barrier.

All dewatering structures will be placed as far away from wetland resources as possible. Filter bags used during construction will be bundled and removed for proper disposal.

## **Stormwater Management**

Runoff generated from impervious surfaces will be collected and managed in accordance with the DEP Stormwater policies in significant improvement to existing conditions. The proposed Project will improve existing conditions within the Project Area by constructing a stormwater management system that includes measures to provide groundwater recharge, attenuate peak flows and provide water quality treatment. Full details on the system (including supporting calculations) are included in the accompanying Stormwater Management Report (Attachment E).

Compliance with the 10 stormwater management standards cited in Section 310 CMR 10.05(6)(k) of the WPA Regulations is evaluated in the Regulatory Compliance section of the Stormwater Management Report.

## **Regulatory Compliance**

As demonstrated below, the Project work fully complies with and exceeds applicable performance standards contained in the WPA for work in the 100-foot Buffer Zone to BVW and the Bordering Land Subject to Flooding. Compliance with each of the applicable performance standards is described in more detail below.

The Buffer Zone is not a resource area and, therefore, work within a Buffer Zone is not governed by specific regulatory performance standards. In general, work within a Buffer Zone is permissible when said work



has been designed, or can be conditioned, such that there will be no impact on the downgradient wetland resource area(s) being buffered. As stated in 310 CMR 10.53(1) of the WPA Regulations:

*For work in Buffer Zone subject to review under 310 CMR 10.02(2)(b)3., the Issuing Authority shall impose conditions to protect the interests of the Act identified for the adjacent Resource Area... The issuing authority may consider the characteristics of the Buffer Zone, such as the presence of steep slopes, that may increase the potential for adverse impacts on Resource Areas. Conditions may include limitations on the scope and location of work in the Buffer Zone as necessary to avoid alteration of Resource Areas. The Issuing Authority may require erosion and sedimentation controls during construction, a clear limit of work, and the preservation of natural vegetation adjacent to the Resource Area and/or other measures commensurate with the scope and location of work with the Buffer Zone to protect the interests of the Act.*

The Project has been designed to address these considerations. Measures have been incorporated into the Project design to ensure that work will be done in a manner that prevents impacts to downgradient wetland resources. A clear limit of work will be identified, and erosion and sedimentation control areas will be installed in the Project Area. Temporary disturbance in vegetated areas of Buffer Zone will be restored in place and seeded with a native seed mix.

The Applicant respectfully requests that the Millis Conservation Commission find these measures adequately protective of the interests identified in the WPA and issue an Order of Conditions approving the work described in this NOI and shown on the accompanying plans.



**ATTACHMENT B**  
**Abutter Information**

---





# Parcel 0028-0046 Abutter's List

Millis, MA

1 inch = 275 Feet




October 13, 2023




Precision Mapping Geospatial Solutions

[www.cai-tech.com](http://www.cai-tech.com)



Data shown on this map is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this map.





# 300 foot Abutters List Report

Millis, MA  
October 13, 2023

CERTIFIED COPY by the TOWN OF MILLIS

Assessors Office Liz Road

## Subject Property:

Parcel Number: 0028-0046-0000  
CAMA Number: 0028-0046-0000  
Property Address: VILLAGE ST

Mailing Address: TOWN OF MILLIS  
900 MAIN ST  
MILLIS, MA 02054

10113123

## Abutters:

Parcel Number: 0025-0088-0000 CAMA Number: 0025-0088-0000 Property Address: MAIN ST TRACT 417	Mailing Address: U S ARMY CORPS OF ENGINEERS REAL ESTATE DIVISION 518 HARTFORD AVE E UXBRIDGE, MA 01569
Parcel Number: 0027-0052-0000 CAMA Number: 0027-0052-000B Property Address: 30 LARCH RD	Mailing Address: FIN FUR & FEATHER CLUB INC P O BOX 272 MILLIS, MA 02054
Parcel Number: 0028-0014-0000 CAMA Number: 0028-0014-0000 Property Address: 34 VILLAGE ST	Mailing Address: LYDIA GEORGE CHRIS TSINIDIS 34 VILLAGE ST MILLIS, MA 02054
Parcel Number: 0028-0015-0000 CAMA Number: 0028-0015-0000 Property Address: 30 VILLAGE ST	Mailing Address: KERRI A BARRETT THOMAS J BARRETT SR. 30 VILLAGE ST MILLIS, MA 02054
Parcel Number: 0028-0015-0000 CAMA Number: 0028-0015-000H Property Address: 30 VILLAGE ST	Mailing Address: KERRI A BARRETT THOMAS J BARRETT SR. 30 VILLAGE ST MILLIS, MA 02054
Parcel Number: 0028-0016-0000 CAMA Number: 0028-0016-0000 Property Address: 36 VILLAGE ST	Mailing Address: HAMPTON LYNDA L & SCOTT D 36 VILLAGE ST MILLIS, MA 02054
Parcel Number: 0028-0019-0000 CAMA Number: 0028-0019-0000 Property Address: 40 VILLAGE ST	Mailing Address: NGUYEN BICH-VAN 40 VILLAGE ST MILLIS, MA 02054
Parcel Number: 0028-0020-0000 CAMA Number: 0028-0020-0000 Property Address: 42 VILLAGE ST	Mailing Address: ANTHONY DELGROSSO LATOYA THOMPSON 42 VILLAGE ST MILLIS, MA 02054
Parcel Number: 0025-0088-0000 CAMA Number: 0028-0021-0000 Property Address: MAIN ST TRACT 417	Mailing Address: U S ARMY CORPS OF ENGINEERS REAL ESTATE DIVISION 518 HARTFORD AVE E UXBRIDGE, MA 01569
Parcel Number: 0028-0022-0000 CAMA Number: 0028-0022-0000 Property Address: MAIN ST TRACT 412	Mailing Address: U S ARMY CORPS OF ENGINEERS REAL ESTATE DIVISION 518 HARTFORD AVE E UXBRIDGE, MA 01569



www.cai-tech.com

10/13/2023

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.

Page 1 of 2



# 300 foot Abutters List Report

Millis, MA  
October 13, 2023

CERTIFIED COPY by the TOWN OF MILLIS

Parcel Number: 0028-0023-0000  
CAMA Number: 0028-0023-0000  
Property Address: VILLAGE ST TR 428

Mailing Address: U S ARMY CORPS OF ENGINEERS  
REAL ESTATE DIVISION  
518 HARTFORD AVE E  
UXBRIDGE, MA 01569

Parcel Number: 0028-0024-0000  
CAMA Number: 0028-0024-0000  
Property Address: MAIN ST TRACT 412

Mailing Address: U S ARMY CORPS OF ENGINEERS  
REAL ESTATE DIVISION  
518 HARTFORD AVE E  
UXBRIDGE, MA 01569

Parcel Number: 0028-0025-0000  
CAMA Number: 0028-0025-0000  
Property Address: 44 VILLAGE ST

Mailing Address: Contact Town For Info

Parcel Number: 0028-0039-0000  
CAMA Number: 0028-0039-0000  
Property Address: BIRCH ST

Mailing Address: WHELAN KENNETH J  
27 BIRCH ST  
MILLIS, MA 02054

Parcel Number: 0028-0041-0000  
CAMA Number: 0028-0041-0000  
Property Address: 68 VILLAGE ST

Mailing Address: WHELAN BRENDA J TRUSTEE WHELAN  
BRENDA J REALTY TRUST  
68 VILLAGE ST  
MILLIS, MA 02054

Parcel Number: 0028-0047-0000  
CAMA Number: 0028-0047-0000  
Property Address: 46 VILLAGE ST

Mailing Address: MOGAN JOHN J JR & MARCIA A C/O  
MOGAN JOHN J JR  
46 VILLAGE ST  
MILLIS, MA 02054



www.cai-tech.com

10/13/2023

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.

Page 2 of 2





**ATTACHMENT C**  
**Wetland Data Forms**

---

## BASBANES WETLAND CONSULTING

39 Hardy St.  
Dunstable, MA 01827

Delineation Report  
21167-1A Millis Well 3  
Village St, Millis, MA

July 20 2023

The following is a report on the delineation of the wetland resource areas at the Millis Well 3 off Village St, Millis, MA. The delineation was done on July 19 2023. The jurisdictional wetland resource area present on site may include: 310 CMR 10.55 Bordering Vegetated Wetland and 310 CMR 10.57 Land Subject to Flooding.

### Delineation Method

A wetland delineation is done by visual survey of topography, evidence of hydrology, and identification of plant species. A determination is made for each plant species as to their indicator status as referenced in the “National List of Plant Species that Occur in Wetlands”, published by the Fish and Wildlife Service. The boundary of the wetland is then determined to be where 50% or more of the vegetation community consists of wetland indicator species with a status of FAC or wetter. Where there is a dominance of wetland plants species, evidence of hydrology is looked for, i.e. water stained leaves, drainage patterns, morphological adaptations, and hydric soils. Typically, hydric soils are determined by digging or augering a pit 20” deep and observing the horizons for color and features. Determinations are made referencing “Field Indicators for Identifying Hydric Soils in New England” and color matched to the Munsell Soil Color Charts.

### Flagging Series

The wetland resource area is delineated by the flagging series 1A-23A. The wetland delineated is a bordering vegetated wetland that is part of an extensive wetland system associated with the Charles River. The Charles River is well over 1500 l.f. from the subject property. The wetland boundary is fairly well defined though the area is relatively flat. The transition of wetland plants of hydric to upland plants as well as non-hydric soils to hydric soils is narrow.

### Vegetation

The vegetation along the delineated area consists of the following dominant species:

Beech, <i>Fagus grand folia</i>	FACU
Maple, Red <i>Acer rubrum</i>	FAC
Maple, Sugar <i>Acer saccharum</i>	FACU
Oak, Red <i>Quercus rubra</i>	FACU
Pine, White <i>Pinus strobus</i>	FACU
Buckthorn, European <i>Rhamnus frangula</i>	FAC
Highbush Blueberry <i>Vaccinium corymbosum</i>	FACW
Lowbush Blueberry <i>Vaccinium angustifolium</i>	FACU
Canada Mayflower <i>Maianthemum canadense</i>	FACU
Fern Cinnamon <i>Osmunda cinnamomea</i>	FACW
Fern Wood <i>Dryopteris spinulosa</i>	
Partridgeberry <i>Mitchella repens</i>	FACU
Sphagnum moss <i>Sphagnum spp.</i>	OBL
Starflower <i>Trientalis borealis</i>	FAC
Poison Ivy <i>Toxicodendron radicans</i>	FAC

**Soils**

As referenced to the NRCS Soil Survey, the soils on the subject property are Swansea in the wetland and Hinckley in the upland area. Swansea soils consist of nearly level, deep (5+ ft.), very poorly drained organic soils in depressions and low flat areas of uplands and glacial outwash plains and terraces. Hinckley soils consist of deep, excessively drained soils on terraces, outwash plains, deltas, kames and eskers.

The typical soil profiles observed were:

SP upland

O <1"  
A 0" – 8" 10YR 2/2  
B 8"-18" 10YR 4/4

SP hydric

O <1"  
A 0" – 10" 10YR 2/1  
B 10"-18" 10YR 4/2 redox

**Indicators of hydrology**

Along with the presence of hydric soil conditions other indicators of hydrology were observed. Those indicators include: water-stained leaves, areas void of vegetation, sphagnum moss.

**Rare Species**

Under MESA and 310 CMR 10:59 Estimated Habitats of Rare Wildlife, any work proposed, regardless of wetlands, within an Estimated or Priority habitat shall be reviewed by the NHESP as well as the Conservation Commission. The site is not located within an Estimated or Priority Habitat

**Vernal Pools**

There are no certified vernal pools on the property per the most recently NHESP map.

**FEMA**

As referenced to the FEMA flood data maps, a portion of the site is located within a regulatory flood zone AE.

If you have any questions please do not hesitate to contact me. Thank you.

Sincerely,



Leah D. Basbanes, M.A.  
Wetland Consultant/Biologist

The wetland resource areas were delineated/reviewed in the keeping with the Massachusetts Wetland Protection Act and were done so to the best of our abilities. Considering all the variables (seasonal growth form of vegetation, soils conditions, topography, weather, etc.) involved in such an effort, please be advised that despite the best effort, no wetland delineation is considered definitive until verified and approved by the final issuing authority.

**BORDERING VEGETATED WETLAND DETERMINATION FORM**

Project/Site: 21167-1A Millis Well 3 City/Town: Millis Sampling Date: July 19 2023

Applicant/Owner: Town of Millis Sampling Point or Zone: non wet SP1

Investigator(s): Leah Basbanes Latitude / Longitude: 42.16812, -71.34051

Soil Map Unit Name: Hinckley NWI or DEP Classification: WS1

Are climatic/hydrologic conditions on the site typical for this time of year? Yes  No  (If no, explain in Remarks)

Are Vegetation , Soil , or Hydrology  significantly disturbed? (If yes, explain in Remarks)

Are Vegetation , Soil , or Hydrology  naturally problematic? (If yes, explain in Remarks)

**SUMMARY OF FINDINGS – Attach site map and photograph log showing sampling locations, transects, etc.**

Wetland vegetation criterion met?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	<b>Is the Sampled Area within a Wetland?</b> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Hydic Soils criterion met?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
Wetlands hydrology present?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
Remarks, Photo Details, Flagging, etc.:			

**HYDROLOGY**

<b>Field Observations:</b>		
Surface Water Present?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> Depth (inches) _____
Water Table Present?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> Depth (inches) _____
Saturation Present (including capillary fringe)?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> Depth (inches) _____
<b>Wetland Hydrology Indicators</b>		
<b>Reliable Indicators of Wetlands Hydrology</b> <input type="checkbox"/> Water-stained leaves <input type="checkbox"/> Evidence of aquatic fauna <input type="checkbox"/> Iron deposits <input type="checkbox"/> Algal mats or crusts <input type="checkbox"/> Oxidized rhizospheres/pore linings <input type="checkbox"/> Thin muck surfaces <input type="checkbox"/> Plants with air-filled tissue (aerenchyma) <input type="checkbox"/> Plants with polymorphic leaves <input type="checkbox"/> Plants with floating leaves <input type="checkbox"/> Hydrogen sulfide odor	<b>Indicators that can be Reliable with Proper Interpretation</b> <input type="checkbox"/> Hydrological records <input type="checkbox"/> Free water in a soil test hole <input type="checkbox"/> Saturated soil <input type="checkbox"/> Water marks <input type="checkbox"/> Moss trim lines  <input type="checkbox"/> Presence of reduced iron <input type="checkbox"/> Woody plants with adventitious roots <input type="checkbox"/> Trees with shallow root systems <input type="checkbox"/> Woody plants with enlarged lenticels	<b>Indicators of the Influence of Water</b> <input type="checkbox"/> Direct observation of inundation <input type="checkbox"/> Drainage patterns <input type="checkbox"/> Drift lines <input type="checkbox"/> Scoured areas <input type="checkbox"/> Sediment deposits  <input type="checkbox"/> Surface soil cracks <input type="checkbox"/> Sparsely vegetated concave surface <input type="checkbox"/> Microtopographic relief <input type="checkbox"/> Geographic position (depression, toe of slope, fringing lowland)
Remarks (describe recorded data from stream gauge, monitoring well, aerial photos, previous inspections, if available):		

This form is only for BVW delineations. Other wetland resource areas may be present and should be delineated according to the applicable regulatory provisions.

**VEGETATION** – Use both common and scientific names of plants.

<u>Tree Stratum</u>		Plot size <u>30'</u>			
Common name	Scientific name	Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
1. Red Oak	Quercus rubra	FACU	30.0	Yes	No
2. White Pine	Pinus strobus	FACU	30.0	Yes	No
3. Red Maple	Acer rubrum	FAC	20.0	Yes	Yes
4. sugar maple	Acer saccharum	FACU	10.0	No	No
5.					
6.					
7.					
8.					
9.					
			<u>90.0</u> = Total Cover		
<u>Shrub/Sapling Stratum</u>		Plot size <u>15'</u>			
Common name	Scientific name	Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
1. European Buckthorn	Rhamnus frangula	FAC	40.0	Yes	Yes
2. Lowbush Blueberry	Vaccinium angustifolia	FACU	30.0	Yes	No
3.					
4.					
5.					
6.					
7.					
8.					
9.					
			<u>70.0</u> = Total Cover		
<u>Herb Stratum</u>		Plot size <u>5'</u>			
Common name	Scientific name	Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
1. Starflower	Trientalis borealis	FAC	10.0	No	No
2. Partridgeberry	Mitchella repens	FACU	20.0	Yes	No
3.					
4.					
5.					
6.					
7.					
8.					
9.					
10.					
11.					
12.					
			<u>30.0</u> = Total Cover		

**VEGETATION** – continued.

<u>Woody Vine Stratum</u>	Plot size _____				
Common name	Scientific name	Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
1.					
2.					
3.					
4.					
0.0 = Total Cover					

<b>Rapid Test:</b> Do all dominant species have an indicator status of OBL or FACW? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>			
<b>Dominance Test:</b>	Number of dominant species 6	Number of dominant species that are wetland indicator plants 2	Do wetland indicator plants make up ≥ 50% of dominant plant species? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<b>Prevalence Index:</b>	Total % Cover (all strata)	Multiply by:	Result
	OBL species	X 1	= 0.00
	FACW species	X 2	= 0.00
	FAC species	X 3	= 0.00
	FACU species	X 4	= 0.00
	UPL species	X 5	= 0.00
	Column Totals	(A) 0	(B) 0
Prevalence Index		B/A = <b>0.00</b>	Is the Prevalence Index ≤ 3.0? Yes <input type="checkbox"/> No <input type="checkbox"/>
<b>Wetland vegetation criterion met?</b> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>			

**Definitions of Vegetation Strata**

- Tree - Woody plants 3 in. (7.62 cm) or more in diameter at breast height (DBH), regardless of height
- Shrub / Sapling - Woody plants less than 3 in. (7.62 cm) DBH and greater than or equal to 3.3 ft. (1 m) tall
- Herb - All herbaceous (non-woody plants, regardless of size, and woody plants less than 3.3 ft. (1 m) tall
- Woody vines - All woody vines greater than 3.3 ft. (1 m) in height

Cover Ranges	
Range	Midpoint
1-5 %	3.0 %
6-15 %	10.5 %
15-25 %	20.5 %
26-50 %	38.0 %
51-75 %	63.0 %
76-95 %	85.5 %
96-100 %	98.0 %



**BORDERING VEGETATED WETLAND DETERMINATION FORM**

Project/Site: 21167-1A Millis Well 3 City/Town: Millis Sampling Date: July 19 2023  
 Applicant/Owner: Town of Millis Sampling Point or Zone: wet SP2  
 Investigator(s): Leah Basbanes Latitude / Longitude: 42.16809, -71.34063  
 Soil Map Unit Name: Swansea NWI or DEP Classification: WS1

Are climatic/hydrologic conditions on the site typical for this time of year? Yes  No  (If no, explain in Remarks)  
 Are Vegetation , Soil , or Hydrology  significantly disturbed? (If yes, explain in Remarks)  
 Are Vegetation , Soil , or Hydrology  naturally problematic? (If yes, explain in Remarks)

**SUMMARY OF FINDINGS – Attach site map and photograph log showing sampling locations, transects, etc.**

Wetland vegetation criterion met?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	<b>Is the Sampled Area within a Wetland?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Hydic Soils criterion met?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
Wetlands hydrology present?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
Remarks, Photo Details, Flagging, etc.:			

**HYDROLOGY**

<b>Field Observations:</b>		
Surface Water Present?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> Depth (inches) _____
Water Table Present?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> Depth (inches) _____
Saturation Present (including capillary fringe)?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/> Depth (inches) <u>10.00</u>
<b>Wetland Hydrology Indicators</b>		
Reliable Indicators of Wetlands Hydrology <input checked="" type="checkbox"/> Water-stained leaves <input type="checkbox"/> Evidence of aquatic fauna <input type="checkbox"/> Iron deposits <input type="checkbox"/> Algal mats or crusts <input type="checkbox"/> Oxidized rhizospheres/pore linings <input type="checkbox"/> Thin muck surfaces <input type="checkbox"/> Plants with air-filled tissue (aerenchyma) <input type="checkbox"/> Plants with polymorphic leaves <input type="checkbox"/> Plants with floating leaves <input type="checkbox"/> Hydrogen sulfide odor	Indicators that can be Reliable with Proper Interpretation <input type="checkbox"/> Hydrological records <input type="checkbox"/> Free water in a soil test hole <input checked="" type="checkbox"/> Saturated soil <input type="checkbox"/> Water marks <input type="checkbox"/> Moss trim lines <input type="checkbox"/> Presence of reduced iron <input type="checkbox"/> Woody plants with adventitious roots <input checked="" type="checkbox"/> Trees with shallow root systems <input type="checkbox"/> Woody plants with enlarged lenticels	Indicators of the Influence of Water <input type="checkbox"/> Direct observation of inundation <input type="checkbox"/> Drainage patterns <input type="checkbox"/> Drift lines <input type="checkbox"/> Scoured areas <input type="checkbox"/> Sediment deposits <input type="checkbox"/> Surface soil cracks <input type="checkbox"/> Sparsely vegetated concave surface <input type="checkbox"/> Microtopographic relief <input type="checkbox"/> Geographic position (depression, toe of slope, fringing lowland)
Remarks (describe recorded data from stream gauge, monitoring well, aerial photos, previous inspections, if available):		

This form is only for BVW delineations. Other wetland resource areas may be present and should be delineated according to the applicable regulatory provisions.



**VEGETATION** – Use both common and scientific names of plants.

<u>Tree Stratum</u>		Plot size <u>30'</u>			
		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name				
1. Red Oak	Quercus rubra	FACU	25.0	Yes	No
2. White Pine	Pinus strobus	FACU	25.0	Yes	No
3. Red Maple	Acer rubrum	FAC	25.0	Yes	Yes
4.					
5.					
6.					
7.					
8.					
9.					
		<u>75.0</u> = Total Cover			
<u>Shrub/Sapling Stratum</u>		Plot size <u>15'</u>			
		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name				
1. European Buckthorn	Rhamnus frangula	FAC	20.0	Yes	Yes
2. Highbush Blueberry	Vaccinium corymbosum	FACW	30.0	Yes	Yes
3. Red Maple	Acer rubrum	FAC	10.0	No	No
4.					
5.					
6.					
7.					
8.					
9.					
		<u>60.0</u> = Total Cover			
<u>Herb Stratum</u>		Plot size <u>5'</u>			
		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name				
1. Cinnamon Fern	Osmunda cinnamomea	FACW	40.0	Yes	Yes
2. Starflower	Trientalis borealis	FAC	10.0	Yes	Yes
3.					
4.					
5.					
6.					
7.					
8.					
9.					
10.					
11.					
12.					
		<u>50.0</u> = Total Cover			

**VEGETATION – continued.**

<u>Woody Vine Stratum</u>		Plot size _____		Indicator	Absolute	Dominant?	Wetland
Common name		Scientific name		Status	% Cover	(yes/no)	Indicator?
							(yes/no)
1.							
2.							
3.							
4.							
				0.0 = Total Cover			

<b>Rapid Test:</b> Do all dominant species have an indicator status of OBL or FACW?			Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<b>Dominance Test:</b>	Number of dominant species	Number of dominant species that are wetland indicator plants	Do wetland indicator plants make up ≥ 50% of dominant plant species?
	7	5	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
<b>Prevalence Index:</b>		Total % Cover (all strata)	Multiply by:
	OBL species		X 1 = 0.00
	FACW species		X 2 = 0.00
	FAC species		X 3 = 0.00
	FACU species		X 4 = 0.00
	UPL species		X 5 = 0.00
	Column Totals	(A) 0	(B) 0
Prevalence Index		B/A = <b>0.00</b>	
			Is the Prevalence Index ≤ 3.0?
			Yes <input type="checkbox"/> No <input type="checkbox"/>
<b>Wetland vegetation criterion met?</b>		Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	

**Definitions of Vegetation Strata**

- Tree - Woody plants 3 in. (7.62 cm) or more in diameter at breast height (DBH), regardless of height
- Shrub / Sapling - Woody plants less than 3 in. (7.62 cm) DBH and greater than or equal to 3.3 ft. (1 m) tall
- Herb - All herbaceous (non-woody plants, regardless of size, and woody plants less than 3.3 ft. (1 m) tall
- Woody vines - All woody vines greater than 3.3 ft. (1 m) in height

Cover Ranges	
Range	Midpoint
1-5 %	3.0 %
6-15 %	10.5 %
15-25 %	20.5 %
26-50 %	38.0 %
51-75 %	63.0 %
76-95 %	85.5 %
96-100 %	98.0 %



**BORDERING VEGETATED WETLAND DETERMINATION FORM**

Project/Site: 21167-1A Millis Well 3 City/Town: Millis Sampling Date: July 19 2023  
 Applicant/Owner: Town of Millis Sampling Point or Zone: wet SP5  
 Investigator(s): Leah Basbanes Latitude / Longitude: 42.16917, -7134025  
 Soil Map Unit Name: Swansea NWI or DEP Classification: WS1

Are climatic/hydrologic conditions on the site typical for this time of year? Yes  No  (If no, explain in Remarks)  
 Are Vegetation , Soil , or Hydrology  significantly disturbed? (If yes, explain in Remarks)  
 Are Vegetation , Soil , or Hydrology  naturally problematic? (If yes, explain in Remarks)

**SUMMARY OF FINDINGS – Attach site map and photograph log showing sampling locations, transects, etc.**

Wetland vegetation criterion met?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	<b>Is the Sampled Area within a Wetland?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Hydic Soils criterion met?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
Wetlands hydrology present?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
Remarks, Photo Details, Flagging, etc.:			

**HYDROLOGY**

<b>Field Observations:</b>		
Surface Water Present?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> Depth (inches) _____
Water Table Present?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> Depth (inches) _____
Saturation Present (including capillary fringe)?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/> Depth (inches) <u>9.00</u>
<b>Wetland Hydrology Indicators</b>		
Reliable Indicators of Wetlands Hydrology <input checked="" type="checkbox"/> Water-stained leaves <input type="checkbox"/> Evidence of aquatic fauna <input type="checkbox"/> Iron deposits <input type="checkbox"/> Algal mats or crusts <input type="checkbox"/> Oxidized rhizospheres/pore linings <input type="checkbox"/> Thin muck surfaces <input type="checkbox"/> Plants with air-filled tissue (aerenchyma) <input type="checkbox"/> Plants with polymorphic leaves <input type="checkbox"/> Plants with floating leaves <input type="checkbox"/> Hydrogen sulfide odor	Indicators that can be Reliable with Proper Interpretation <input type="checkbox"/> Hydrological records <input type="checkbox"/> Free water in a soil test hole <input checked="" type="checkbox"/> Saturated soil <input type="checkbox"/> Water marks <input type="checkbox"/> Moss trim lines <input type="checkbox"/> Presence of reduced iron <input type="checkbox"/> Woody plants with adventitious roots <input checked="" type="checkbox"/> Trees with shallow root systems <input type="checkbox"/> Woody plants with enlarged lenticels	Indicators of the Influence of Water <input type="checkbox"/> Direct observation of inundation <input type="checkbox"/> Drainage patterns <input type="checkbox"/> Drift lines <input type="checkbox"/> Scoured areas <input type="checkbox"/> Sediment deposits <input type="checkbox"/> Surface soil cracks <input type="checkbox"/> Sparsely vegetated concave surface <input type="checkbox"/> Microtopographic relief <input type="checkbox"/> Geographic position (depression, toe of slope, fringing lowland)
Remarks (describe recorded data from stream gauge, monitoring well, aerial photos, previous inspections, if available):		

This form is only for BVW delineations. Other wetland resource areas may be present and should be delineated according to the applicable regulatory provisions.

**VEGETATION** – Use both common and scientific names of plants.

<u>Tree Stratum</u>		Plot size <u>30'</u>			
		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name		Scientific name			
1.	Red Oak	Quercus rubra	FACU	20.0	Yes No
2.	White Pine	Pinus strobus	FACU	20.0	Yes No
3.	Red Maple	Acer rubrum	FAC	40.0	Yes Yes
4.					
5.					
6.					
7.					
8.					
9.					
<u>80.0</u> = Total Cover					
<u>Shrub/Sapling Stratum</u>		Plot size <u>15'</u>			
		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name		Scientific name			
1.	European Buckthorn	Rhamnus frangula	FAC	40.0	Yes Yes
2.	Highbush Blueberry	Vaccinium corymbosum	FACW	30.0	Yes Yes
3.	Red Maple	Acer rubrum	FAC	10.0	No No
4.					
5.					
6.					
7.					
8.					
9.					
<u>80.0</u> = Total Cover					
<u>Herb Stratum</u>		Plot size <u>5'</u>			
		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name		Scientific name			
1.	Cinnamon Fern	Osmunda cinnamomea	FACW	40.0	Yes Yes
2.					
3.					
4.					
5.					
6.					
7.					
8.					
9.					
10.					
11.					
12.					
<u>40.0</u> = Total Cover					

**VEGETATION – continued.**

<u>Woody Vine Stratum</u>		Plot size _____		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name		Scientific name					
1.	Poison Ivy	Toxicodendron radicans		FAC	30.0	Yes	Yes
2.							
3.							
4.							
				30.0 = Total Cover			

<b>Rapid Test:</b> Do all dominant species have an indicator status of OBL or FACW?			Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<b>Dominance Test:</b>	Number of dominant species	Number of dominant species that are wetland indicator plants	Do wetland indicator plants make up ≥ 50% of dominant plant species? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	7	5	
<b>Prevalence Index:</b>		Total % Cover (all strata)	Multiply by: Result
	OBL species		X 1 = 0.00
	FACW species		X 2 = 0.00
	FAC species		X 3 = 0.00
	FACU species		X 4 = 0.00
	UPL species		X 5 = 0.00
	Column Totals	(A) 0	(B) 0
Prevalence Index		B/A = <b>0.00</b>	Is the Prevalence Index ≤ 3.0? Yes <input type="checkbox"/> No <input type="checkbox"/>
<b>Wetland vegetation criterion met?</b>			Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

**Definitions of Vegetation Strata**

- Tree - Woody plants 3 in. (7.62 cm) or more in diameter at breast height (DBH), regardless of height
- Shrub / Sapling - Woody plants less than 3 in. (7.62 cm) DBH and greater than or equal to 3.3 ft. (1 m) tall
- Herb - All herbaceous (non-woody plants, regardless of size, and woody plants less than 3.3 ft. (1 m) tall
- Woody vines - All woody vines greater than 3.3 ft. (1 m) in height

Cover Ranges	
Range	Midpoint
1-5 %	3.0 %
6-15 %	10.5 %
15-25 %	20.5 %
26-50 %	38.0 %
51-75 %	63.0 %
76-95 %	85.5 %
96-100 %	98.0 %





**ATTACHMENT D**  
**Project Plans**

---



# TOWN OF MILLIS, MASSACHUSETTS WELL 3 WATER TREATMENT FACILITY

PERMIT REVIEW SET

OCTOBER 2023

## SELECT BOARD

CRAIG SCHULTZE	CHAIR
ELLEN ROSENFELD	VICE CHAIR
ERIN UNDERHILL	CLERK

## DEPARTMENT OF PUBLIC WORKS


JAMES F. McKAY	DIRECTOR
----------------	----------

## WATER AND SEWER DEPARTMENT

RON McKENNEY	SUPERINTENDENT
--------------	----------------



LOCUS PLAN  
SCALE: 1" = 500'



SITE PLAN  
SCALE: 1" = 40'




NOT FOR  
CONSTRUCTION







CAD FILE: G:\clients\Millis MA\2023\967\02A Well 3 PFAS Final Design & Permitting\08 - Drawings\01-D-01.dwg LAYOUT: D-1



1. SOUTHWEST CORNER OF CHEMICAL FEED BUILDING FACING NORTHEAST




2. NORTH SIDE OF BUILDING FACING SOUTHEAST



3. SOUTHWEST CORNER OF BUILDING FACING NORTHEAST



4. NORTHEAST CORNER OF FACILITY OUTSIDE OF FENCE FACING SOUTHWEST



5. EAST SIDE OF BUILDING FACING WEST



6. NORTHEAST CORNER OF BUILDING FACING SOUTHWEST



7. EAST SIDE OF PIPING BETWEEN CHEMICAL FEED BUILDING AND WELL PUMP HOUSE FACING WEST





8. NORTHEAST CORNER OF FACILITY OUTSIDE OF FENCE FACING SOUTHWEST

NOTES  
 1) CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL DEMOLISHED BUILDINGS MATERIALS, INCLUDING CONCRETE SLAB AND FOUNDATION. FOR DETAILS REGARDING DEMOLITION OF EXISTING BUILDINGS SEE SPECIFICATION SECTIONS 02050 AND 02221.  
 2) CONTRACTOR TO DECOMMISSION EXISTING ELECTRICAL AND WATER SERVICES AS SHOWN ON SHEET C-102 PRIOR TO BUILDING DEMOLITION.



One Beacon Street, Suite 8100  
 Boston, MA 02108  
 Phone: 617-497-7800  
 www.kleinfelder.com

REVISIONS				
REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**DEMOLITION PLAN**  
 TOWN OF MILLIS, MASSACHUSETTS  
 WELL 3 WATER TREATMENT FACILITY



TOWN OF MILLIS  
 DEPARTMENT OF PUBLIC WORKS  
 900 MAIN ST, MILLIS, MA 02054

**PERMIT REVIEW SET**

PROJECT NO.	20233667.002A
ISSUE DATE	OCT. 2023
CURRENT REVISION	-
DESIGNED BY	MPS
DRAWN BY	MPS
CHECKED BY	GAA
APPROVED BY	GAA

D-001

**NOT FOR CONSTRUCTION**








Signed By: \_\_\_\_\_ # 12345

REVISIONS

REV	DESCRIPTION	DSN	CHK	DATE

SCALE VERIFICATION



THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

0 20 40  
SCALE: 1" = 20' SCALE IN FEET

ORIGINAL DRAWING SIZE IS 22 x 34

SITE PREPARATION PLAN

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054

PERMIT REVIEW SET

PROJECT NO.	20233667.002A
ISSUE DATE	OCT. 2023
CURRENT REVISION	DRAFT
DESIGNED BY	MPS
DRAWN BY	MPS
CHECKED BY	GAA
APPROVED BY	GAA

C-102

**NOT FOR CONSTRUCTION**



OWNER:  
N/F TOWN OF MILLIS  
PARCEL 0028-0046-0000  
(NO DEED REF. FOUND)  
(PLAN NO. 377 OF 1973)

Now or Formerly  
DOMENIC J. TIBERI et ux  
PARCEL 0028-0025-0000  
(Book 33903 Page 340)  
(Plan No. 519 of 1989, Lot 1)

Now or Formerly  
WHELAN REALTY  
TRUST  
L 0028-0041-0000  
(11874 Page 403)  
(Plan No. 142 of 1997, Lot 3)

CAD FILE: G:\clients\Millis MA\2023\3667\002A\_Well 3 PRAS Final Design & Permitting\08\_Drawing\C-101 C-102\_Site Layout.dwg LAYOUT: C-102 PLOTTED: 11/1/2023 12:34 PM BY: mckenna.nobels





One Beacon Street, Suite 8100  
 Boston, MA 02108  
 Phone: 617-497-7800  
 www.kleinfelder.com

Signed By: ----- # 12345

REVISIONS				
REV	DESCRIPTION	DSN DWN	CHK APP	DATE

**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY


SCALE: 1" = 20' SCALE IN FEET  
 ORIGINAL DRAWING SIZE IS 22 x 34

**OVERALL SITE PLAN**  
 TOWN OF MILLIS, MASSACHUSETTS  
 WELL 3 WATER TREATMENT FACILITY



TOWN OF MILLIS  
 DEPARTMENT OF PUBLIC WORKS  
 900 MAIN ST, MILLIS, MA 02054

<b>PERMIT REVIEW SET</b>	
PROJECT NO. 20233667.002A	<b>C-103</b>
ISSUE DATE OCT. 2023	
CURRENT REVISION DRAFT	
DESIGNED BY MPS	
DRAWN BY MPS	
CHECKED BY GAA	
APPROVED BY GAA SHEET	6 of 60



**NOT FOR CONSTRUCTION**

CAD FILE: G:\clients\Millis MA\2023\967 002A Well 3 PRAS Final Design & Permitting\08 - Drawings\C-101 C-102 Site Layout.dwg LAYOUT: C-103  
 PLOTTED: 11/11/2023, 12:34 PM BY: mdelmar@kbts































Signed By: \_\_\_\_\_ # \_\_\_\_\_

REVISIONS

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**A SECTION**  
M-003 SCALE: 1" = 4'



**B SECTION**  
M-003 SCALE: 1" = 4'

NOTES:  
1. CONTRACTOR SHALL INSTALL PIPE SUPPORTS IN ACCORDANCE WITH SPECIFICATION SECTION 15056.

SCALE VERIFICATION

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



SCALE: 1" = 4' SCALE IN FEET

ORIGINAL DRAWING SIZE IS 22 x 34

PROCESS SECTION

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054

PERMIT REVIEW SET

PROJECT NO. 20233667.002A  
ISSUE DATE OCT. 2023  
CURRENT REVISION -  
DESIGNED BY TB  
DRAWN BY PF  
CHECKED BY TB  
APPROVED BY ---- SHEET

M-004


**NOT FOR CONSTRUCTION**

CAD FILE: G:\clients\Millis MA\20233667.002A Well 3 PFAS Final Design & Permitting\08 - Drawings\M-003 - Interior Piping.dwg LAYOUT: M-004 PLOTTED: 11/1/2023 12:36 PM BY: mdelmona.noberts


Signed By: \_\_\_\_\_ # \_\_\_\_\_

REVISIONS

REV	DESCRIPTION	DSN DWN	CHK APP	DATE




**WELL 3 DEMOLITION PLAN**  
SCALE: NTS




**DEMOLITION PLAN**  
SCALE: 1" = 4'

- NOTES
- EXISTING CHEMICAL FEED ITEMS TO BE REMOVED AND DISPOSED OF INCLUDED BUT ARE NOT LIMITED TO LEVEL PROBES, A CHEMICAL FEED CONTROL PANEL, A FOUR FUNCTION VALVE DRAIN, PVC PIPING, A FLOW METER, A CHECK VALVE, A SAMPLE TAP, COPPER PIPING, CHEMICAL INJECTION NOZZLES, TUBING, APPURTENANCES, CONTROL PANELS, A 320 GAL SODIUM HYPOCHLORITE BULK TANK, A 15 GAL SODIUM HYPOCHLORITE DAY TANK, A 300 GAL PE SODIUM HYDROXIDE BULK TANK, AN EXISTING 1000 GAL FRP SODIUM HYDROXIDE BULK TANK, A 32 GAL PE SODIUM FLUORIDE STORAGE CONTAINER, AND A 20 GAL SODIUM FLUORIDE SATURATOR.
  - ALL CHEMICAL FEED PUMPS AND CHEMICAL TRANSFER PUMPS SHALL BE REMOVED AND RETURNED TO OWNER.
  - CONTRACTOR SHALL FIELD VERIFY EXISTING EQUIPMENT.



**WELL 3 MODIFICATION PLAN**  
SCALE: NTS




**MODIFICATION PLAN**  
SCALE: 1" = 4'

- NOTES
- CLEAN, REDEVELOP, AND INSPECT WELLS PRIOR TO INSTALLING PUMPS. REFER TO SPECIFICATION SECTION 02673.
  - DISINFECT WELL SCREEN AND APPURTENANCES PRIOR TO PUMP INSTALLATION. REFER TO SPECIFICATION SECTION 02673.
  - PAINTING FSB TO COAT ALL PIPES IN ACCORDANCE WITH SPECIFICATION SECTION 09960.

SCALE VERIFICATION

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



ORIGINAL DRAWING SIZE IS 22 x 34

**PUMP AND EXISTING BUILDING MODIFICATIONS**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054

PERMIT REVIEW SET

PROJECT NO.	20233667.002A
ISSUE DATE	OCT. 2023
CURRENT REVISION	-
DESIGNED BY	TB
DRAWN BY	MR
CHECKED BY	TB
APPROVED BY	ABB

M-005

















NOT FOR CONSTRUCTION


CAD FILE: G:\clients\Millis\MA\2023\967\002A\_Well 3 PNAS Final Design & Permitting\08 - Drawings\M-005 - Pump Station And Chem Feed Modifications.dwg LAYOUT: M-005 PLOTTED: 11/1/2023, 12:38 PM BY: malenna.roberts





**CHEMICAL PROCESS SCHEMATIC LEGEND**

-  FOUR FUNCTION VALVE
-  BACKPRESSURE VALVE
-  PRESSURE RELIEF VALVE
-  ULTRASONIC LEVEL TRANSDUCER
-  EXPANSION JOINT
-  FLEXIBLE CONNECTION
-  STRAINER
-  PULSATION DAMPENER
-  PRESSURE GAUGE
-  AIR RELEASE VALVE
-  BALL VALVE
-  FOOT VALVE
-  ANTI-SIPHON VALVE
-  SOLENOID VALVE
-  CHECK VALVE
-  UNION



**NOTES:**


1. FLOODED SUCTION REQUIRED.
2. VENT GAS PRIOR TO METERING PUMPS.
3. SLOPE SUCTION LINE DOWN FROM TANK TO METERING PUMP SO GAS CANNOT ENTER PUMP HEAD.
4. ALL BALL VALVES USED FOR SODIUM HYPOCHLORITE SHALL BE 1/4 TURN TRUE UNION VENTED BALL VALVES.
5. BACKPRESSURE VALVES SHALL BE INSTALLED IN SERIES PER MASSDEP GUIDELINES FOR SODIUM HYPOCHLORITE.
6. CAMLOCK FITTINGS SHALL BE FRP.
7. ALL FITTINGS AND ACCESSORIES SHALL BE TRUE UNION.
8. 3/8" FLEXIBLE TUBING SHALL EXTEND AT LEAST 2' FROM START AND END OF 3" RIGID PVC CHEMICAL CONDUIT.
9. CHEMICAL METERING PUMPS SHALL INCLUDE AN INTERLOCK SYSTEM THAT IS HARD WIRED OR USE A TWIST TYPE PLUG AND RECEPTACLE WITH PILOT LIGHT "ON OR ENERGIZED" INDICATOR TO HELP PREVENT OVERFEEDS.
10. MOUNTING PANELS FOR ALL CHEMICAL FEED EQUIPMENT, INCLUDING BUT LIMITED TO PUMPS, PIPING, CALIBRATION COLUMN, SHALL BE CHEMICALLY COMPATIBLE WITH SODIUM HYPOCHLORITE.
11. SODIUM HYPOCHLORITE CHEMICAL FEED SYSTEM SHALL BE INSTALLED ACCORDING TO THE REQUIREMENTS PROVIDED IN THE MASSDEP CHEMICAL FEED SYSTEM CHECKLIST AND/OR ALL MASSDEP GUIDELINES AND REGULATIONS.
12. CONTRACTOR TO SUPPLY INITIAL 300 GALLON FILL OF SODIUM HYPOCHLORITE (12.5%) BUNK TANK PRIOR TO START-UP AND COMMISSIONING.

**SODIUM HYPOCHLORITE CHEMICAL FEED SCHEMATIC**

SCALE: NTS

**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**SODIUM HYPOCHLORITE CHEMICAL FEED SCHEMATIC**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054


**PERMIT REVIEW SET**

PROJECT NO.	20233667.002A
ISSUE DATE	OCT. 2023
CURRENT REVISION	-
DESIGNED BY	AB/GAA
DRAWN BY	MPS
CHECKED BY	TB
APPROVED BY	TB

M-007



NOTE: SEE SCHEMATICS FOR SIZES AND CONFIGURATIONS



CHEMICAL	STORAGE TANK SIZE
SODIUM HYPOCHLORITE (NaOCl)	300 GAL.

NOTE: FOR NaOCl TANK ONLY

**SODIUM HYPOCHLORITE BULK CHEMICAL STORAGE TANK DETAIL**

SCALE: N.T.S.

**NOT FOR CONSTRUCTION**












REVISIONS

REV	DESCRIPTION	DSN DWN	CHK APP	DATE

SCALE VERIFICATION


THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



**BACKWASH TANK**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY







TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054

PERMIT REVIEW SET

PROJECT NO.	20233667.002A
ISSUE DATE	OCT. 2023
CURRENT REVISION	-
DESIGNED BY	ABB
DRAWN BY	MR
CHECKED BY	TB
APPROVED BY	ABB

M-011

**NOT FOR  
CONSTRUCTION**



- NOTES:  
1. CONTRACTOR SHALL FURNISH PIPE SUPPORTS IN ACCORDANCE WITH SPECIFICATION SECTION 02615.  
2. CONTRACTOR SHALL COAT PIPES IN ACCORDANCE WITH SPECIFICATION SECTION 09960.


CAD FILE: G:\clients\Millis MA\2023\3667\002A\_Well 3 PFAS Final Design & Permitting\08 - Drawings\M-011 - BACKWASH RECYCLE.dwg LAYOUT: M-011 Backwash Tank PLOTTED: 11/10/2023 12:37 PM BY: mckenna.roberts



[Click Here to Select Office Address](#)


REVISIONS

REV	DESCRIPTION	DSN DWN	CHK APP	DATE




**CHEMICAL INJECTION TAP DETAIL**

SCALE: N.T.S.



**CHEMICAL FILL STATION DETAIL**


SCALE: N.T.S.



NOTES:  
1. "X" SHALL BE REPLACED BY CORRESPONDING TANK NUMBER.  
2. 25% CAUSTIC SODA SHALL BE REPLACED WITH APPROPRIATE CHEMICAL NAME AND STRENGTH. COORDINATE WITH ENGINEER.


**BULK TANK LABEL DETAIL**

SCALE: N.T.S.



**PRESSURE/SAMPLE TAP DETAIL**


N.T.S.



NOTES:  
1. ONLY ONE FILL LINE SHALL BE INSTALLED FOR SODIUM HYPOCHLORITE AND SODIUM HYDROXIDE EACH.


**CHEMICAL FILL LINE DETAILS**

SCALE: N.T.S.




**CHEMICAL INJECTION GUARD DETAIL**

SCALE: N.T.S.




**CONCRETE PIPE SUPPORT DETAIL**

SCALE: N.T.S.



**CHEMICAL TANK VENT**


SCALE: N.T.S.



NOTES:  
1. FLOOR DRAINS NOT TO BE INSTALLED IN CHEMICAL CONTAINMENT AREAS.

**EMERGENCY SHOWER AND EYE WASH**

SCALE: N.T.S.



**METALLIC SUPPORT**

SCALE: N.T.S.

SCALE VERIFICATION

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**PROCESS DETAILS SHEET 1 OF 2**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054

PERMIT REVIEW SET

PROJECT NO.	20233667.002A
ISSUE DATE	OCT. 2023
CURRENT REVISION	-
DESIGNED BY	ABI/GAA
DRAWN BY	MPS
CHECKED BY	TB
APPROVED BY	TB





M-501

**NOT FOR CONSTRUCTION**

CAD FILE: G:\clients\Millis MA\20233667.002A\_Well 3 PRAS Final Design & Permitting\08\_Drawing\04.dwg - Chem Feed\_receiver.dwg LAYOUT: M-501 - Details 1 PLOTTED: 11/1/2023, 12:37 PM BY: mckenna.roberts

REVISIONS

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



NOTES:  
REFER TO SPECIFICATION SECTION 03420 FOR ADDITIONAL ACCESS HATCH REQUIREMENTS.

**SINGLE GRATE ACCESS HATCH**  
SCALE: N.T.S.

**NOT FOR CONSTRUCTION**

**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**PROCESS DETAILS SHEET 2 OF 2**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054

PERMIT REVIEW SET



PROJECT NO.	20233667.002A
ISSUE DATE	OCT. 2023
CURRENT REVISION	-
DESIGNED BY	AB/GAA
DRAWN BY	MD
CHECKED BY	TB
APPROVED BY	TB

M-502

CAD FILE: G:\clients\Millis MA\20233667.002A\_Well 3 PFAS Final Design & Permitting\08 - Drawings\M-502 - M Details.dwg LAYOUT: M-502 - Details 2 PLOTTED: 11/17/2023 12:37 PM BY: mckenna.roberts



PROJECT PREVIEW & DESCRIPTION



2 AXON - 2  
SCALE:

1 AXON - 1  
SCALE:

ABBREVIATIONS

&	And	GND	Ground	S	South
@	At	GR	Grade	SAFB	Sound Attenuation Fiber Blanket
A/E	Architect / Engineer	GRL	Grille	SC	Sealed Concrete
AB	Anchor Bolt	GRTG	Grating	SCHED	Schedule
AC	Air Conditioning	GSKT	Gasket	SCR	Screw
ACT	Acoustic Ceiling Tile	GT	Grout	SCRN	Screen
ACP	Acoustic Ceiling Panel	GVL	Gravel	SD	Soap Dispenser
AD	Access Door	GWB	Gypsum Wall Board	SECT	Section
ADH	Adhesive			SF	Square Foot
ADJ	Adjustable	HB	Hose Bibb	SLG	Single
ADJC	Adjacent	HC	Handicapped	SHT	Sheet
AFF	Above Finished Floor	HDW	Hardware	SHTHG	Sheathing
AH	Air Handler	HGT	Height	SHV	Shelving
AL	Aluminum	HM	Hollow Metal	SIM	Similar
ALT	Alternate	HMD	Hollow Metal Door	SK	Sink
ANOD	Anodized	HNDRL	Handrail	SM	Sheet Metal
APP	Approximately	HO	Hold Open	SP	Spray Particle Paint
ARCH	Architectural	HORIZ	Horizontal	SPEC	Specifications
ASPH	Asphalt	HP	High Point	SQ	Square
		HR	Hour	SS / ST STL	Stainless Steel
		HVAC	Heat, Ventilation & Air Conditioning	STD	Standard
BD	Board			STL	Steel
BETW	Between	ID	Inside Diameter	STOR	Storage
BIT	Bituminous	IF	Inside Face	STR	Structural
BLDG	Building	IN	Inch or Inches	SUSP	Suspended
BLKG	Blocking	INSUL	Insulation	SVF	Sheet Vinyl Flooring
BM	Beam	INT	Interior	SYM	Symbol
BO	By Others	JAN	Janitor	SYMM	Symmetrical
BOT	Bottom	JNT	Joint	SYS	System
BP	Building Paper			S4S	Surface Four Sides
BR	Brass				
BRZ	Bronze				
BU	Built Up	KD	Knocked Down	T	Treads (Stairs)
		KIT	Kitchen	T&G	Tongue and Groove
C	Course			TB	Toggle Bolt
C	Center Line	L	Left	TBD	To Be Determined
CAB	Cabinet	LF	Linear Foot	TDO	Thermoset Decorative Overlay (Melamine)
CEM	Cement	LG	Length	TEMP	Tempered / Temporary
CG	Corner Guard	LAD	Ladder	TEL	Telephone
CPT	Carpet	LAM	Laminate	TERR	Terrazzo
CHAN	Channel	LAV	Lavatory	THK	Thick
CHBD	Chalkboard	LB	Pound	THRES	Threshold
CHFR	Chamfer	LBL	Label	THRU	Through
CHR	Chrome	LCC	Lead Coated Copper	T&G	Tongue and Groove
CI	Cast Iron	LCH	Left Hand	T.O.	Top Of
CJ	Control Joint	LHR	Left Hand Reverse	TCC	Top Of Concrete
CL	Closet	LIN	Linear	TOM	Top Of Masonry
CLG	Ceiling	LKR	Locker	TOS	Top Of Steel
CLR	Clearance	LNTL	Lintel	TOW	Top Of Wall
CMPST	Composite	LONG	Longitudinal	TRANS	Translucent
CMU	Concrete Masonry Unit	LP	Low Point	TYP	Typical
CNTR	Counter	LT	Light		
COL	Column	LTWT	Lightweight	UL	Underwriters Laboratory
COMP	Compressible	LTG	Lighting	UNFIN	Unfinished
CONC	Concrete	LVR	Louver	UNO / UON	Unless Otherwise Noted
CONN	Connection			UR	Urinal
CONSTR	Construction	MAINT	Maintenance	UV	Unit Ventilator
CONT	Continuous	MANF	Manufacturer		
CONTR	Contractor	MAS	Masonry	VB	Vapor Barrier or Vinyl Base
COP	Copper	MATL	Material	VT / VCT	Vinyl Composition Tile
CORR	Corrosion	MAX	Maximum	VEN	Veneer
CT	Ceramic Tile	MDO	Medium Density Overlay	VER	Verify
CW	Curtain Wall	MECH	Mechanical	VERT	Vertical
		MED	Medium	VEST	Vestibule
Ø	Diameter	MEMB	Membrane	VIF	Verify In Field
DBL	Double	MF	Metal Flashing	VNR	Veneer
DEMO	Demolition	MFR	Manufacturer	VR	Vapor Retarder
DIA	Diameter	MH	Manhole	VWC	Vinyl Wall Covering
DIV	Division	MIN	Minimum		
DIM	Dimension	MIR	Mirror	W	West
DMPF	Dampproofing	MISC	Miscellaneous	WC	Water Closet
DN	Down	MLDG	Molding	WD	Wood
DOP	Door Opening	MO	Masonry Opening	W/	With
DR	Door	MS	Metal Stud	W/O	Without
DS	Downspout	MTD	Mounted	WGL	Wired Glass
DSP	Dry Standpipe	MTL	Metal	WLD	Welded
DTL	Detail	MTR	Mortar	WP	Working Point
DWG	Drawing	MULL	Mullion	WT	Weight
		MVBL	Movable	WTH	Width
				WTRPRF	Waterproofing
				WWF	Welded Wire Fabric
E	East	N	North		
EA	Each	NA	Not Applicable		
EB	Expansion Bolt	NAT	Natural		
EF	Expansion Fan	NIC	Not In Contract		
EJ	Expansion Joint	NO	Number		
EL	Elevation	NOM	Nominal		
ELEC	Electrical	NTS	Not To Scale		
ENGR	Engineer				
ENTR	Entrance	OA	Overall		
EP	Electrical Panel	OC	On Center		
EQ	Equal	OD	Outside Diameter		
EQUIP	Equipment	OF	Outside Face		
ESB	Exterior Soffit Board	OFF	Office		
ESMT	Easement	OH	Overhead		
ETR	Existing to Remain	OPNG	Opening		
EWC	Electric Water Cooler	OPHD	Opposite Hand		
EX / EXST	Existing	OPP	Opposite		
EXC	Excavate				
EXH	Exhaust	P&S	Power & Signal		
EXP	Expansion	PAR	Parallel		
EXT	Exterior	PART	Partition		
		PC	Precast		
FCO	Floor Clean Out	PERF	Perforated		
FD	Floor Drain	PERP	Perpendicular		
FDN	Foundation	PI	Plastic		
FE	Fire Extinguisher	PLAM	Plastic Laminate		
FEV	Fire Extinguisher Cabinet	PM	Pressed Metal		
FF	Fabric Flashing	PNL	Panel		
FGL	Fiberglass	PRMT	Perimeter		
FHC	Fire Hose Cabinet	PT	Pressure Treated		
FHY	Fire Hydrant	PTD	Painted		
FIN	Finished	PVG	Paving		
FL	Floor	PWD	Flywood		
FLUOR	Fluorescent	QT	Quarry Tile		
FOC	Face of Concrete	QTY	Quantity		
FOF	Face of Finish				
FOM	Face of Masonry				
FR	Fire Resistant				
FPRF	Fireproofing	R	Radius or (Stair) Risers		
FRP	Fiber Reinforced Plastic	RAD	Radiator		
FS	Full Size	RCP	Reflected Ceiling Plan		
FT	Foot or Feet	RD	Roof Drain		
FTG	Footing	REC	Recessed		
FTR	Fin Tube Radiation	REF	Reference		
FURN	Furniture	REFR	Refrigerator		
FURR	Furring	REINF	Reinforcing		
FV	Field Verify	REM	Removable		
FWC	Fabric Wall Covering	REQD	Required		
		REQU	Requirements		
G	Gas	RESIL	Resilient		
GA	Gauge	RFI	Rigid Foam Insulation		
GALV	Galvanized	RFG	Roofing		
GB	Grab Bar	RH	Right Hand		
GC	General Contractor	RM	Room		
GEN	Generator	RO	Rough Opening		
GL	Glass	RV	Roof Vent		
GLMU	Glass Masonry Unit				



One Beacon Street, Suite 8100  
Boston, MA 02108  
Phone: 617-497-7800  
www.kleinfelder.com

REVISIONS

REV	DESCRIPTION	DSN DWN	CHK APP	DATE

PLOTTED: 9/26/2023 8:52:23 AM

GENERAL NOTES


- ALL WORK TO BE NEW U.O.N.
- ALL WORK SHALL COMPLY WITH FEDERAL, STATE, AND LOCAL BUILDING REGULATIONS.
- ANY CONFLICTS BETWEEN SITE CONDITIONS AND DRAWINGS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE OWNER AND ARCHITECT/DESIGNER.
- ALL DOORS TO BE A MINIMUM OF 4" FROM NEAREST PERPENDICULAR PARTITION, U.O.N.
- TEMPERED GLASS TO BE USED IN ALL LOCATIONS AS REQUIRED BY MASSACHUSETTS STATE BUILDING CODE - CMR 780.
- REVIEW LAYOUTS FOR PARTITIONS IN FIELD WITH THE OWNER AND ARCHITECT/DESIGNER PRIOR TO START OF CONSTRUCTION.
- PROVIDE FIRE EXTINGUISHERS IN QUANTITIES AND LOCATIONS ON DWGS (MIN 1/6000 SQ-FT & 75' MAX TRAVEL DISTANCE). REVIEW FINAL LOCATIONS WITH THE ARCHITECT/DESIGNER PRIOR TO START OF CONSTRUCTION.
- COORDINATE BLOCKING REQUIREMENTS AND LOCATIONS WITH ELEVATIONS AND DETAILS. ALL WOOD BLOCKING TO BE FIRE RETARDANT TREATED.
- ALIGN CENTERLINES OF ALL WALL-MOUNTED FIRE EXTINGUISHERS AND MEP/IP DEVICES ON WALLS IN THE SAME LOCATION.
- DISCLAIMER: MANUFACTURERS REFERENCES ARE INTENDED TO ESTABLISH COLOR AND FINISH ONLY AND ARE NOT INTENDED TO LIMIT SELECTIONS FROM OTHER MANUFACTURERS. WHEN ALTERNATE SELECTIONS ARE SUBMITTED, SUBMITTAL SHALL INCLUDE MATERIALS LISTED FOR COMPARISON.
- DIMENSIONS:
  - ALL DIMENSIONS ARE TO FINISHED FACE OF WALL U.O.N.
  - DRAWINGS ARE NOT TO BE SCALED; VERIFY ANY MISSING OR CONFLICTING WRITTEN DIMENSIONS WITH THE ARCHITECT/DESIGNER PRIOR TO CONSTRUCTION.
  - NOTIFY ARCHITECT OF CONDITIONS WHERE CLEAR OR CRITICAL DIMENSIONS ARE DESIGNATED BUT CANNOT BE MET OR WHERE CORRIDOR/AISLE WIDTH CANNOT MEET THE MINIMUM REQUIREMENTS (3'-8" U.O.N.).
  - MAINTAIN FINISH FLOOR BASE ELEVATION THROUGHOUT THE CONTRACT AREA SUCH THAT ALL DIMENSIONS INDICATED AS ABOVE FINISH FLOOR ARE AT THE SAME ELEVATION.

SYMBOLS LEGEND

- 0 COLUMN GRID LINE
- ∅ CENTER LINE
- 1 DETAIL MARKER
- 101 DOOR TAG
- SIM SECTION MARKER
- Room name ROOM IDENTIFICATION
- 11 WALL TAG

MATERIALS LEGEND

	ALUMINUM		GWB
	BATT INSULATION		PARTICLE BOARD
	BRICK		PLYWOOD
	CERAMIC TILE		RIGID INSULATION
	CMU		SAND, CEMENT, GROUT
	COMPRESSIBLE FILLER		SHINGLE
	CONCRETE		SMOKE SEALANT
	EARTH		SPRAYED FIREPROOFING
	GRATE		STEEL
	GRAVEL		WOOD



SCALE AS NOTED

ORIGINAL DRAWING SIZE IS 22 x 34

GENERAL NOTES, LEGENDS & ABBREVIATIONS

VILLAGE STREET MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY  
PFAS UPGRADES PRELIMINARY DESIGN



TOWN OF MILLIS  
DPW ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT 2023
CURRENT REVISION	
DESIGNED BY	KL, PM
DRAWN BY	PM
CHECKED BY	DS
APPROVED BY	DS















A. GENERAL NOTES

- 1. ALL WORK MUST CONFORM TO THE REQUIREMENTS OF THE MASSACHUSETTS STATE BUILDING CODE, 9TH EDITION.
2. PROPOSED FIELD MODIFICATION, REVISIONS AND ADDITIONS TO THE DESIGN DRAWING MUST BE APPROVED BY THE ENGINEER...
3. CONTRACTOR MUST PROVIDE ALL MATERIAL, LABOR, EQUIPMENT, CONSUMABLES, AND ALL OTHER ITEMS REQUIRED TO COMPLETE THE WORK...
4. CONTRACTOR MUST VISIT THE PROJECT SITE AND OBSERVE CONDITIONS FOR THE PROPOSED CONSTRUCTION...
5. COMPLETED SHOP DRAWINGS FOR ALL WORK MUST BE SUBMITTED FOR REVIEW AND APPROVAL PRIOR TO THE START OF FABRICATION AND CONSTRUCTION ACTIVITIES...
6. UNLESS NOTED OTHERWISE ON THE DESIGN DRAWINGS, ALL DESIGN, MATERIALS, FABRICATION, TESTING, AND CONSTRUCTION MUST COMPLY WITH THE FOLLOWING NOTES, REFERENCED CODES, SPECIFICATIONS AND STANDARDS...
7. THE STRUCTURAL DRAWINGS MUST BE USED IN CONJUNCTION WITH ALL OTHER DESIGN DRAWINGS AND SPECIFICATIONS...
8. STRUCTURAL REQUIREMENTS TO SECURE FIXED EQUIPMENT, INCLUDING BUT NOT LIMITED TO ROOF TOP UNITS, EQUIPMENT AND EMBEDMENTS, ARE INCIDENTAL TO THE REQUIREMENTS OF A SPECIFIC EQUIPMENT MANUFACTURER...

B. PROTECTION OF EXISTING STRUCTURES NOTES

- 1. EXISTING STRUCTURES, CONDUITS, UTILITY LINES AND OTHER UTILITIES MUST BE IDENTIFIED BY THE OWNER AND CONTRACTOR AND CLEARLY MARKED ON-SITE PRIOR TO INITIATING CONSTRUCTION...
2. UNLESS NOTED OTHERWISE ON THE DESIGN DRAWINGS, ALL EXISTING STRUCTURES ARE UNCOVERED BY THE CONTRACTOR...
3. THE CONTRACTOR MUST REPORT ITS FINDINGS TO THE OWNER'S SITE REPRESENTATIVE FOR INSTRUCTIONS BEFORE PROCEEDING FURTHER...

C. DESIGN CRITERIA NOTES

- 1. STRUCTURES ARE DESIGNED IN ACCORDANCE WITH THE MASSACHUSETTS STATE BUILDING CODE, 9TH EDITION.
2. DEAD LOAD: WEIGHT OF BUILDING COMPONENTS SPECIFIED ON THE DRAWINGS
3. LIVE LOAD: INTERIOR SLABS, LIGHT STORAGE, HEAVY STORAGE, FLOOR PLATES AND GRADING
4. ROOF LIVE LOAD: MAINTENANCE
5. SNOW LOAD: GROUND SNOW, FLAT-ROOF SNOW, EXPOSURE FACTOR, THERMAL FACTOR, IMPORTANCE FACTOR, SLOPE FACTOR, DRIFT SURCHARGE, DRIFT WIDTH
6. WIND LOAD: RISK CATEGORY, ULTIMATE WIND SPEED, NOMINAL WIND SPEED, EXPOSURE CATEGORY, DIRECTIONALITY FACTOR, GUST EFFECT FACTOR, TOPOGRAPHIC FACTOR, INTERNAL PRESSURE COEFFICIENT
7. SEISMIC LOAD: RISK CATEGORY, IMPORTANCE FACTOR, SITE CLASSIFICATION, SEISMIC DESIGN CATEGORY, RESPONSE MODIFICATION FACTOR, DESIGN SPECTRAL RESPONSES
8. GEOTECHNICAL: GEOTECHNICAL INVESTIGATION ON GOING.

REFERENCED SOIL PROPERTIES FROM GEOTECHNICAL REPORT ARE AS FOLLOWS: APPROXIMATE GROUND WATER ELEVATION BELOW GRADE, SOIL BEARING CAPACITY (ALLOWABLE), COEFFICIENT OF FRICTION, SUBGRADE MODULUS

- 9. FLOOD: DESIGN CLASS, LOWEST FLOOR ELEVATION, DRY FLOODPROOFED ELEVATION
10. RAIN: INTENSITY

D. BUILDING ERECTION NOTES

- 1. THE CONTRACTOR SHALL PROVIDE, FURNISH, AND ERECT BUILDING INCLUDING ALL STRUCTURAL SUPPORTS (PRIMARY AND SECONDARY), ROOFING AND SIDING MATERIALS, DOORS, AND DOOR OPERATIONG EQUIPMENT.

E. CAST-IN-PLACE CONCRETE NOTES

- 1. ALL CONCRETE WORK AND MATERIALS MUST BE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND THE CURRENT EDITION OF THE FOLLOWING STANDARDS:
a. MASSACHUSETTS STATE BUILDING CODE (9TH EDITION)
b. GUIDE TO MASS CONCRETE (ACI 207)
c. SPECIFICATIONS FOR STRUCTURAL CONCRETE (ACI 301)
d. HOT WEATHER CONCRETE REQUIREMENTS (ACI 305)
e. COLD WEATHER CONCRETE REQUIREMENTS (ACI 306)
f. BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE (ACI 318)
g. BUILDING CODE REQUIREMENTS FOR ENVIRONMENTAL ENGINEERING CONCRETE STRUCTURES (ACI 350)
h. RECOMMENDED PRACTICE FOR PLACING REINFORCING STEEL (CRSI)
i. STRUCTURAL WELDING CODE - REINFORCING STEEL (AWS D1.4)
j. PROJECT SPECIFICATIONS
k. OSHA STANDARDS 1910 & 1926
l. ACI DETAILING MANUAL (SP-66)
2. SHOP DRAWINGS, SHOWING ALL FABRICATION DIMENSIONS AND LOCATIONS FOR PLACING OF THE REINFORCING STEEL AND ACCESSORIES, MUST BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ANY FABRICATION.
3. REINFORCING BARS MUST BE FABRICATED IN ACCORDANCE WITH THE STANDARD FABRICATED TOLERANCES SPECIFIED IN ACI 315, CHAPTER 4.
4. NO ALUMINUM EMBEDMENT IN THE CONCRETE IS PERMITTED.
5. ALL EXPOSED CONCRETE EDGES MUST HAVE A 1/4" X 3/4", 45° CHAMFER UNLESS NOTED OTHERWISE.
6. ALL PERMANENTLY EXPOSED VERTICAL AND HORIZONTAL CONCRETE SURFACES MUST BE TREATED OR SEALED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND CONCRETE FINISH REQUIREMENTS.
7. UNLESS NOTED OTHERWISE STEEL REINFORCEMENT MUST CONFORM TO THE FOLLOWING STANDARDS:
a. REINFORCING STEEL MUST BE DEFORMED BILLET STEEL CONFORMING TO ASTM A615, GRADE 60.
b. UNCOATED REINFORCING STEEL MUST BE DEFORMED BILLET STEEL CONFORMING TO ASTM A706, GRADE 60.
c. EPOXY COATED REINFORCING STEEL MUST BE DEFORMED BILLET STEEL CONFORMING TO ASTM A775, GRADE 60.
d. WELD WIRE FABRIC (MESH) MUST CONFORM TO ASTM A185 AND MUST BE PROVIDED IN FLAT SHEETS (ROLLS NOT PERMITTED).
e. UNLESS NOTED OTHERWISE ON THE DESIGN DRAWINGS ALL REINFORCING STEEL IS UNCOATED (PLAIN) DEFORMED BARS.
f. THE ALL REINFORCING STEEL AND EMBEDMENTS SECURELY IN PLACE PRIOR TO PLACING CONCRETE. PROVIDE SUPPORTS TO MAINTAIN THE POSITION OF REINFORCEMENT WITHIN SPECIFIED TOLERANCES DURING ALL CONSTRUCTION ACTIVITIES. WET "STICKING" DOWELS, ANCHORS, ETC. INTO CONCRETE IS NOT PERMITTED.
g. REINFORCING STEEL MUST BE DETAILED AND FABRICATED IN ACCORDANCE WITH ACI 315 "DETAILS AND DETAILING CONCRETE REINFORCEMENT"
h. UNDIMENSIONED HOOKS AT ENDS OF REINFORCEMENT AND STIRRUPS MUST BE STANDARD HOOKS IN ACCORDANCE WITH ACI 318 UNLESS NOTED OTHERWISE.
i. REINFORCING STEEL MUST BE SPLICED AS SPECIFIED ON THE DESIGN DRAWINGS OR AS APPROVED, IN WRITING, BY THE ENGINEER. WHEN SPLICE LENGTHS ARE NOT SPECIFIED ON THE DESIGN DRAWINGS THEY MUST BE THE MINIMUM LENGTHS DEFINED IN THE "TENSION LAP SPLICE LENGTH" TABLE. SPLICES NOT DEFINED ON THE DESIGN DRAWINGS MUST BE LAPPED IN ACCORDANCE WITH THE PROVISIONS OF ACI 318 FOR CLASS B SPLICES.
j. REINFORCING STEEL MUST BE CONTINUOUS THROUGH ALL CONSTRUCTION JOINTS, CORNERS, AND INTERSECTIONS UNLESS NOTED OTHERWISE. REINFORCING STEEL MUST NOT BE CONTINUOUS THROUGH SLAB-ON-GRADE CONTROL JOINTS. REINFORCING STEEL MUST BE LAPPED AT NECESSARY SPLICES OR HOOKED AT DISCONTINUOUS END WITH ACI 318 STANDARD HOOKS UNLESS NOTED OTHERWISE.
k. FIELD WELDING OF CROSSING BARS BY TACK WELDING IS STRICTLY PROHIBITED.
l. ALL REINFORCING STEEL MUST BE FREE FROM LOSE RUST, SCALE OR ANY FOREIGN MATERIAL PRIOR TO PLACING ANY CONCRETE.
8. PROVIDE ADDITIONAL REINFORCEMENT ALONG EACH SIDE OF OPENINGS AS SPECIFIED IN THE STANDARD DETAILS UNLESS NOTED OTHERWISE.
9. MECHANICAL REINFORCEMENT SPLICES SHALL BE PERMITTED SUBJECT TO THE CONTRACTOR PROPOSED LOCATIONS AND APPROVAL, IN WRITING, BY THE ENGINEER. IN ALL ENGINEER APPROVED INSTANCES, MECHANICAL SPLICES MUST DEVELOP AT A MINIMUM OF 125 PERCENT OF THE SPECIFIED YIELD STRENGTH OF THE REINFORCING BAR.
10. MINIMUM CONCRETE PROTECTIVE COVERING FOR REINFORCEMENT SHALL BE AS FOLLOWS, UNLESS NOTED OTHERWISE:
a. CONCRETE CAST AGAINST EARTH (NOT FORMED)
b. CONCRETE EXPOSED TO EARTH OR WEATHER
c. CONCRETE NOT EXPOSED TO EARTH OR WEATHER
d. CONCRETE OVER OR IN-CONTACT WITH LIQUID
11. UNLESS NOTED OTHERWISE CONSTRUCTION, EXPANSION, AND CONTROL JOINTS MUST CONFORM TO THE FOLLOWING STANDARDS:
a. HORIZONTAL CONSTRUCTION JOINTS ARE PERMITTED ONLY WHERE SPECIFIED ON THE DESIGN DRAWINGS. ALL OTHERS DEEMED NECESSARY, BY THE CONTRACTOR, MUST BE APPROVED, IN WRITING, BY THE ENGINEER.
b. THE LOCATION OF VERTICAL CONSTRUCTION JOINTS MUST BE APPROVED, IN WRITING, BY THE ENGINEER. CONSTRUCTION JOINTS MUST BE ROUGHENED TO 1/2" AMPLITUDE IN ACCORDANCE WITH ICRI CSP STANDARDS.
c. UNLESS NOTED OTHERWISE, PLACE VERTICAL CONTROL JOINTS IN RETAINING WALLS AT 20'-0" O.C. (MAX.), 1/2" DEEP, V-CHAMFERED ON BOTH FACES. CONSTRUCTION JOINTS MUST COINCIDE WITH CONTROL JOINTS.
d. THE DESIGNATION "C.J." INDICATES A CONSTRUCTION JOINT BETWEEN SUCCESSIVE CONCRETE PLACEMENTS.
12. A MINIMUM OF 72 HOURS MUST ELAPSE BETWEEN ADJACENT CONCRETE PLACEMENTS.

E. CAST-IN-PLACE CONCRETE NOTES (CONT.)

- 13. UNLESS NOTED OTHERWISE EMBEDDED ITEMS MUST CONFORM TO THE FOLLOWING STANDARDS:
a. CONCRETE WORK MUST BE COORDINATED WITH ALL PROCESS, EQUIPMENT, WATERPROOFING, ARCHITECTURAL, MECHANICAL, HVAC, FIRE PROTECTION, CIVIL, PLUMBING, ELECTRICAL WORK AND VENDOR'S DRAWINGS FOR EMBEDDED ITEMS NOT SPECIFIED ON THE DESIGN DRAWINGS. THE CONTRACTOR IS FULLY RESPONSIBLE FOR COORDINATING AND PLACING ALL EMBEDDED ITEMS SPECIFIED ON THE DRAWINGS OR REQUIRED BY VARIOUS TRADES.
b. PRIOR TO PLACEMENT OF ANY CONCRETE, ALL DESIGN DRAWINGS MUST BE REVIEWED TO ENSURE THAT ALL EMBEDDED ITEM ARE PROPERLY PLACED AND ANCHORED. THE CONTRACTOR MUST VERIFY INSTALLATION AND LOCATIONS OF ALL EMBEDDED ITEMS INCLUDING, BUT NOT NECESSARILY LIMITED TO, INSERTS, ANCHOR BOLTS, ANCHOR RODS, DOWELS, BLOCKOUTS, SLEEVES, EMBEDDED PIPING AND CONDUIT PRIOR TO CONCRETE PLACEMENT.
c. ALL EMBEDDED PLATES MUST BE FLUSH WITH FINISH SURFACE OF CONCRETE.
d. WATERSTOPS MUST BE OF SIZE AND TYPE AS SPECIFIED ON THE DESIGN DRAWINGS AND IN THE PROJECT SPECIFICATIONS AND MUST BE CONNECTED TO PROVIDE A CONTINUOUS WATERTIGHT SEAL.
14. CONCRETE FLOOR AND ROOF SLOPES MUST BE AN INTEGRAL PART OF FRAMED SLABS. SEPARATE CONCRETE FILL OR TOPPING SLABS ARE NOT PERMITTED UNLESS NOTED OTHERWISE ON THE DESIGN DRAWINGS.
15. CONCRETE SURFACES SPECIFIED TO BE ROUGHENED MUST BE ROUGHENED TO 1/4" AMPLITUDE IN ACCORDANCE WITH ICRI CSP STANDARDS.
16. CONCRETE SLABS AND BEAMS MUST BE PLACED MONOLITHICALLY UNLESS NOTED OTHERWISE.
17. AIR-ENTRAIN ALL CONCRETE.
18. ALL CONCRETE MUST HAVE TYPE I OR II PORTLAND CEMENT CONFORMING TO ASTM C150.
19. ALL CONCRETE MUST BE NOMINAL WEIGHT AND HAVE THE FOLLOWING MINIMUM STRENGTH UNLESS NOTED OTHERWISE:
a. LEAN CONCRETE FOR FILL, 1000 PSI @ 28 DAYS
b. SPREAD FOOTING AND FOUNDATION WALLS, 5000 PSI @ 28 DAYS
c. SLAB-ON-GRADE, 5000 PSI @ 28 DAYS
d. HOUSEKEEPING PADS, 5000 PSI @ 28 DAYS
e. LIQUID CONTAINMENT STRUCTURES, 5000 PSI @ 28 DAYS
20. ADHESIVE ANCHORING SYSTEM FOR DRILLED-IN REINFORCING BARS MAY BE PERMITTED SUBJECT TO THE APPROVAL, IN WRITING, BY THE ENGINEER. WHEN APPLICATION IS APPROVED, THE ANCHORING SYSTEM MUST BE DESIGNED BY A PROFESSIONAL STRUCTURAL ENGINEER REGISTERED IN THE STATE HAVING AUTHORITY OF THE PROJECT. THE ANCHORING SYSTEM MUST CONFORM TO THE REQUIREMENTS OF ICC-ES AC308 AND BE DESIGNED ACCORDING TO THE METHODS OUTLINES THEREIN AND BE CAPABLE DEVELOPING THE FULL YIELD STRENGTH OF THE BAR BASED ON THE RESULTS OF UNCONFINED PULL-OUT TESTING.
F. POST-INSTALLED ANCHORS
1. THE CONTRACTOR MUST BE RESPONSIBLE TO POSITION AND INSTALL ALL POST-INSTALLED ANCHOR BOLTS TO THE LOCATIONS AND ELEVATIONS SPECIFIED ON THE DESIGN DRAWINGS, IN ACCORDANCE WITH THE REQUIREMENTS AND TOLERANCES OF THE PROJECT SPECIFICATION AND MANUFACTURER RECOMMENDATIONS. POST-INSTALLED ANCHORS MUST BE INSTALLED ONLY IN HARDENED, CURE CONCRETE THAT IS 28 DAYS OR OLDER.
2. DRILLED-IN ADHESIVE ANCHOR SYSTEM MUST BE HILTI HIT-RE 500v3, DIAMETER AND ANCHOR MATERIAL AS SPECIFIED ON THE DESIGN DRAWINGS, COMPLETED WITH THREADED ROD, NUT AND WASHER AS MANUFACTURED BY HILTI, INC., OR EQUAL AS APPROVED, IN WRITING, BY THE ENGINEER. ANCHORS MUST BE INSTALLED IN PROPERLY PREPARED AND CLEANED DRY HOLES, FREE OF STANDING WATER, MOISTURE, ETC. IN STRICT ACCORDANCE WITH MANUFACTURERS REQUIREMENTS.
G. CAST-IN-PLACE ANCHOR BOLTS & EMBEDMENTS
1. THE CONTRACTOR IS RESPONSIBLE TO POSITION AND INSTALL ALL ANCHOR BOLTS AND EMBEDMENTS TO THE LOCATIONS AND ELEVATIONS SPECIFIED ON THE DESIGN DRAWINGS AND IN ACCORDANCE WITH THE REQUIREMENTS AND TOLERANCES OF THE PROJECT SPECIFICATIONS. ALL ANCHOR BOLTS AND EMBEDMENTS MUST BE RIGIDLY SECURED AND PROTECTED IN PLACE TO PREVENT MOVEMENT OR DAMAGE DURING CONCRETE PLACEMENT OPERATIONS WITH TEMPLATES. RIGID TEMPLATES MUST REMAIN IN PLACE A MINIMUM OF 24 HOURS AFTER CONCRETE PLACEMENT HAS CEASED.
2. THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL ANCHOR BOLTS AND EMBEDMENTS FROM DAMAGE OR RUST DURING SHIPMENT AND STORAGE.
3. ANCHOR BOLTS MUST BE SHOP FABRICATED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS TO THE MATERIALS, DIAMETERS AND DIMENSIONS SPECIFIED ON THE DESIGN DRAWINGS. ANCHOR BOLTS MUST BE COMPLETE WITH WASHERS AND HEAVY HEX NUTS. ALL ANCHOR BOLT ASSEMBLIES MUST BE TAGGED WITH MARK NUMBER, INCLUDING STEEL MATERIAL GRADE IDENTIFICATION.
4. STRUCTURAL STEEL EMBEDMENT PLATES, BARS, SHAPES, AND ASSEMBLIES MUST BE FABRICATED IN ACCORDANCE WITH THE PROJECT SPECIFICATION MATERIALS AS SPECIFIED ON THE DESIGN DRAWINGS AND MUST CONFORM TO THE REQUIREMENTS OF THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC). ALL EMBEDMENT ASSEMBLIES MUST BE TAGGED WITH MARK NUMBER.
5. ANCHOR BOLT ASSEMBLIES AND STEEL EMBEDMENTS MUST BE HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A123 AND ASTM A153, AS APPLICABLE.



One Beacon Street, Suite 8100
Boston, MA 02108
Phone: 617-497-7800
www.kleinfelder.com

NOT FOR CONSTRUCTION


Table with 5 columns: REV, DESCRIPTION, DSN DWN, CHK APP, DATE. Contains a grid for tracking revisions.

SCALE VERIFICATION section containing a graphic of a 1-inch scale bar and text: 'THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING' and 'IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY'.

ORIGINAL DRAWING SIZE IS 22 x 34

GENERAL NOTES SHEET 1 OF 2

VILLAGE STREET MILLIS, MASSACHUSETTS
WELL 3 WATER TREATMENT FACILITY
PFAS UPGRADES PRELIMINARY DESIGN



TOWN OF MILLIS
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION
900 MAIN ST, MILLIS, MA 02054

75% DESIGN

Table with project metadata: PROJECT NO. 20233667.002A, ISSUE DATE SEPT. 2023, CURRENT REVISION, DESIGNED BY DF, DRAWN BY JFC, CHECKED BY KM, APPROVED BY DF SHEET 29 of 60.

S-101












**NOT FOR CONSTRUCTION**

REVISIONS

REV	DESCRIPTION	DSN DWN	CHK APP	DATE

SCALE VERIFICATION


THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34


**FOUNDATION**  
VILLAGE STREET MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY  
PFAS UPGRADES PRELIMINARY DESIGN



75% DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	
DESIGNED BY	DF
DRAWN BY	JFC
CHECKED BY	KM
APPROVED BY	DF


S-301




**NOT FOR  
CONSTRUCTION**

REVISIONS


REV	DESCRIPTION	DSN DWN	CHK APP	DATE




**1 SECTION**  
S-301 SCALE: 1/2" = 1'-0"




**2 SECTION**  
S-301 SCALE: 1/2" = 1'-0"



**3 SECTION**  
S-301 SCALE: 3/4" = 1'-0"



**A DETAIL**  
S-401 SCALE: 3/4" = 1'-0"

**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH  
ON ORIGINAL DRAWING  
  
IF IT'S NOT 1 INCH ON THIS  
SHEET ADJUST YOUR SCALES  
ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

SECTIONS

VILLAGE STREET MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY  
PFAS UPGRADES PRELIMINARY DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	
DESIGNED BY	DF
DRAWN BY	JFC
CHECKED BY	KM
APPROVED BY	DF

**S-401**



## ELECTRICAL SYMBOLS

	LINEAR LIGHTING FIXTURES "F1" INDICATES FIXTURE TYPE - TYPICAL FOR ALL FIXTURES "1" INDICATES CIRCUIT NUMBER - TYPICAL FOR ALL FIXTURES "o" INDICATES THE SWITCH CONTROL - TYPICAL FOR ALL FIXTURES
	WALL MOUNTED LIGHTING FIXTURE.
	SURFACE OR PENDANT MOUNTED FIXTURE.
	EMERGENCY EXIT SIGN
	EMERGENCY LIGHTING BATTERY UNIT WITH TWO LIGHT HEADS
	REMOTE EMERGENCY LIGHTING UNIT WITH TWO LIGHTING HEADS PROVIDE 3/4", 2#10, 1#10GND TO NEAREST THE EMERGENCY LIGHTING BATTERY UNIT
	SINGLE POLE SWITCH 120V, 20A "o" INDICATES THE SWITCH CONTROL
	2-POLE SWITCH 120V, 20A 1 POLE FOR ROOM LIGHT FIXTURES, 1-POLE FOR EXHAUST FAN CONTROL
	3-WAY SWITCH 120V, 20A "o" INDICATES THE SWITCH CONTROL
	4-WAY SWITCH 120V, 20A "o" INDICATES THE SWITCH CONTROL
	BREAK GLASS STATION
	DIGITAL TIME CLOCK SWITCH
	MECHANICAL TIMER SWITCH
	WALL MOUNTED DUAL TECHNOLOGY OCCUPANCY SENSOR/SWITCH
	LOW VOLTAGE SWITCH
	COMBINATION PHOTOCELL/MOTION DETECTOR SENSOR
	CEILING MOUNTED DUAL TECHNOLOGY OCCUPANCY SENSOR
	DUPLEX RECEPTACLE, WEATHER-RESISTANT 120V, 20A WITH WEATHERPROOF COVER, "GF" INDICATES GROUND FAULT TYPE "1" INDICATES CIRCUIT NUMBER - TYPICAL FOR ALL RECEPTACLES
	DUPLEX RECEPTACLE 120V, 20A
	(2) DUPLEX (QUAD) RECEPTACLES, 120V, 20A "WP" INDICATES WITH WEATHERPROOF COVER
	SIMPLEX RECEPTACLE, WEATHER-RESISTANT 120V, 20A WITH WEATHERPROOF COVER "TL" INDICATES TWIST LOCK TYPE
	UNFUSED DISCONNECT SWITCH, "30" INDICATES 30 AMP RATING, PROVIDE 3-POLE, UNLESS OTHERWISE INDICATED.
	FUSED DISCONNECT SWITCH, "20" INDICATES 20 AMP FUSE RATING, PROVIDE 3-POLE UNLESS OTHERWISE INDICATED.
	3-PHASE RECEPTACLE
	WALL MOUNTED COMBINATION MOTOR STARTER WITH MOTOR CIRCUIT PROTECTOR, "FVNR" INDICATES TYPE OF MOTOR STARTER
	MOTOR STARTER WITH MOTOR CIRCUIT PROTECTOR, "FVNR" INDICATES TYPE OF MOTOR STARTER
	ENCLOSED VARIABLE FREQUENCY DRIVE
	MANUAL MOTOR STARTER 120V, 20A
	JUNCTION BOX
	NON-UTILITY POLYMER CONCRETE HAND HOLE
	ALARM RELAY, "AR1" REFERS TO RELAY NAME DESIGNATION
	CONTROL RELAY, "CR1" REFERS TO RELAY NAME DESIGNATION
	MOTOR START RELAY
	TIMING RELAY, "TR1" REFERS TO RELAY NAME DESIGNATION

## ELECTRICAL SYMBOLS

	NORMALLY OPEN RELAY CONTACT
	NORMALLY CLOSED RELAY CONTACT
	OPERATOR PUSH BUTTON NORMALLY OPEN CONTACT
	OPERATOR PUSH BUTTON NORMALLY CLOSED CONTACT
	PRESSURE SWITCH - CLOSURES ON HIGH PRESSURE
	PRESSURE SWITCH - CLOSURES ON LOW PRESSURE
	UNDERGROUND CONDUIT DUCT BANK
	HOMERUN DESIGNATION TO PANEL LP1 CIRCUIT #1, WITH THE FOLLOWING CONDUIT/WIRES UNLESS OTHERWISE NOTED: <ul style="list-style-type: none"> <li>• 3/4"C WITH 2#12, 1#12GND FOR 20AMP SINGLE PHASE CIRCUITS AND ELECTRIC UNIT HEATER THERMOSTAT CONTROL</li> <li>• 3/4"C WITH 3#12, 1#12GND FOR 20AMP THREE PHASE CIRCUITS.</li> <li>• 3/4"C WITH 2#10, 1#10GND FOR 30AMP SINGLE PHASE CIRCUITS.</li> <li>• 3/4"C WITH 3#10, 1#10GND FOR 30AMP THREE PHASE CIRCUITS.</li> <li>• 3/4"C WITH 2#8, 1#10GND FOR 40AMP &amp; 50AMP SINGLE PHASE CIRCUITS.</li> <li>• 3/4"C WITH 3#8, 1#10GND FOR 40AMP &amp; 50AMP THREE PHASE CIRCUITS.</li> </ul>
	EYS TYPE CONDUIT SEAL
	SURGE PROTECTION DEVICE
	UTILITY POLE
	UTILITY HANDHOLE, "E" REPRESENTS ELECTRICAL HANDHOLE, "C" REPRESENT COMMUNICATION HANDHOLE
	MOLDED CASE CIRCUIT BREAKER, 3-POLE UNLESS OTHERWISE INDICATED, "20" INDICATES TRIP AMPERE RATING, "100" INDICATES FRAME SIZE, "GFCI" INDICATES CIRCUIT BREAKER TO HAVE GROUND FAULT CIRCUIT INTERRUPT
	DRY TYPE TRANSFORMER
	3/4" x 10" COPPER CLAD GROUND ROD
	BUILDING GROUNDING SYSTEM
	MOTOR, "10" INDICATES HORSEPOWER RATING
	CABLE/CONDUIT DESIGNATION, "XX" REFERS CABLE CONDUIT REFERENCE, REFER TO CABLE/CONDUIT AND DUCT/CABLE SCHEDULES.
	OPERATOR STATION (SUPPLIED BY DIV. 16 UNO ), "XXXX" REFERS TO TAGNAME ID, "YYY" REFERS TO THE TYPE OF OPERATOR STATION
	UNLESS OTHERWISE NOTED INSTRUMENTATION OR PROCESS EQUIPMENT (SUPPLIED BY OTHER DIVISIONS) "XX-XXXX" REFERS TO TAGNAME ID
	GENERATOR EMERGENCY STOP
	OCCUPIED/UNOCCUPIED SELECTOR SWITCH. (SUPPLIED BY DIV. 16)
	THERMOSTAT (SUPPLIED BY DIV. 15)
	MOTOR OPERATED DAMPER (SUPPLIED BY DIV. 15)
	MANUAL WALL SWITCH (BY DIV. 15)
	REFRIGERANT SENSOR (BY DIV. 15)
	METERING PUMP CONTROL PANEL (SUPPLIED BY DIV. 11)
	CHEMICAL FILL STATION (SUPPLIED BY DIV. 13)
	INTRINSICALLY SAFE BARRIER PANEL (SUPPLIED BY DIV. 13)
	ELECTRIC UNIT HEATER, "X" INDICATES UNIT ELECTRIC COIL RATING (SUPPLIED BY DIV. 15)
	EQUIPMENT CIRCUIT NUMBER DESIGNATION TO PANEL LP1-LP CIRCUIT #21.

## FIRE ALARM / SECURITY SYSTEM SYMBOLS

	MANUAL FIRE ALARM STATION
	FIRE ALARM AUDIO/VISUAL DEVICE
	FIRE ALARM VISUAL ONLY DEVICE
	FIRE ALARM BEACON
	SMOKE DETECTOR
	DUCT SMOKE DETECTOR
	REMOTE TEST STATION AND ALARM FOR DUCT SMOKE DETECTOR
	HEAT DETECTOR, COMBINATION RATE-OF-RISE AND FIXED TEMPERATURE
	CARBON MONOXIDE DETECTOR
	INPUT MONITORING MODULE
	RELAY CONTROL MODULE
	FIRE ALARM CONTROL PANEL
	FIRE ALARM ANNUNCIATOR PANEL
	CELLULAR DIGITAL ALARM COMMUNICATOR TRANSMITTER
	MASTER BOX
	KEY DEPOSITORY - KNOX BOX
	FLOW SWITCH
	TAMPER SWITCH
	24V ELECTRIC SPRINKLER BELL, PROVIDED BY FIRE PROTECTION FSB, PROVIDE AND MOUNT IN WEATHERPROOF BACKBOX
	MAGNETIC DOOR SWITCH
	KEY PAD
	SECURITY ALARM CONTROL PANEL

## TELE/DATA & CCTV SYMBOLS

	WALL MOUNTED DATA OUTLET, 2D INDICATES (2) CAT6 TERMINAL DATA CONNECTORS, 1T INDICATES (1) CAT6 TERMINAL TELEPHONE CONNECTOR
	CLOSED CIRCUIT TELEVISION CAMERA - PROVIDED BY DIV. 13
	DIGITAL VIDEO RECORDING SERVER - PROVIDED BY DIV. 13
	POWER OVER ETHERNET SWITCH - PROVIDED BY DIV. 13

## CHEMICAL ALARM SYSTEM SYMBOLS

	MANUAL CHEMICAL ALARM STATION
	CHEMICAL ALARM AUDIO/VISUAL DEVICE
	CHEMICAL ALARM CONTROL PANEL



Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



SCALE VERIFICATION  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

## ELECTRICAL LEGEND AND GENERAL NOTES

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN	
PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB

E-001

**GENERAL NOTES**

- GENERAL CONTRACTOR TO PROVIDE CONCRETE MOUNTING AND HOUSEKEEPING PADS ON ALL FLOOR OR GRADE MOUNTED ELECTRICAL EQUIPMENT. THE FOLLOWING EQUIPMENT IS THE MINIMUM REQUIREMENT FOR HOUSEKEEPING PADS. ADDITIONAL PADS MAYBE REQUIRED BASED ON THE ELECTRICAL CONTRACTORS MOUNTING METHODS, ELECTRICAL CONTRACTOR SHALL COORDINATE WITH GENERAL CONTRACTOR FOR ALL HOUSEKEEPING PAD SIZES AND LOCATIONS.  
1.1. DRY TYPE TRANSFORMERS
- ALL CONDUIT AND EQUIPMENT SHALL BE INSTALLED AND GROUNDED IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE AND APPLICABLE LOCAL CODES.
- BONDING JUMPERS, CONDUIT CLAMPS AND POINTS OF ATTACHMENT ARE NOT SHOWN ON DRAWINGS. SIZE BONDING JUMPERS IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE. THE POINTS OF ATTACHMENT OF THE GROUND CLAMPS SHALL BE ACCESSIBLE LOCATIONS.
- EQUIPMENT & CONDUIT INSTALLATIONS ARE SHOWN DIAGRAMMATICALLY ONLY AND SHALL BE INSTALLED IN A MANNER TO PREVENT CONFLICTS WITH EQUIPMENT AND STRUCTURAL CONDITIONS. EXPOSED CONDUITS SHALL BE INSTALLED PARALLEL TO BEAMS AND WALLS.
- CONDUITS SHALL BE TERMINATED SO AS TO PERMIT NEAT CONNECTIONS TO MOTORS AND OTHER EQUIPMENT.
- NO CONDUIT SMALLER THAN 3/4" PIPE SIZE NOR WIRE SMALLER THAN NO. 12 A.W.G. SHALL BE USED UNLESS OTHERWISE NOTED.
- RECEPTACLES AND SWITCHES SHALL BE MOUNTED 45" ABOVE FINISHED FLOOR.
- THE WIRING AND BLOCK DIAGRAMS, QUANTITY AND SIZE OF WIRES AND CONDUIT REPRESENT A SUGGESTED ARRANGEMENT BASED UPON SELECTED STANDARD COMPONENTS OF ELECTRICAL AND PROCESS EQUIPMENT. MODIFICATIONS ACCEPTABLE TO THE ENGINEER MAY BE MADE BY THE CONTRACTOR TO ACCOMMODATE EQUIPMENT ACTUALLY PURCHASED. THE BASIC SEQUENCE AND METHOD OF CONTROL MUST BE MAINTAINED AS INDICATED ON THE DRAWINGS AND/OR SPECIFICATIONS.

**DEMOLITION NOTES**

- UNLESS OTHERWISE NOTED, ALL EXISTING ELECTRICAL SYSTEMS (POWER, LIGHTING, LOW VOLTAGE, CONTROLS, ETC) AND ASSOCIATED EQUIPMENT INDICATED WITH HATCH MARKS IS TO BE DEMOLISHED. DISCONNECT AND DE-ENERGIZE THE EQUIPMENT. REMOVE THE EQUIPMENT TO BE DEMOLISHED OR SALVAGED PER SECTION 02050. ALL CONTROL DEVICES, CONDUIT, CABLING, BOXES, SUPPORTS, ETC, ASSOCIATED WITH THE DEMOLISHED EQUIPMENT SHALL BE REMOVED. THE CONDUIT AND CABLING SHALL BE REMOVED BACK TO SOURCE.
- NO DEVICE OR EQUIPMENT INDICATED FOR DEMOLITION WILL BE REUSED OR SALVAGED UNLESS SPECIFICALLY NOTED AS SUCH. ALL EQUIPMENT REMOVED SHALL BE REMOVED FROM SITE AND PROPERLY DISPOSED OF. PRIOR TO REMOVAL OF EQUIPMENT COORDINATE WITH OWNER FOR ANY EQUIPMENT THE OWNER WILL KEEP.
- EXISTING EQUIPMENT INDICATED ON THE DEMOLITION PLANS ARE BASED ON SITE OBSERVATIONS AND IT IS NOT THE INTENTION OF THESE DRAWINGS TO SHOW ALL EQUIPMENT AND MATERIALS TO BE DISCONNECTED AND/OR REMOVED.
- ALL UNDERGROUND CONDUIT SHALL BE CUT BELOW GRADE, CAPPED AND BACKFILLED WITH DIRT TO MATCH GRADE. ALL CONDUIT STUBBING UP FROM CONCRETE SLAB SHALL BE CUT AND CAPPED AND SLAB LEVEL. ALL WIRING SHALL BE REMOVED COMPLETELY.

**ABBREVIATIONS**

(2)1" C, 3#8, #10GND	2. 1-INCH CONDUITS EACH CONDUIT CONTAINING 3-#8 AWG WIRES AND 1-#10 GROUND CONDUCTOR	RGS	RIGID GALVANIZED STEEL
3/4" CE	EMPTY CONDUIT. NUMERAL DENOTES SIZE	RVNR	REDUCED VOLTAGE NON-REVERSING
AFF	ABOVE FINISHED FLOOR	SPD	SURGE SUPPRESSOR DEVICE
AFG	ABOVE FINISHED GRADE	SOV	SOLENOID VALVE
AR	ALARM RELAY	S/S	SOFT STARTER
ATS	AUTOMATIC TRANSFER SWITCH	TB	TERMINAL BOX
CR	CONTROL RELAY	TD	MOTOR TEMPERATURE DETECTOR
CP	CONTROL PANEL	TR	TIMING RELAY
DRG. DWG.	DRAWING	TS	TEMPERATURE SWITCH
EAN	EXCEPT AS NOTED	TSP	TWISTED SHIELDED PAIR
EC	ELECTRICAL CONTRACTOR	TSTW	TWO SPEED TWO WINDING
ETM	ELAPSED TIME METER	TYP	TYPICAL
FE	FLOW ELEMENT	UG	UNDERGROUND
FIT	FLOW INDICATOR TRANSMITTER	UNO	UNLESS OTHERWISE NOTED
FS	FLOW SWITCH	VFD	VARIABLE FREQUENCY DRIVE
FT	FLOW TRANSMITTER	WP	WATER PROOF
FVNR	FULL VOLTAGE NON-REVERSING	WHM	WATT HOUR UTILITY METER
GND, GRD	GROUNDING CONDUCTOR (EQUIPMENT)	XFMR	TRANSFORMER
HOA	HAND-OFF-AUTOMATIC		
HH	HANDHOLE		
J OR JB	JUNCTION BOX		
JPB	JOG PUSHBUTTON		
LE	LEVEL ELEMENT		
LIT	LEVEL INDICATOR TRANSMITTER		
LL	LOW LEVEL		
LS	LEVEL SWITCH		
LT	LEVEL TRANSMITTER		
MC	MOTOR CONTROLLER (STARTER)		
MCC	MOTOR CONTROL CENTER		
MH	MANHOLE		
MFR	MANUFACTURER		
MS	MOTION OR MOISTURE SENSOR		
NTS	NOT TO SCALE		
OEM	ORIGINAL EQUIPMENT MANUFACTURE SUPPLIED		
OH	OVERHEAD		
OL	MOTOR OVERLOAD HEATER		
OS	OPERATOR STATION		
PB	PUSHBUTTON CONTROL STATION MOMENTARY CONTACT TYPE, STOP START		
PBE	PUSHBUTTON CONTROL STATION MAINTAINED EMERGENCY STOP TYPE, TWIST TO RELEASE		
PBL	PUSHBUTTON CONTROL STATION MOMENTARY TYPE WITH LOCK-OUT DEVICE, STOP-START		
PBM	PUSHBUTTON CONTROL STATION MAINTAINED CONTACT TYPE, STOP START		
PIT	PRESSURE INDICATOR TRANSMITTER		
PL	PUSHBUTTON CONTROL STATION MOMENTARY TYPE WITH LOCK-OUT DEVICE, STOP		

Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL GENERAL NOTES**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

**75% DESIGN**

PROJECT NO.	20233667.002A	<b>E-002</b>
ISSUE DATE	SEPT. 2023	
CURRENT REVISION	-	
DESIGNED BY	MC	
DRAWN BY	RLB	
CHECKED BY	MC	
APPROVED BY	ABB	
SHEET		36 of 60



Signed By: ---- # 12345


REV	DESCRIPTION	DSN DWN	CHK APP	DATE

**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL TREATMENT BUILDING ONE LINE DIAGRAM**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB

E-003



**TREATMENT BUILDING ONE LINE DIAGRAM**  
NOT TO SCALE

Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY


ORIGINAL DRAWING SIZE IS 22 x 34  
**ELECTRICAL**  
**WELL STATION #3 ONE LINE DIAGRAMS**  
TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

**75% DESIGN**

PROJECT NO. 20233667.002A	<b>E-004</b>
ISSUE DATE SEPT. 2023	
CURRENT REVISION -	
DESIGNED BY MC	
DRAWN BY RLB	
CHECKED BY MC	
APPROVED BY ABB	



**WELL STATION #3 DEMOLITION ONE LINE DIAGRAM**  
NOT TO SCALE



**WELL STATION #3 ONE LINE DIAGRAM**  
NOT TO SCALE



Signed By: ---- # 12345

REVISIONS				
REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

0 1"

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL SITE PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST., MILLIS, MA 02054

75% DESIGN


PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB

E-005



**SITE PLAN:**  
SCALE: 1" = 10'

Signed By: ---- # 12345




REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



**ELECTRICAL LOWER LEVEL FLOOR POWER PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST., MILLIS, MA 02054

**75% DESIGN**


PROJECT NO. 20233667.002A	<b>E-101</b>
ISSUE DATE SEPT. 2023	
CURRENT REVISION -	
DESIGNED BY MC	
DRAWN BY RLB	
CHECKED BY MC	
APPROVED BY ABB	SHEET 40 of 60



REV	DESCRIPTION	DSN DWN	CHK APP	DATE




**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL UPPER LEVEL FLOOR POWER PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN


PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB

E-102  
SHEET 41 of 60



FUTURE  
5

Signed By: ---- # 12345



REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH  
ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS  
SHEET ADJUST YOUR  
SCALES ACCORDINGLY

0 4' 8'  
SCALE: 1/4" = 1'-0" SCALE IN FEET

ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL  
LIGHTING FLOOR PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST., MILLIS, MA 02054

**75% DESIGN**

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT., 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB



**E-201**





Signed By: --- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**  
 THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
 0 1"  
 IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

0 4' 8'  
 SCALE: 1/4" = 1'-0" SCALE IN FEET

ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL LOW VOLTAGE FLOOR PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
 WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
 DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
 900 MAIN ST, MILLIS, MA 02054

75% DESIGN


PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB

E-301

SHEET 44 of 60








– PROVIDE ALL INTERCONNECTING CONDUIT/CABLE

**EF-1 EXHAUST FAN WIRING DIAGRAM**


NOT TO SCALE



– PROVIDE ALL INTERCONNECTING CONDUIT/CABLE

**EF-3 EXHAUST FAN WIRING DIAGRAM**


NOT TO SCALE



– PROVIDE ALL INTERCONNECTING CONDUIT/CABLE

**EF-2 EXHAUST FAN WIRING DIAGRAM**


NOT TO SCALE



– PROVIDE ALL INTERCONNECTING CONDUIT/CABLE


**EF-4 EXHAUST FAN WIRING DIAGRAM**

NOT TO SCALE



**SCADA COMMUNICATION RISER DIAGRAM**

NOT TO SCALE




**FIRE/SECURITY NOTES:**

1. RISER DIAGRAM ONLY REPRESENTS TYPE OF DEVICES AND DOES NOT REPRESENT ACTUAL QUANTITIES. REFER TO PLAN DRAWINGS QUANTITIES AND LOCATIONS OF DEVICES.
2. MINIMUM SIZE CONDUIT SHALL BE 3/4" UNLESS NOTED OTHERWISE.
3. SYSTEM CONDUIT/CABLING SHALL BE INSTALLED IN ACCORDANCE WITH EQUIPMENT SUPPLIERS APPROVED SHOP DRAWINGS AND WIRING DIAGRAMS.
4. PROVIDE RED COLORED CIRCUIT BREAKER HANDLE LOCK ON POWER CIRCUIT. HANDLE LOCK SHALL ALLOW THE CIRCUIT BREAKER TO TRIP, BUT PREVENT SWITCHING OF THE CIRCUIT BREAKER TO THE "OFF" POSITION.
5. ALL COMPONENTS OF THE SYSTEM SHALL BE MOUNTED IN ACCORDANCE WITH ADA REQUIREMENTS.

**FIRE/SECURITY SYSTEM RISER DIAGRAM**

NOT TO SCALE



**CHEMICAL ALARM RISER DIAGRAM**

NOT TO SCALE

**CHEMICAL ALARM NOTES:**

1. RISER DIAGRAM ONLY REPRESENTS TYPE OF DEVICES WITHIN AN AREA AND DOES NOT REPRESENT ACTUAL QUANTITIES. REFER TO PLAN DRAWINGS FOR EXACT QUANTITIES AND LOCATIONS OF DEVICES.
2. MINIMUM SIZE CONDUIT SHALL BE 3/4" UNLESS NOTED OTHERWISE.
3. SYSTEM CONDUIT/CABLING SHALL BE INSTALLED IN ACCORDANCE WITH EQUIPMENT SUPPLIERS APPROVED SHOP DRAWINGS AND WIRING DIAGRAMS.
4. PROVIDE RED COLORED CIRCUIT BREAKER HANDLE LOCK ON POWER CIRCUIT. HANDLE LOCK SHALL ALLOW THE CIRCUIT BREAKER TO TRIP, BUT PREVENT SWITCHING OF THE CIRCUIT BREAKER TO THE "OFF" POSITION.
5. ALL COMPONENTS OF THE SYSTEM SHALL BE MOUNTED IN ACCORDANCE WITH ADA REQUIREMENTS.
6. THE CHEMICAL ALARM SYSTEM SHALL BE UL LISTED 4-ZONE CONVENTIONAL TYPE FIRE ALARM SYSTEM.



Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL DIAGRAMS II**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

**75% DESIGN**

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB




E-401



### PANELBOARD SCHEDULE

NO. LP1													LOCATION: 011 ELECTRIC ROOM												
208/120 V, 3 PH, 4 W, — A MAIN, 100% SOLID NEUTRAL; — A MCB													22,000 AIC AT — V FULL GROUND BUS — A MLO SURFACE MOUNTING												
CIRCUIT	DESCRIPTION OF LOAD	LOAD (KVA)			BREAKER		CIRCUIT	CIRCUIT	LOAD (KVA)			BREAKER		CIRCUIT											
		AØ	BØ	CØ	TRIP	POLE			POLE	TRIP	AØ	BØ	CØ		DESCRIPTION OF LOAD										
1	INTERIOR LIGHTING	0.94			20A	1			1	20A	1.0			2											
3	EXTERIOR LIGHTING		0.10		20A	1			1	20A	0.80			4											
5	EMERGENCY SHOWER		0.15		20A	1			1	20A	0.80	0.80		6											
7	FIRE ALARM CONTROL PANEL FACP	0.50			20A	1			1	20A	0.40			8											
9	CHEMICAL ALARM CONTROL PANEL CACP	0.50			20A	1			1	20A	0.77			10											
11	GAS UNIT HEATER GUH-1		1.10		20A	1			1	20A	0.20			12											
13	GAS UNIT HEATER GUH-2	1.10			20A	1			1	20A	0.77			14											
15	ELECTRIC WALL HEATER EWH-1		1.50		20A	1			1	20A	0.10			16											
17	CFP-601, CFP-611, CFP-621			0.75	20A	1			1	20A	0.72			18											
19	CFP-602, CFP-612, CFP-622	0.75			20A	1			1	20A	0.72			20											
21	CHEMICAL FILL STATIONS		0.20		20A	1			1	20A	0.72			22											
23	FLOW METERS			1.00	20A	1			1	20A	0.72			24											
25	GAS WATER HEATER TWH-1	0.50			20A	1			1	20A	0.12			26											
27	RECIRC. PUMP RP-1		0.10		20A	1			1	—	—			28											
29	—	—	—	—	—	1			1	—	—			30											
31	—	—	—	—	—	1			1	—	—			32											
33	—	—	—	—	—	1			1	—	—			34											
35	—	—	—	—	—	1			1	—	—			36											
37	—	—	—	—	—	1			1	—	—			38											
39	—	—	—	—	—	1			1	20A	0.50		GENERATOR BATTERY CHARGER & STATOR HEAT.	40											
41	—	—	—	—	—	1			1	20A	1.50		GENERATOR BLOCK HEATER	42											
SUB-TOTAL CONNECTED		—	—	—	—	—			—	—	—		—	—											
* PROVIDE GFCI BREAKER													SUB-TOTAL CONNECTED KVA AØ = —												
													SUB-TOTAL CONNECTED KVA BØ = —												
													SUB-TOTAL CONNECTED KVA CØ = —												
													TOTAL CONNECTED KVA = —												

### LIGHTING FIXTURE SCHEDULE

TYPE	DESCRIPTION	MANUFACTURER & CATALOG SERIES	LAMPS		VOLTS	WATTS	MOUNTING		REMARKS
			TYPE	LUMENS			TYPE	HEIGHT	
F1	48" LED ENCLOSED AND GASKETED INDUSTRIAL LIGHTING FIXTURE.	LITHONIA FEM-L48-6000LM-MAFL-MVOLT-35K-80CRI	LED 3500K	6000lm	120	45	PENDANT	20'-0" ABOVE FINISHED FLOOR UNLESS OTHERWISE NOTED	
F2	48" LED ENCLOSED AND GASKETED INDUSTRIAL LIGHTING FIXTURE.	LITHONIA FEM-L48-4000LM-MAFL-MVOLT-35K-80CRI	LED 3500K	4000lm	120	31	SURFACE		
W1	EXTERIOR BUILDING MOUNTED LED WALL PACK LIGHT FIXTURE	LITHONIA TWP-LED-20C-700-50K-T3M-120-PE-DDXB	LED 5000K	4200lm	120	45	WALL	APPROXIMATELY 9'-0" AFF	INTEGRAL PHOTOCELL CONTROLLED
	SELF CONTAINED EMERGENCY LIGHTING BATTERY UNIT NEMA 4 WITH TWO LIGHTING HEADS	REFER TO SPECIFICATIONS			120	8W	WALL	APPROXIMATELY 8'-6" AFF	INSTALL 3/4"C, 2#12, 1#12GND TO REMOTE HEADS
	SEALED-BEAM WEATHERPROOF REMOTE LIGHTING FIXTURE WITH TWO LIGHTING HEADS	REFER TO SPECIFICATIONS			120	8W	WALL	APPROXIMATELY 8'-6" AFF	
	EMERGENCY EXIT SIGN LED TYPE WITH BATTERY BACK-UP NEMA 4X	REFER TO SPECIFICATIONS			120		WALL	APPROXIMATELY 8'-6" AFF	

#### LIGHTING FIXTURE SCHEDULES NOTES:

1. THE CATALOG NUMBERS LISTED ARE GIVEN AS A GUIDE TO THE DESIGN AND QUALITY OF FIXTURE DESIRED. EQUIVALENT DESIGNS, MATERIALS, DIMENSIONS, COEFFICIENT OF UTILIZATIONS AND EQUAL QUALITY FIXTURES OF OTHER MANUFACTURERS WILL BE ACCEPTABLE.

### POWER CABLE/CONDUIT SCHEDULE

SYMBOL	CONDUIT SIZE	CONDUCTORS*	GND*
P22	3/4"	(2)#12	(1)#12
P24	3/4"	(4)#12	(1)#12
P26	3/4"	(6)#12	(1)#12
P32	3/4"	(2)#10	(1)#10
P33	3/4"	(3)#10	(1)#10
P53	3/4"	(3)#8	(1)#10
P54	3/4"	(4)#8	(1)#10
P63	1"	(3)#6	(1)#8
P64	1"	(4)#6	(1)#8
P83	1 1/4"	(3)#4	(1)#8
P84	1 1/4"	(4)#4	(1)#8
P103	1 1/2"	(3)#3	(1)#6
P104	1 1/2"	(4)#3	(1)#6
P113	1 1/2"	(3)#2	(1)#6
P114	1 1/2"	(4)#2	(1)#6
P133	2"	(3)#1	(1)#6
P134	2"	(4)#1	(1)#6
P153	2"	(3)#1/0	(1)#6
P154	2"	(4)#1/0	(1)#6
P173	2 1/2"	(3)#2/0	(1)#6
P174	2 1/2"	(4)#2/0	(1)#6
P203	2 1/2"	(3)#3/0	(1)#4
P204	2 1/2"	(4)#3/0	(1)#4
P233	3"	(3)#4/0	(1)#4
P234	3"	(4)#4/0	(1)#4
P253	3"	(3)250KCMIL	(1)#4
P254	3"	(4)250KCMIL	(1)#4
P304	3"	(4)350KCMIL	(1)#4

### TELE/DATA CABLE/CONDUIT SCHEDULE

SYMBOL	CONDUIT SIZE	CABLES
TD1	1"	1-CAT6
FO1	1"	6-STRAND FIBER OPTIC CABLE

### SIGNAL CABLE/CONDUIT SCHEDULE

SYMBOL	CONDUIT SIZE	CONDUCTORS
S	1"	VENDER PROVIDED
S1	3/4"	1-2/C#16 TSP
S13	3/4"	1-3/C#16 TSP
S2	3/4"	2-2/C#16 TSP
S23	3/4"	2-3/C#16 TSP
S3	1"	3-2/C#16 TSP
S33	1"	3-3/C#16 TSP
S4	1"	4-2/C#16 TSP
S5	1"	5-2/C#16 TSP
S6	1 1/2"	6-2/C#16 TSP
S7	1 1/2"	7-2/C#16 TSP
S8	1 1/2"	8-2/C#16 TSP
S9	1 1/2"	9-2/C#16 TSP
S10	2"	10-2/C#16 TSP
TC1	3/4"	8/C#18

### CONTROL CABLE/CONDUIT SCHEDULE

SYMBOL	CONDUIT SIZE	CONDUCTORS
C2	3/4"	2#14
C4	3/4"	4#14
C5	3/4"	5#14
C6	3/4"	6#14
C7	3/4"	7#14
C8	3/4"	8#14
C9	3/4"	9#14
C10	3/4"	10#14
C12	3/4"	12#14
C16	1"	16#14
C20	1"	20#14
C30	1"	30#14
C60	2"	60#14
C64	2"	64#14
C100	2 1/2"	100#14

NOTE: CONDUIT AND CONDUCTOR SIZES ARE TO BE PER THE ABOVE SCHEDULES UNLESS OTHERWISE NOTED.




Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

### ELECTRICAL SCHEDULES

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN







TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

### 75% DESIGN

PROJECT NO. 20233667.002A	E-402
ISSUE DATE SEPT. 2023	
CURRENT REVISION -	
DESIGNED BY MC	
DRAWN BY RLB	
CHECKED BY MC	
APPROVED BY ABB	SHEET 47 of 60




DUCT / CABLE SCHEDULE				
DUCT NO.	SIZE	CONDUCTORS	FROM	TO
D1	3"	(4) 350KCMIL	UTILITY POLE	MCB
D2	3"	PULL STRING	UTILITY POLE	STUB UP BELOW MCB
D3	3"	(4) 350KCMIL, #4 GND	GENERATOR	GENERATOR DISCONNECT SWITCH
D4	1"	(4) #12, #12GND	LP3 PANELBOARD	GENERATOR AUXILIARY SYSTEMS
D5	1"	(12) #14	GENERATOR	ATS, EMERGENCY STOP, SCADA RTU PANEL
D6	2"	(4) #4/0, #6 GND	MDP	WELL STATION #3 DP1
D7	3"	12 STRAND FIBER OPTIC CABLE	FILTER BUILDING FIBER OPTIC PATCH PANEL	WELL STATION #3 FIBER OPTIC PATCH PANEL




- NOTES:**
- BACKFILL DUCT BANK IN LAYERS AND MANUALLY TAMP OR "PUDDLE" CONCRETE FILL. PROVIDE RED DUCT BANK MARKER TAPES, READING "CAUTION - ELECTRICAL LINES BELOW", OVER ENTIRE LENGTH OF DUCTLINE. LOCATE TAPES 12 INCHES BELOW GRADE. PROVIDE A TAPE FOR EVERY 12 INCHES OF WIDTH OF DUCTLINE.
  - A MINIMUM OF 12" SEPARATION SHALL BE KEPT BETWEEN DUCT BANK SECTIONS WITHIN SAME TRENCH.
  - REINFORCING STEEL SHALL BE #5 REBAR WITH CROSS SECTION SPACED EVERY 24". CONCRETE TO BE RATED FOR 3000 PSI AFTER 28 DAYS.

**DUCTBANK SECTIONS**  
NO SCALE



**UTILITY POLE SERVICE  
RISER DETAIL**  
NOT TO SCALE



- NOTES:**
- BACKFILL IN LAYERS AND MANUALLY TAMP. PROVIDE RED DUCT BANK MARKER TAPE, READING "CAUTION - ELECTRICAL LINES BELOW", OVER ENTIRE LENGTH OF DUCTLINE. LOCATE TAPE 12 INCHES BELOW GRADE. PROVIDE A TAPE FOR EVERY 12 INCHES OF WIDTH OF DUCTLINE.
  - TRENCHING AND BACKFILLING SHALL BE PERFORMED UNDER DIVISION 2 OF THIS CONTRACT.

**SINGLE UNDERGROUND CONDUIT SECTION**  
NOT TO SCALE

Signed By: --- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

0 1"

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34  
**ELECTRICAL  
SITE DETAILS**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN	
PROJECT NO.	20233967.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	MC
DRAWN BY	RLB
CHECKED BY	MC
APPROVED BY	ABB

E-403




Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**ELECTRICAL DETAILS**


TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST., MILLIS, MA 02054

**75% DESIGN**

PROJECT NO.	20233667.002A	<b>E-404</b>
ISSUE DATE	SEPT. 2023	
CURRENT REVISION	-	
DESIGNED BY	MC	
DRAWN BY	RLB	
CHECKED BY	MC	
APPROVED BY	ABB	SHEET 49 of 60




**ELEVATION VIEW**  
NOT TO SCALE




**WIRING DIAGRAM**  
NTS

- NOTE:
- ALL EXPOSED SURFACES OF COMPONENTS SHALL HAVE A YELLOW ENAMEL FINISH, INCLUDING CONDUIT (WITHIN 10'-0" RADIUS OF THE STATION, BOXES, ENCLOSURE AND HORN GRILLE.
  - ALARM STATION TO BE MOUNTED OUTSIDE OF EACH CHEMICAL ROOM CONTAINING A EMERGENCY SHOWER. REFER TO PLAN DRAWINGS FOR EYEWASH JUNCTION BOX LOCATIONS.

**EMERGENCY EYE WASH ALARM STATION**  
NOT TO SCALE




**ELECTRICAL EQUIPMENT STANCHION MOUNTING DETAIL**  
NOT TO SCALE




**CONDUIT STUB-UP**  
NOT TO SCALE

- NOTES:
- ALL CONDUIT INSTALLED IN SLAB SHALL BE PVC SCHEDULE 40 EXCEPT ALL SIGNALS CONDUITS AND VFD MOTOR FEEDERS SHALL BE RIGID STEEL.
  - ALL PVC COATED RIGID STEEL CONDUIT WHICH HAS BEEN FIELD CUT OR DAMAGED SHALL BE SPRAYED OR PAINTED WITH A PVC COATING ACCEPTABLE FOR USE TO REPAIR OR SEAL PVC COATED RIGID STEEL CONDUIT. ONLY MANUFACTURER APPROVED PVC COATING SEALANT SHALL BE ACCEPTABLE.



**CONDUIT PENETRATION EXISTING CONCRETE WALL**  
NOT TO SCALE



**MOTORIZED VALVE MANUAL MOTOR STARTER MOUNTING**  
NOT TO SCALE

**FIRE PROTECTION NOTES**

1. THE WORK COVERED CONSISTS OF FURNISHING ALL LABOR AND MATERIALS NECESSARY TO INSTALL, COMPLETE AND READY FOR CONTINUOUS OPERATION, THE FIRE PROTECTION SYSTEMS, APPARATUS AND EQUIPMENT FOR THIS PROJECT.
2. ALL EQUIPMENT AND MATERIALS FURNISHED UNDER THE FIRE PROTECTION FSB, LABOR AND TESTING PERFORMED HEREIN SHALL BE IN COMPLETE ACCORDANCE WITH THE STATE BUILDING CODE, ALL LOCAL CODES AND REGULATIONS, NATIONAL FIRE PROTECTION ASSOCIATION, INSURANCE REGULATIONS AND REQUIREMENTS GOVERNING SUCH WORK.
3. ANY AND ALL PERMITS REQUIRED FOR INSTALLATION OF ANY MATERIAL SHALL BE OBTAINED AS PART OF THE WORK OF THE SPECIFICATION, INCLUDING ALL FEES OR EXPENSES INCURRED.
4. IT IS THE INTENT OF THESE DOCUMENTS THAT THE ENTIRE BUILDING BE 100% SPRINKLED, INCLUDING ELECTRIC ROOMS.
5. PROVIDE A COMPLETE HYDRAULICALLY CALCULATED SPRINKLER SYSTEM THROUGHOUT THE BUILDING. ALL WORK SHALL BE IN STRICT CONFORMANCE WITH NFPA 13 (2013) AND INCLUDING ALL RULES AND REGULATIONS OF THE LOCAL FIRE DEPARTMENT.
6. SPRINKLERS, PIPING AND THEIR LAYOUT SHOWN ON THE DRAWINGS ARE SCHEMATIC AND ARE SHOWN ON THE DRAWINGS ONLY AS A GUIDE AND AID TO THE CONTRACTOR IN PREPARATION OF THE FABRICATION DRAWINGS. THE SPRINKLERS, PIPING AND THEIR LAYOUT ARE NOT INTENDED TO SHOW EVERY OFFSET AND FITTING. ADDITIONAL OFFSETS AND FITTINGS WILL BE REQUIRED TO BE INSTALLED WHEN COORDINATING WITH ALL TRADES TO AVOID WHERE CONFLICTS MAY OCCUR THAT MAY NOT BE INDICATED ON THE DRAWINGS, SUCH AS, BUT NOT LIMITED TO: BEAMS, COLUMNS, DUCTWORK, LIGHTING, OR PIPING. MODIFICATION TO THE SPRINKLER SPACING WILL BE ALLOWED AT NO COST TO THE PROJECT SUBJECT TO ARCHITECT'S/ENGINEER'S APPROVAL AND CONTINUED COMPLIANCE WITH NFPA 13 (2013).
7. THE FIRE PROTECTION CONTRACTOR SHALL PREPARE WORKING DRAWINGS OF THE SPRINKLER WORK AND OBTAIN APPROVALS FROM THE LOCAL FIRE DEPARTMENT PRIOR TO INSTALLATION.
8. ROUTING OF SPRINKLER MAINS, BRANCHES AND SPRINKLERS SHALL BE THOROUGHLY COORDINATED WITH OTHER TRADES AND THE BUILDING STRUCTURE PRIOR TO SUBMISSION OF COORDINATED SHOP DRAWINGS.
9. SPRINKLERS IN AREAS WITH NO FINISHED CEILING SHALL BE UPRIGHT TYPE, LOCATED AS HIGH AS POSSIBLE, SPRINKLERS SUBJECT TO POTENTIAL PHYSICAL DAMAGE SHALL BE INSTALLED WITH LISTED PROTECTIVE CAGES.
10. SPRINKLERS INSTALLED BELOW SLOPED CEILINGS OR ROOFS, SHALL BE INSTALLED IN STRICT ACCORDANCE TO NFPA 13 (2013) AND SPRINKLER MANUFACTURER'S INSTALLATION LISTING.
11. SPRINKLERS IN AREAS WITH FINISHED CEILING SHALL BE CONCEALED TYPE WITH FACTORY PAINTED COVER PLATES. COVER PLATE COLORS SHALL BE COORDINATED WITH ENGINEER FOR FINAL APPROVAL OF THE COLOR SELECTION.
12. SPRINKLERS SHALL BE LOCATED ABOVE AND BELOW ALL DUCTWORK GREATER THAN 4'-0" IN WIDTH.
13. MISCELLANEOUS DISCREPANCIES OR OMISSIONS WHICH MIGHT APPEAR ON THE DRAWINGS OR IN THE SPECIFICATIONS WILL NOT RELIEVE THE FIRE PROTECTION SUB-CONTRACTOR OF CODE COMPLIANCE.
14. SPRINKLER PIPING SHALL NOT BE INSTALLED TO PASS OVER ELECTRIC PANELS. PROVIDE SHEET METAL PROTECTIVE SHIELDS OVER ELECTRIC PANELS.
15. BACKFLOW PREVENTION DEVICES SHALL BE PROVIDED WITH A HOSE VALVE TEST HEADER ASSEMBLY PIPED TO EXTERIOR OR OTHER ACCEPTED MEANS THAT ALLOWS FOR FULL FLOW TESTING OF SYSTEM DEMAND IN ACCORDANCE WITH NFPA 13 (2013).
16. REFER TO DESIGN CRITERIA FOR SPRINKLER DENSITY AND AREA OF APPLICATION.
17. REFER TO ARCHITECTURAL SECTIONS AND ELEVATIONS FOR EXACT LOCATION OF EXTERIOR PENETRATIONS.

**FIRE PROTECTION DESIGN CRITERIA**

1. FIRE SUPPRESSION CRITERIA
  - A. THE FIRE PROTECTION FSB SHALL MAKE PROVISIONS FOR OBTAINING UPDATED HYDRANT FLOW TEST INFORMATION FOR THIS PROJECT. ANY FLOW TEST INFORMATION NOTED IN THE CONTRACT DOCUMENTS ARE CONSIDERED PRELIMINARY. A NEW FLOW TEST SHALL BE REQUIRED AT THIS CONTRACTOR'S EXPENSE.
  - B. THE FOLLOWING SPRINKLER DESIGN DENSITIES SHALL BE USED FOR SPRINKLER SYSTEM PIPE SIZING:
 

ORDINARY HAZARD OCCUPANCIES GROUP 1

 DESIGNED FOR 0.15 GPM OVER THE MOST REMOTE 1500 SQUARE FEET. MAXIMUM SPACING OF 130 SQUARE FEET PER SPRINKLER, UNLESS NOTED OTHERWISE. INCLUDE 250 GPM FOR INSIDE HOSE STREAM ALLOWANCE AS PART OF THE CALCULATION. MAXIMUM VELOCITIES SHALL NOT EXCEED 20 FEET PER SECOND.
  - C. FIRE PROTECTION SIGNALING SYSTEMS CONTROL EQUIPMENT AND ANNUNCIATOR PANEL ARE SHOWN ON THE ELECTRICAL DRAWINGS.
  - D. THE SPRINKLER LAYOUT SHOWN ON THESE DRAWINGS SHALL BE HYDRAULICALLY CALCULATED. THE RESULTS OF THE HYDRAULIC CALCULATION SHALL SHOW THAT THERE IS SUFFICIENT PRESSURE TO OPERATE THE REQUIRED NUMBER OF SPRINKLERS AT THE MOST REMOTE DESIGN AREAS. PIPE SIZES AND NODE LOCATIONS HAVE BEEN SHOWN ON THE DRAWINGS TO INDICATE DESIGN INTENT.
  - E. THE SPRINKLER CONTRACTOR SHALL FOLLOW THE DESIGN CRITERIA INDICATED ON THE DRAWINGS, BUT WILL BE ALLOWED TO VARY THE PIPE SIZES TO ALLOW FOR COORDINATION AND MINOR CHANGES IN THE PREPARATION.
2. SEQUENCE OF OPERATION
  - A. WET SPRINKLER SYSTEM: THE WET PIPE SYSTEM EMPLOYS AUTOMATIC (CLOSED FUSIBLE LINK) SPRINKLERS ATTACHED TO PIPING CONTAINING WATER UNDER PRESSURE AT ALL TIMES. WHEN A FIRE OCCURS, INDIVIDUAL SPRINKLERS ARE ACTIVATED BY HEAT AND WATER FLOWS IMMEDIATELY. THE FLOW OF WATER RAISES THE ALARM CHECK VALVE CLAPPER FROM ITS SEAT, THIS ALLOWS WATER TO ENTER THE ALARM LINE. THE FLOW SWITCH ON THE ALARM LINE ACTIVATES A LOCAL AUDIBLE ALARM PROVIDING AN ELECTRIC SIGNAL, WHICH IS SENT TO THE FIRE ALARM CONTROL PANEL, THIS SIGNAL IS FORWARDED TO THE LOCAL FIRE DEPARTMENT. A FIRE DEPARTMENT CONNECTION IS CONNECTED TO THE SUPPLY SIDE OF THE SYSTEM FOR USE BY THE LOCAL FIRE DEPARTMENT PUMPER TRUCK.
3. TESTING CRITERIA FOR FINAL ACCEPTANCE
  - A. APPROVAL OF SPRINKLER SYSTEM: THE INSTALLING SPRINKLER CONTRACTOR SHALL:
    - a. NOTIFY THE AUTHORITY HAVING JURISDICTION AND OWNER'S REPRESENTATIVE OF THE TIME AND DATE TESTING WILL BE PERFORMED.
    - b. PERFORM ALL REQUIRED ACCEPTANCE REQUIREMENTS LISTED IN NFPA 13 (2013) HYDROSTATIC TESTS.
    - c. COMPLETE AND SIGN THE APPROPRIATE CONTRACTOR'S MATERIAL AND TEST CERTIFICATES.
  - B. COMPLETE AS-BUILT DRAWINGS AS SPECIFIED.

**FIRE PROTECTION LEGEND**

SYMBOL	ABBREVIATION	DESCRIPTION
—————		ABOVE FLOOR PIPING (INDICATED AS SINGLE LINEWORK)
=====		BELOW FLOOR PIPING (INDICATED AS DOUBLE LINEWORK)
—————		NEW WORK (INDICATED AS HEAVY LINEWORK)
————— F —————	F	FIRE PROTECTION SERVICE MAIN
————— WS —————	WS	WET SPRINKLER SYSTEM
—○—	UP	UP (PENETRATES LEVEL ABOVE)
—→—		RISE (BUT DOES NOT PENETRATE LEVEL ABOVE)
—←—	DN	DOWN (PENETRATES LEVEL BELOW)
—→—		DROP (BUT DOES NOT PENETRATE LEVEL BELOW)
—→—		DIRECTION OF FLOW
—SS—		SHUTOFF VALVE (OUTSIDE SCREW AND YOKE WITH SUPERVISORY SWITCH)
—  —	FDC	FIRE DEPARTMENT CONNECTION
—K—	CV	CHECK VALVE
—H—	DV	DRAIN VALVE WITH HOSE THREADS
—T—	TS	TAMPER SWITCH
—S—	FS	FLOW SWITCH
—P—	PS	PRESSURE SWITCH
—G—	PG	PRESSURE GAUGE
—NIFPC—	NIFPC	NOT IN FIRE PROTECTION CONTRACT
—FPC—	FPC	FIRE PROTECTION CONTRACTOR
—VIV—	VIV	VALVE IN VERTICAL
—RPBP—	RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
—WACV—	WACV	WET ALARM CHECK VALVE
—○—		ISOLATION VALVE W/ TAMPER SWITCH
—●—	CONCEALED	CONCEALED SPRINKLER
—○—	PENDENT	PENDENT SPRINKLER
—○—	UPRIGHT	UPRIGHT SPRINKLER
—○ G —	UPRIGHT	UPRIGHT SPRINKLER W/ PROTECTIVE GUARD
—XXX—		HYDRAULIC CALCULATION NODES
—X—		HYDRAULIC CALCULATION NODES



Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**PLUMBING LEGEND AND GENERAL NOTES**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

**75% DESIGN**

PROJECT NO. 20233667.002A	<b>FP-001</b>
ISSUE DATE SEPT. 2023	
CURRENT REVISION -	
DESIGNED BY RLB	
DRAWN BY RLB	
CHECKED BY JL	
APPROVED BY ABB SHEET	










Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**HVAC LEGEND AND GENERAL NOTES**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

**75% DESIGN**

PROJECT NO.	20233667.002A	<b>H-001</b>
ISSUE DATE	SEPT. 2023	
CURRENT REVISION	-	
DESIGNED BY	RLB	
DRAWN BY	RLB	
CHECKED BY	RHB	
APPROVED BY	ABB	


**SEQUENCE OF OPERATION**

- EF-1 AND IL-1  
INTAKE LOUVER IL-1 SHALL HAVE A DIRECT CONNECTED ACTUATOR. ACTUATOR SHALL BE CONTROLLED AS FOLLOWS:
  - IL-1 LOUVER SHALL OPEN WHEN EF-1 IS SWITCHED ON. WHEN EF-1 IS SWITCHED OF, THE IL-1 DAMPER SHALL CLOSE.
- EF-1:
  - WHEN THE REFRIGERATION MONITOR ENTERS AN ALARM STATE, THE FAN MOTOR OPERATED DAMPER SHALL OPEN. THE DAN MOTOR SHALL START AND RUN AND IL-1 MOTOR OPERATED DAMPER SHALL OPEN. WHEN THE REFRIGERATION MONITOR LEAVES THE ALARM STATE, THE FAN MOTOR SHALL BE STOPPED AND THE FAN MOTOR OPERATED DAMPER AND IL-1 MOTOR OPERATED DAMPER SHALL CLOSE.
  - WHEN A MANUAL WALL SWITCH IS PLACED IN THE "ON" POSITION, THE FAN MOTOR OPERATED DAMPER SHALL OPEN, THE FAN MOTOR SHALL START AND RUN AND IL-1 MOTOR OPERATED DAMPER SHALL OPEN; UNLESS EF-2 BREAKGLASS SWITCH IS ACTIVATED, IN WHICH CASE THE FAN SHALL NOT START AND THE FAN MOTOR OPERATED AND IL-1 MOTOR OPERATED DAMPER SHALL REMAIN CLOSED. WHEN THE MANUAL WALL SWITCH IS PLACED IN THE "OFF" POSITION, THE FAN MOTOR SHALL BE STOPPED AND THE FAN MOTOR OPERATED DAMPER AND IL-1 MOTOR OPERATED DAMPER SHALL CLOSE.
- EF-2:  
FAN SHALL RUN CONTINUOUSLY AND ASSOCIATED MOTOR OPERATED DAMPER SHALL BE OPEN. WALL CAP WITH GRAVITY DAMPER SHALL ALLOW MAKE-UP INTO THE SPACE. WHEN A BREAK GLASS SWITCH IS MOVED TO THE "OFF" POSITION, THE FAN SHALL BE STOPPED, THE MOTOR OPERATED DAMPER SHALL CLOSE AND EF-1/IL-1 SHALL BE STOPPED AND THE ASSOCIATED MOTOR OPERATED DAMPER SHALL CLOSE UNLESS OVERRIDDEN BY THE REFRIGERATION MONITOR. SIGNAGE AT FAN EF-2 SHALL NOTE " FAN EF-2 EMERGENCY STOP"
- EF-3:  
ELECTRICAL ROOM EXHAUST FAN SHALL BE STARTED AND STOPPED BY A WALL MOUNTED THERMOSTAT. ASSOCIATED MOTOR OPERATED DAMPER SHALL CYCLE OPEN AND CLOSED AS APPROPRIATE. A WALL CAP WITH GRAVITY DAMPER SHALL ALLOW AIR INTO THE ROOM TO MAKE-UP THE AIR EXHAUSTED.
- EF-4:  
FAN SHALL BE STARTED AND STOPPED BY ROOM LIGHT SWITCH. A WALL CAP WITH GRAVITY DAMPER SHALL ALLOW AIR INTO THE ROOM TO MAKE-UP THE AIR EXHAUSTED.
- DHU-1 AND ACC-1:  
DEHUMIDIFIER SHALL OPERATE BASED ON INTEGRAL CONTROL SEQUENCES AND TEMPERATURE AND HUMIDITY SENSORS WITHIN THE UNIT CABINET. THE SEQUENCES SHALL MAINTAIN A SPACE TEMPERATURE OF 75° F DRY BULB AND 40% RELATIVE HUMIDITY. DEW POINT TEMPERATURE SHALL BE CONTINUOUSLY MAINTAINED AT 50°. UPON A RISE IN DRY BULB SPACE TEMPERATURE OVER THE SETPOINT OF 75° (ADJ.) THE UNIT SHALL SWITCH INTO COOLING MODE AND ENERGIZE THE REMOTE CONDENSING TO MAINTAIN DRY BULB SPACE TEMPERATURE SETPOINT. UPON DETECTION OF SMOKE VIA A DUCT MOUNTED SMOKE DETECTOR, THE DH SYSTEM SHALL DEENERGIZE AND A SIGNAL SHALL BE SENT TO THE FACP.
- EW-1:  
ELECTRIC WALL HEATER SHALL BY CYCLE FROM AN INTEGRAL THERMOSTAT TO MAINTAIN SPACE TEMPERATURE SETPOINT.
- EUH-1:  
ELECTRIC UNIT HEATER SHALL BY CYCLE FROM THE THERMOSTAT TO MAINTAIN SPACE TEMPERATURE SETPOINT.
- GUH-1 AND GUH-2:  
UNIT HEATERS SHALL FIRE ON LOW STAGE OR HIGH STAGE AS DETERMINED BY A WALL MOUNTED SPACE THERMOSTAT TO MAINTAIN A SPACE TEMPERATURE SETPOINT OF 65° (ADJ.) THE UNIT HEATERS SHALL INCLUDE THE CAPABILITY TO RUN THE UNIT FAN FOR SUMMER VENTILATION WITH NO HEAT.

**GENERAL NOTES**

- HVAC WORK IS INDICATED DIAGRAMMATICALLY. EXACT LOCATIONS OF ALL COMPONENTS ARE TO BE DETERMINED IN THE FIELD AND BY THE ACTUAL BUILDING CONDITIONS. DUCTS, PIPING OR EQUIPMENT INTERFERING WITH OTHER INSTALLATIONS SHALL BE RELOCATED AS REQUIRED AT NO ADDITIONAL COST TO THE OWNER. EXACT LOCATIONS MUST HAVE THE APPROVAL OF THE ARCHITECT.
- ALL WORK SHALL BE COORDINATED WITH ALL OTHER TRADES BEFORE ANY INSTALLATION IS MADE.
- ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH STATE CODES, MANUFACTURER'S APPROVED PUBLISHED LITERATURE, AND AUTHORITIES HAVING JURISDICTION.
- INSTALLATION OF EQUIPMENT SHALL PERMIT ACCESSIBILITY FOR SERVICE AND/ REPAIR OR REPLACEMENT.
- ALL CEILING MOUNTED EQUIPMENT SHALL BE INSTALLED IN SUCH A WAY THAT LIGHTS, PIPING, AND DUCTWORK DO NOT BLOCK ACCESS TO UNITS AND RELATED ACCESSORIES.
- HVAC CONTRACTOR SHALL COORDINATE ALL WALL, CEILING, FLOOR, ROOF AND BEAM PENETRATIONS WITH ARCHITECT AND STRUCTURAL ENGINEER.
- ALL DUCT SIZES SHOWN ARE NET INSIDE CLEAR DIMENSIONS.
- PROVIDE INSTRUMENT TEST HOLES WITH CAPS IN AIR DISTRIBUTION SYSTEMS AS REQUIRED TO BALANCE SYSTEM.
- HVAC CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHEETMETAL TRANSITIONS AT FANS, COILS, AND OTHER SIMILAR HVAC EQUIPMENT.
- ALL MISCELLANEOUS SUPPORTS REQUIRED FOR HVAC EQUIPMENT INSTALLATION SHALL BE PROVIDED BY HVAC SUBCONTRACTOR.
- EXACT LOCATION OF THERMOSTAT TO BE COORDINATED WITH FINAL LOCATION OF WALL MOUNTED ARCHITECTURAL AND ELECTRICAL EQUIPMENT.
- PROVIDE FLEXIBLE DUCT CONNECTIONS ON INTAKES AND DISCHARGES OF ALL AIR HANDLING UNITS.
- COORDINATE DUCT MOUNTED SMOKE DETECTORS WITH ELECTRICAL CONTRACTOR AND -FURNISHED AND WIRED BY THE ELECTRICAL CONTRACTOR, INSTALLED BY THE HVAC CONTRACTOR.
- ALL DUCT AND PIPE PENETRATIONS THROUGH WALLS AND FLOORS SHALL BE SEALED WITH FIRE-STOP PENETRATION SEAL IN ACCORDANCE WITH UL 1479.
- COORDINATE THE DIMENSIONS AND EXACT LOCATION OF THE SUSPENDED STRUCTURAL FRAME WITH THE SUPPORT REQUIREMENTS AND SERVICE ACCESS FOR DH-1.


**EQUIPMENT TAG SYMBOLS & ABBREVIATIONS**



**INSTRUMENTATION**

- Ⓣ HEATING/COOLING THERMOSTAT
- Ⓢ DUCT SMOKE DETECTOR
- Ⓢ SWITCH
- Ⓢⓐ SWITCH WITH BREAK GLASS

**LEGEND/SYMBOLS**



**ABBREVIATIONS**

AFG	ABOVE FINISH GROUND
ACD	AUTOMATIC CONTROL DAMPER
AD	ACCESS DOOR
AFF	ABOVE FINISHED FLOOR
AP	ACCESS PANEL
ARCH	ARCHITECT
ATC	AUTOMATIC TEMPERATURE CONTROL
BDD	BACKDRAFT DAMPER
BTU	BRITISH THERMAL UNIT
BTUH	BTU PER HOUR
BOD	BOTTOM OF DUCT
CAP	CAPACITY
CD	CEILING DIFFUSER
CFM	CUBIC FEET PER MINUTE
CO	CLEANOUT
CP	CONTROL PANEL
DIA	DIAMETER
DB	DRY BULB TEMPERATURE
DDC	DIRECT DIGITAL CONTROL
DN	DOWN
DWG	DRAWING
DX	DIRECT EXPANSION
EA	EXHAUST AIR
EAT	ENTERING AIR TEMPERATURE
EFF	EFFICIENCY
ELV	ELEVATION
ER	EXHAUST REGISTER
ESP	EXTERNAL STATIC PRESSURE
EWT	ENTERING WATER TEMPERATURE
EXH	EXHAUST
FA	FREE AREA
FD	FIRE DAMPER
FLA	FULL LOAD AMPS
FPI	FINS PER INCH
FPM	FEET PER MINUTE
FT	FEET
FTR	FINNED TUBE RADIATION
GAL	GALLONS
GALV	GALVANIZED
GC	GENERAL CONTRACTOR
GPM	GALLONS PER MINUTE
HP	HORSEPOWER
HVAC	HEATING, VENTILATING AND AIR CONDITIONING
HZ	HERTZ
IN	INCHES
KE	KITCHEN EXHAUST
KW	KILOWATTS
LAT	LEAVING AIR TEMPERATURE
LD	LINEAR DIFFUSER
LF	LINEAR FEET
LWT	LEAVING WATER TEMPERATURE
MBH	THOUSANDS OF BTU'S PER HOUR
MCC	MOTOR CONTROL CENTER
NC	NORMALLY CLOSED
NIC	NOT IN CONTRACT
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OAT	OUTSIDE AIR TEMPERATURE
OBD	OPPOSED BLADE DAMPER
OD	OUTSIDE DIAMETER
ø	PHASE
PD	PRESSURE DROP
PRV	PRESSURE REDUCING VALVE
PSI	POUNDS PER SQUARE INCH (GAUGE)
R	RETURN
RA	RETURN AIR
RG	RETURN GRILLE
RM	ROOM
RPM	REVOLUTIONS PER MINUTE
RR	RETURN REGISTER
S	SUPPLY
SA	SUPPLY AIR
SAT	SUPPLY AIR TEMPERATURE
SCT	SATURATED CONDENSING TEMPERATURE
SD	SMOKE DAMPER
SF	SQUARE FEET
SFD	SMOKE/FIRE DAMPER
SP	STATIC PRESSURE
SQ	SQUARE
SR	SUPPLY REGISTER
SST	SATURATED SUCTION TEMPERATURE
STL	STEEL
TYP	TYPICAL
UC	UNDERCUT DOOR
V	VOLTS
VD	VOLUME DAMPER
VFD	VARIABLE FREQUENCY DRIVE
VP	VANDAL PROOF
W/O	WITH
W/O	WITHOUT
WB	WET BULB TEMPERATURE
WG	WATER GAUGE
WMS	WIRE MESH SCREEN

Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE


**SAR** ENGINEERING, INC.  
Mechanical/Electrical Engineers  
150 Crossman Drive, Suite 300  
Billerica, Massachusetts 01824  
617.221.9228  
www.sar.com

**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

0 4' 8'  
SCALE: 1/4" = 1'-0" SCALE IN FEET  
ORIGINAL DRAWING SIZE IS 22 x 34

**HVAC FLOOR PLAN**


TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

**75% DESIGN**

PROJECT NO. 20233667.002A	H-101
ISSUE DATE SEPT. 2023	
CURRENT REVISION -	
DESIGNED BY RLB	
DRAWN BY RLB	
CHECKED BY RHB	SHEET 54 of 60
APPROVED BY ABB	





DEHUMIDIFIER SCHEDULE												
TAG NO.	MANUFACTURER MODEL NO. OR EQUAL	AREA SERVED	TYPE	MOISTURE REMOVAL (LBS/HR)	SENSIBLE COOLING (MBH)	TOTAL COOLING (MBH)	AIRFLOW (CFM)	ELECTRICAL DATA				REMARKS
								MCA	MAX FUSE	VOLT	PHASE	
DHU-1	DESERT AIRE LW-10	FILTER ROOM	CEILING	18.6	80.10	100	6,900	26	40	480	3	①

① PROVIDE HUMIDITY AND TEMPERATURE CONTROLLER TYPICAL TO DESERT AIRE MODEL CA2500 AND R-407C REFRIGERANT.

UNIT HEATER SCHEDULE														
TAG NO.	LOCATION	AIR					MOUNT HEIGHT (FT.)	GAS (PROPANE)		ELECTRICAL DATA			MANUFACTURER MODEL NUMBER	REMARKS
		CFM	HP	THROW (FT)	EAT (°F)	LAT (°F)		INPUT (MBH)	OUTPUT (MBH)	V	PH	HZ		
GUH-1	FILTER ROOM	1,090	1/3	40	50	110	-	75	61.5	120	1	60	MODINE HDC-75	①②③
GUH-2	FILTER ROOM	1,090	1/3	40	50	110	-	75	61.5	120	1	60	MODINE HDC-75	①②③

- ① PROVIDE TWO STAGE GAS VALVE WITH INTERMITTENT PILOT CONTROL, 100% SHUTOFF WITH CONTINUOUS RETRY.  
 ② PROVIDE NATURAL GAS TO PROPANE GAS CONVERSION KIT.  
 ③ PROVIDE WITH SIDEWALL TERMINATION KIT

ELECTRIC HEATER SCHEDULE									
TAG NO.	LOCATION	CAPACITY		FAN DATA				MANUFACTURER MODEL NUMBER	REMARKS
		KW	CFM	V	PH	HZ			
EUH-1	ELECTRIC ROOM	3.0	350	480	3	60	QMARK MUH0341		
EWH-1	BATHROOM	1.5	-	120	1	60	QMARK CWH1151DSF		

REMOTE CONDENSER SCHEDULE										
TAG NO.	MANUFACTURER MODEL NO. OR EQUAL	REFRIG TYPE	AMBIENT TEMP. (°F)	FANS QTY	ELECTRICAL DATA				REMARKS	
					MCA	MOPD	VOLTS	PHASE		
ACC-1	DESERT AIRE RC5S079	R-407C	95	3	-	15	480	3		

FAN SCHEDULE													
TAG NO.	SERVICE	FAN TYPE	CFM	ESP (IN WC)	SPEED (RPM)		ELECTRICAL DATA				MANUFACTURER & MODEL NUMBER	REMARKS	
					FAN	MOTOR	HP	V	PH	HZ			
EF-1	PFAS AREA	WALL MOUNTED DOME	1400	0.50	1411	1725	1/2	120	1	60	GREENHECK CUE-120-VG	①②③	
EF-2	CHEMICAL AREA	WALL MOUNTED DOME	300	0.50	1662	1725	1/10	120	1	60	GREENHECK CUE-80-VG	①②③	
EF-3	ELECTRICAL ROOM	INLINE CABINET	500	0.50	1411	1725	1/2	120	1	60	GREENHECK CSP-A510-VG	①②③	
EF-4	BATHROOM/JANITOR	INLINE CABINET	150	0.50	1221	1350	32W	120	1	60	GREENHECK CSP-A360-VG	①②③	

- ① PROVIDE THERMAL OVERLOAD MOTOR AND STAINLESS STEEL BIRDSCREEN.  
 ② PROVIDE MOTOR COVER/BELT GUARD, TEFC FAN MOTOR, INLET FLEX DUCT CONNECTION, AND OUTLET WIRE MESH SCREEN.  
 ③ ECM MOTOR




Signed By: --- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**HVAC SCHEDULES AND DETAILS**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN

PROJECT NO. 20233667.002A

ISSUE DATE SEPT. 2023

CURRENT REVISION -

DESIGNED BY RLB


DRAWN BY RLB

CHECKED BY RHB


APPROVED BY ABB

H-200


SHEET 55 of 60




6 DX PIPE SUPPORT DETAIL  
NO SCALE




5 GAS VENT DETAIL  
NO SCALE




4 SECTION A  
NO SCALE



1 DRAIN PAN WATER SEAL PIPING DETAIL  
NO SCALE



2 LOUVER/PLENUM CONNECTION DETAIL  
NO SCALE



3 ACCU MOUNTING DETAIL  
NO SCALE

X=-NEGATIVE INTERNAL STATIC PRESSURE AT FAN INLET

- NOTES:  
 1. ALLOW SUFFICIENT SPACE BELOW DRAIN PAN FOR TRAP  
 2. PITCH DRAIN FOR PROPER RUN-OFF  
 3. MANUALLY PRIME FILL TRAP BEFORE START-UP TO FORM INITIAL DRAIN SEAL  
 4. SUPPORT LENGTHY DRAIN LINES TO PREVENT SAG AND CONDENSATE OVERFLOW

- NOTES:  
 1. BLOCK UNUSED PORTION OF LOUVER WITH 4" THICK INSULATED METAL PANEL.  
 2. SEE ARCHITECTURAL PLANS FOR LOUVER INSTALLATION DETAIL.

## PLUMBING NOTES:

- THE WORK COVERED CONSISTS OF FURNISHING ALL LABOR AND MATERIALS NECESSARY TO INSTALL, COMPLETE AND READY FOR CONTINUOUS OPERATION, THE PLUMBING SYSTEMS, APPARATUS AND EQUIPMENT FOR THIS PROJECT.
- ALL EQUIPMENT AND MATERIALS FURNISHED UNDER THE PLUMBING SUB-CONTRACT, LABOR AND TESTING PERFORMED HEREIN SHALL BE IN COMPLETE ACCORDANCE WITH THE STATE BUILDING CODE, LOCAL FUEL GAS AND PLUMBING CODES, ALL LOCAL CODES AND REGULATIONS, NATIONAL FIRE PROTECTION ASSOCIATION, INSURANCE REGULATIONS AND REQUIREMENTS GOVERNING SUCH WORK.
- ANY AND ALL PERMITS REQUIRED FOR INSTALLATION OF ANY MATERIAL SHALL BE OBTAINED AS PART OF THE WORK OF THE SPECIFICATION INCLUDING ALL FEES OR EXPENSES INCURRED.
- WHERE WATER PIPING IS SHOWN DROPPING INTO PLUMBING CHASES WITH SIZES NOTED, THAT SIZE SHALL BE CARRIED FULL LENGTH THROUGH THE CHASE. REFER TO PLUMBING FIXTURE SCHEDULE ON THIS DRAWING FOR INDIVIDUAL FIXTURE CONNECTION SIZES.
- UNLESS OTHERWISE NOTED, ALL HORIZONTAL DRAINAGE PIPING WHICH IS 3" OR LESS IN DIAMETER SHALL PITCH OF NOT LESS THAN 1/4" PER FOOT AND ALL HORIZONTAL DRAINAGE PIPING WHICH IS 4" OR LARGER IN DIAMETER SHALL PITCH OF NOT LESS THAN 1/8" PER FOOT.
- ALL BELOW FLOOR PIPING THAT INTERSECTS A GRADE BEAM REQUIRES COORDINATION WITH STRUCTURAL FOR STRUCTURAL DETAILS, REFER TO STRUCTURAL DRAWINGS.
- PROVIDE ALL FLOOR CLEANOUTS WITH HUB AND SPIGOT; LEAD AND OAKUM JOINTS FROM CLEANOUT TO AND INCLUDING CONNECTION TO SANITARY OR STORM DRAIN.
- REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATION OF ALL PLUMBING FIXTURES AND EQUIPMENT.
- ALL BURIED DOMESTIC WATER PIPING, TEMPERED WATER PIPING OR AIR PIPING SHALL BE SOFT ROLLED "K" COPPER COIL AND BE PROTECTED WITH A HIGH DENSITY RUBBER INSULATION. FITTINGS SHALL NOT BE PERMITTED IN OR UNDER SLAB. PROVIDE SLAB PENETRATIONS WITH SLEEVE AND FIRE STOPPING.
- INTERIOR PLUMBING AND HVAC EQUIPMENT REQUIRING A LP GAS CONNECTION SHALL BE PROVIDED WITH AN EMERGENCY GAS RELIEF VENT AT EACH GAS TRAIN IN ACCORDANCE WITH THE MASSACHUSETTS FUEL GAS CODE AND AS INDICATED WITH THE FOLLOWING CHART:

CFH	AMOUNT OF RELIEF VENTS REQUIRED	SIZE OF EACH RELIEF VENT		
		0' TO 40'	0' TO 100'	0' TO 200'
UNDER 1,000 CFH	1	3/4"	1"	1 1/4"
1,000 CFH TO 2,500 CFH	3	3/4"	1"	1 1/4"
2,500 CFH TO 12,500 CFH	3	3/4"	1"	1 1/4"
OVER 12,500 CFH	4	3/4"	1"	1 1/4"

- MISCELLANEOUS DISCREPANCIES OR OMISSIONS WHICH MIGHT APPEAR ON THE PLANS OR SPECIFICATIONS WILL NOT RELIEVE THE PLUMBING SUB-CONTRACTOR OF CODE COMPLIANCE.
- ALL FLOOR DRAINS SHALL BE PROVIDED WITH A TRAP PRIMER CONNECTION. THIS CONTRACTOR SHALL PROVIDE ALL ASSOCIATED EQUIPMENT NECESSARY TO PROVIDE A COMPLETE SYSTEM INCLUDING AN ELECTRONICALLY OPERATED PRIMING MANIFOLD AND ALL ASSOCIATED PIPING REQUIRED.
- GAS FIRED EQUIPMENT - PROVIDE FULL SIZE SOV AND DRIP LEG IN ACCESSIBLE LOCATION. MAKE FINAL CONNECTION TO EQUIPMENT WITH NECESSARY REDUCER AND UNION CONNECTION. PC TO COORDINATE EXACT CONNECTION SIZE, LOAD, LOCATION, AND EQUIPMENT ACCESS NEEDS PRIOR TO GAS INSTALLATION.

## PLUMBING FIXTURE SCHEDULE

DESIGNATION	FIXTURE DESCRIPTION	CONNECTION SIZE					REMARKS
		CW	HW	TW	S/W	V	
ES-1	EMERGENCY SHOWER/EYEWASH	-	-	1-1/4"	-	-	GUARDIAN G1950 - SEE NOTE 1 - SEE NOTE 7
WC-1	WATER CLOSET - FLOOR MTD.	1"	-	-	4"	2"	SEE SPECIFICATION
LAV-1	LAVATORY	1/2"	1/2"	-	2"	2"	SEE SPECIFICATION
JS-1	JANITOR SINK	3/4"	3/4"	-	3"	2"	SEE SPECIFICATION
TMV	THERMOSTATIC MIXING VALVE	-	-	1-1/4"	-	-	LAWLER MODEL 911E - SEE NOTE 3
HB	HOSE BIBB	1/2"	-	-	-	-	INTEGRAL VACUUM BREAKER W/ VANDAL RESISTANT "T" HANDLE KEY - SEE NOTE 2
WH	WALL HYDRANT	1/2"	-	-	-	-	NON-FREEZE, QUARTER TURN, INTEGRAL VACUUM BREAKER W/ VANDAL RESISTANT "T" HANDLE KEY - SEE NOTE 2
FD	FLOOR DRAIN	-	-	-	2"	2"	SEE SPECIFICATION. PROVIDE WITH TRAP PRIMER.

### NOTES:

- PROVIDE FLOW SWITCH WITH SINGLE POLE, DOUBLE THROW CONTACTS, AND 20 GPM BALANCING REGULATOR (G6040).
- MOUNT FIXTURE 4-0" AFF
- PROVIDE DIAL THERMOMETER ON INLETS.
- ALL EXPOSED VALVES, PIPING AND FITTINGS SHALL BE CHROME PLATED.
- PLUMBING CONTRACTOR SHALL PROVIDE EACH CONNECTION TO EACH SINK OR PIECE OF EQUIPMENT WITH ITS OWN INDIVIDUAL SHUTOFF VALVE
- PROVIDE 90° ELBOW FOR EYEWASH DRAIN OUTLET TO DRAIN DIRECT ON FLOOR.

## GAS FIRED TANKLESS WATER HEATER SCHEDULE

TAG NO.	MANUFACTURER AND MODEL NO.	MAX INPUT (MBH)	CONTINUOUS FLOW RATE (GPM) AT 80° RISE	FLUE SIZE (IN.)	OUTLET TEMP SETTING (° F)	REMARKS
TWH-1	NORITZ MODEL NC380	380	7.8	6	120	LP GAS, INSTALL PER MANUFACTURER'S INSTRUCTIONS FOR MULTI-UNIT INSTALLATION

## PLUMBING LEGEND

SYMBOL	ABBREVIATION	DESCRIPTION
—		ABOVE FLOOR PIPING (INDICATED AS SINGLE LINEWORK)
==		BELOW FLOOR PIPING (INDICATED AS DOUBLE LINEWORK)
— — —		NEW WORK (INDICATED AS HEAVY LINEWORK)
---	CW	COLD WATER
----	HW	HOT WATER
- - - - -	HWR	HOT WATER RECIRCULATION
— TW —	TW	TEMPERED WATER
-----	S/W	SANITARY DRAINAGE (SOIL/WASTE)
-----	FLUE	FLUE EXHAUST
— G —	G	GAS (LIQUID PROPANE)
○	UP	UP (PENETRATES LEVEL ABOVE)
↓	DN	DOWN (PENETRATES LEVEL BELOW)
↓	DP	DROP (BUT DOES NOT PENETRATE LEVEL BELOW)
→ 0.1		DIRECTION OF FLOW
→		DIRECTION & DESIGNATION OF SLOPE (IN FT/FT)
—		SHUTOFF VALVE
—	BVA	BALANCING VALVE ASSEMBLY
—	CV	CHECK VALVE
—	PRV	PRESSURE REDUCING VALVE
—	DV	DRAIN VALVE WITH HOSE THREADS
—		GAS SHUTOFF VALVE
—	PG	PRESSURE GAUGE
—	SA	SHOCK ABSORBER
—	CO	CLEANOUT
—	WCO	WALL CLEANOUT
—	FCO	FLOOR CLEANOUT
—	FD	FLOOR DRAIN
—	HB	HOSE BIBB
—	WH	WALL HYDRANT
—	NIPC	NOT IN PLUMBING CONTRACT
—	PC	PLUMBING CONTRACTOR
—	NO	NORMALLY OPEN
—	NC	NORMALLY CLOSED
—	INV	INVERT ELEVATION
—	CFH	CUBIC FEET PER HOUR
—	W&T	WASTE & TRAP
—	VIV	VALVE IN VERTICAL
—	OED	OPEN END DRAIN
—	VTR	VENT THRU ROOF
—	CC	CAPPED CONNECTION
—	UN	UNION
—	ST	STRAINER
—	WTS	WATER TIGHT SLEEVE
—	P=	PLUMBING FIXTURE DESIGNATION
—	WM	WATER METER
—	RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
—	TWH	TANKLESS WATER HEATER
—	FFE	FINISHED FLOOR ELEVATION
—	LPC	LIMIT PLUMBING CONTRACT
—	TDL	TOTAL DEVELOPED LENGTH
—		EMERGENCY SHOWER/EYE WASH STATION
—		EMERGENCY SHOWER STATION

## SHOCK ABSORBER SCHEDULE\*

PDI RATING SYMBOL	A	B	C	D	E
PRECISION PLUMBING PRODUCTS	SC-500	SC-750	SC-1000	SC-1250	SC-1500
WATTS REGULATOR COMPANY	0750030	0750053	0750060	0750070	0750090
WADE	S-P	10-P	20-P	50-P	75-P

\* MANUFACTURERS NAMES AND MODEL NUMBERS ARE SHOWN ONLY TO REPRESENT TYPE, STYLE AND LEVEL OF QUALITY EXPECTED, SIMILAR PRODUCTS BY OTHER MANUFACTURERS WILL BE ACCEPTABLE.



Signed By: --- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



### SCALE VERIFICATION

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING


0 1"

IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

### PLUMBING LEGEND AND GENERAL NOTES

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

### 75% DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	RLB
DRAWN BY	RLB
CHECKED BY	JL
APPROVED BY	ABB

P-001

SHEET 56 of 60






Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SCALE VERIFICATION**  
 THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
  
 IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

0 4' 8'  
 SCALE: 1/4" = 1'-0" SCALE IN FEET

ORIGINAL DRAWING SIZE IS 22 x 34

**PLUMBING  
SITE PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054

75% DESIGN

PROJECT NO. 20233667.002A	P-002
ISSUE DATE SEPT. 2023	
CURRENT REVISION -	
DESIGNED BY RLB	
DRAWN BY RLB	
CHECKED BY JL	
APPROVED BY ABB	SHEET 57 of 60


**OWNER:**  
 N/F TOWN OF MILLIS  
 PARCEL 0028-0016 0000

**SITE PLAN:**  
 SCALE: 1" = 10'




Signed By: ---- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE



**SAR** ENGINEERING, INC.  
Mechanical/Electrical Engineers  
150 Grossman Drive, Suite 300  
Burlington, Massachusetts 02184  
617 221-9228  
www.sar.com

**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



ORIGINAL DRAWING SIZE IS 22 x 34

**PLUMBING UNDERGROUND FLOOR PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054


75% DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	RLB
DRAWN BY	RLB
CHECKED BY	JL
APPROVED BY	ABB

P-100



REV	DESCRIPTION	DSN DWN	CHK APP	DATE




**SWR** ENGINEERING, INC.  
Mechanical/Electrical Engineers  
159 Crossman Drive, Suite 309  
Bellingham, Massachusetts 02184  
617 221-9228  
www.swr.com

**SCALE VERIFICATION**

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING

0 1"


IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



ORIGINAL DRAWING SIZE IS 22 x 34

**PLUMBING FLOOR PLAN**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN



TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST., MILLIS, MA 02054

**75% DESIGN**

PROJECT NO.	20233967.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	RLB
DRAWN BY	RLB
CHECKED BY	JL
APPROVED BY	ABB

P-101

Signed By: --- # 12345

REV	DESCRIPTION	DSN DWN	CHK APP	DATE

**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

ORIGINAL DRAWING SIZE IS 22 x 34

**PLUMBING DETAILS**

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 PFAS WTP FINAL DESIGN




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION  
900 MAIN ST, MILLIS, MA 02054


75% DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	SEPT. 2023
CURRENT REVISION	-
DESIGNED BY	RLB
DRAWN BY	RLB
CHECKED BY	JL
APPROVED BY	ABB

P-200




**1 WATER METER ASSEMBLY DIAGRAM**  
NOT TO SCALE




**2 REDUCED PRESSURE BACKFLOW PREVENTER**  
NOT TO SCALE


PIPE SIZE	INSULATION SHIELD LENGTH (X")			GAUGE
	1/2"	3/4"	1"	
1/2" TO 3"	12"	12"	12"	18
4"	12"	12"	12"	16
5"	18"	18"	18"	16
6"	18"	18"	18"	16
8" TO 14"	24"	24"	24"	14



**3 PIPE AND HANGER SHIELD DETAIL**  
NOT TO SCALE





**4 TRAP PRIMER DETAIL**



**5 TANKLESS GAS FIRED WATER HEATER DIAGRAM**  
NOT TO SCALE





OWNER:  
N/F TOWN OF MILLIS  
PARCEL 0028-0046-0000  
(NO DEED REF. FOUND)  
(PLAN NO. 377 OF 1973)

Now or Formerly  
DOMENIC J. TIBERI ETUX  
PARCEL 0028-0025-0000  
(Book 33903 Page 340)  
(Plan No. 519 of 1989, Lot 1)

24' WIDE EASEMENT  
FOR ROAD (APPROX. LOC.)  
(PLAN NO. 377 OF 1973)

Now or Formerly  
BRENDA J. WHELAN REALTY  
TRUST  
PARCEL 0028-0041-0000  
(Book 11874 Page 403)  
(Plan No. 142 of 1997, Lot 3)

OWNER OF RECORD:  
TOWN OF MILLIS  
NO DEED REFERENCE FOUND  
PLAN No. 377 OF 1973  
PARCEL 0028-0046-0000  
BIRCH STREET

**LEGEND**

- ⊕ WATER MANHOLE
- ⊕ HYDRANT
- ⊕ WATER SHUT OFF/WATER GATE
- ⊕ GUY WIRE
- ⊕ UTILITY POLE
- ⊕ BOLLARD
- ⊕ ELECTRIC METER
- ⊕ GATE POST
- ⊕ CHAIN LINK FENCE W/BARBED WIRE
- CONC CONCRETE
- ENT ENTRANCE
- GEN GENERATOR
- G GAS
- OHW OVERHEAD WIRES
- W WATER
- 12" C.I. PIPE SIZE AND MATERIAL
- C.I. CAST IRON
- D.I. DUCTILE IRON
- HDPE HIGH-DENSITY POLYETHYLENE
- X METAL FENCE
- ⊕ METAL GATE
- ⊕ TREELINE
- DSE DIGSAFE ELECTRIC
- DSG DIGSAFE GAS
- DSW DIGSAFE WATER
- WETLANDS
- SOIL PROBES
- WETLAND FLAG

OWNER:  
N/F TOWN OF MILLIS  
PARCEL 0028-0046-0000  
(NO DEED REF. FOUND)  
(PLAN NO. 377 OF 1973)

- NOTES:**
- THE TOPOGRAPHY, SITE DETAIL, AND SURFACE IMPROVEMENTS DEPICTED HEREON WERE OBTAINED FROM AN ON-THE-GROUND INSTRUMENT SURVEY CONDUCTED BY BRENNAN CONSULTING, INC ON SEPTEMBER 1, 2022, SEPTEMBER 6, 2022 AND JULY 20, 2023.
  - PROPERTY AND EASEMENT LINES SHOWN HEREON ARE PER MassGIS AND SHOULD NOT BE USED AS A DETERMINATION OF BOUNDARY.
  - THE HORIZONTAL DATUM IS BASED ON THE MASSACHUSETTS COORDINATE SYSTEM, NAD83, MAINLAND ZONE AS DERIVED FROM GPS OBSERVATIONS.
  - THE VERTICAL DATUM IS BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) AS DERIVED FROM GPS OBSERVATIONS.
  - BENCH MARK INFORMATION:  
TBM: BREN-1: BENCH TIE SPIKE SET IN UTILITY POLE AT WELL BUILDING AS SHOWN HEREON.  
ELEVATION = 124.79  
TBM: BREN-2: X-CUT ON HYDRANT BONNET NUT AS SHOWN HEREON.  
ELEVATION = 125.29
  - CONTOUR INTERVAL EQUALS ONE (1) FOOT.
  - UTILITIES SHOWN HEREON ARE BASED UPON OBSERVED ABOVE GROUND EVIDENCE. BURIED UTILITY LINES SHOWN HEREON ARE BASED UPON MARKS ON THE GROUND AND RECORD PLANS PROVIDED BY THE TOWN OF MILLIS.
  - WETLANDS SHOWN HEREON WERE DELINEATED BY LEAH BASBANES ON JULY 19, 2023.

I HEREBY CERTIFY THAT THIS PLAN IS BASED ON AN ACTUAL FIELD SURVEY.


*[Signature]*  
PROFESSIONAL LAND SURVEYOR

07/25/2023  
DATE



**REVISIONS**

NO.	DATE	DESCRIPTION	BY	CHK'D
1	7/24/23	ADDED WETLAND DELINEATION	CLR	PBO



**EXISTING CONDITIONS PLAN**  
**MILLIS VILLAGE STREET**  
**TREATMENT FACILITY / WELL 3**  
**MILLIS, MASSACHUSETTS**  
**(NORFOLK COUNTY)**

PREPARED FOR  
KLEINFELDER

SCALE: 1" = 20'      DATE: SEPTEMBER 14, 2022

**Brennan Consulting**  
ENGINEERING TRANSPORTATION SURVEYING  
24 RAY AVENUE, BURLINGTON, MA  
PHONE: (781) 273-3434 WWW.BRENNANCONSULTS.COM

FIELD CHIEF: JT	APPROVED: CE	PM: PBO	SHEET NO. 1 OF 1
RESEARCH: PBO	COMP: PBO	CADD: PBO	JOB NO. 21169-1

P: 21169-1-A Well 3 Wetland Survey, Millis - Kleinfelder Survey/Map/Plan, Worksheet V21169-1A.dwg



**ATTACHMENT E**  
**Stormwater Report**

---





# MEMORANDUM

TO: Town of Millis Conservation Commission  
FROM: Greg Avenia, P.E., Kleinfelder  
DATE : October 2023  
SUBJECT: Millis Well 3 PFAS Treatment Facility Design, Village Street, Millis, MA 02054  
CC: Tyler Bernier, P.E., Kleinfelder

---

This Stormwater Management Report has been prepared to show compliance with the Massachusetts Stormwater Management Standards to support the Project's Notice of Intent Application.

The Town of Millis is proposing the installation of a 70' x 45' PFAS treatment facility to support Well 3 off Village Street in Millis, MA. The proposed development will also include the installation of above-ground backwash storage tanks, associated utilities including a tight tank sewer system, a paved driveway and an infiltration basin.

## 1 EXISTING DRAINAGE CONDITIONS

The proposed site is adjacent to the existing Well 3 facilities, southwest along the existing gravel driveway. The intersection of the gravel driveway and Birch Street is approximately 1,500 feet to the southwest. Under existing conditions, the proposed 31,581 square-foot site is mostly wooded. Wooded area borders the site to the south, the gravel driveway and wetland to the west, existing Well 3 infrastructure to the north, and a grassed field to the east past a loop in the gravel driveway.

The entirety of the site is within the Charles River watershed. Stormwater drains in two directions from a high point to the southeast of the proposed site. Approximately half of the site drains to the wetlands to the northwest, with the rest draining towards Maple Swamp located to the east. Both wetlands ultimately connect to the Charles River.

## 2 PROPOSED DRAINAGE CONDITIONS

Stormwater flows will emulate existing drainage conditions to the maximum extent possible, however a portion of the site that currently drains to the wetlands west of the site has been rerouted to the east to maximize water quality and quantity treatment via the proposed infiltration basin. Kleinfelder estimates that the proposed development will create approximately 7,510 square feet of new impervious area, comprised of the proposed treatment building, paved driveway, and concrete pad for above-ground backwash storage tanks. The existing chemical feed building will be demolished down to existing grade and the equipment will

be relocated to the new treatment facility. The working area of the site will be graded to emulate existing drainage patterns in slopes ranging from 1% to approximately 5%. Proposed grades will be tied into existing grade at a maximum of 3:1 H:V slopes.

A stormwater swale along the existing gravel drive will capture the majority of runoff coming from the proposed building roof, the paved access drive, and concrete pad. The swale will direct stormwater to the proposed infiltration basin to the north of the site via an 8-inch pipe. Stormwater from the rear of the building will be directed to the proposed basin by a berm. The project site has been located and designed so that the impact within the 100-foot wetland buffer and 100-year flood zone are minimized to the maximum extent possible.

### 3 HYDROLOGIC ANALYSIS

A HydroCAD hydrologic analysis was performed under both existing and proposed conditions. Each model was analyzed for the 1, 2, 5, 10, 25, and 100-year storm events. Rainfall data was acquired from the Precipitation Frequency Data Server maintained by NOAA. The total watershed for the site was measured to be approximately 0.65 acres. Stormwater flow comes from an existing high point southeast of the project site and flows to the wetland to the west or to Maple Swamp to the east.

The soil data used for this analysis was acquired via the Web Soil Survey, provided by NRCS. Within the project site, areas not classified as water or impervious areas are generally hydrologic soil group A. Soils on the site are classified as very sandy loams and loamy sands.

For analysis of existing conditions, the site was divided into two main sub-watershed areas separated by a natural high point that extends across the project area, effectively dividing the site in half.

- SC-1 is approximately 24,786 square feet in area. It represents the western portion of the site and is comprised of woods in good conditions, unconnected impervious area, such as building roofs and tank concrete pads, and gravel access road. Stormwater drains across the access drive to the wetland west of the site.
- SC-2 is approximately 19,349 square feet in area. It encompasses the eastern portion of the site and drains to the east toward Maple Swamp. Ground cover in this area is entirely woods in good condition.

Under proposed conditions, the site was separated into five sub-watershed areas based on proposed drainage features and grading.

- SC-1 is approximately 3,356 square feet in area. It represents a portion of the site driveway that drains to the west before being captured by the proposed stormwater system. Ground cover in this area includes paved surfaces, gravel access drive, and grassed area.
- SC-2 is approximately 11,864 square feet in area. It encompasses most of the developed area of the site that flows to the west. Ground cover includes paved surface, concrete pads, building roofs, and



grassed area. Stormwater from this area is captured by the proposed stormwater system and routed to an infiltration basin.

- SC-3 is approximately 9,595 square feet in area. This subcatchment area includes areas of direct flow from the north and east sides of the site into the infiltration basin. Ground cover includes grassed areas and the area of the infiltration basin, classified as water surface area.
- SC-4 is approximately 7,531 square feet in area. This encompasses the backside of the berm on the east side of the proposed infiltration basin, pressure relief outlet, and woods extending to the gravel road surrounding the site. Ground cover in this area is classified as a wood/grass combination.
- SC-5 is approximately 11,789 square feet in area. This represents the area on the west side of the site that is not captured by the stormwater system and flows directly to the western wetland. The ground cover in this area includes the existing well 3 building, the existing gravel access drive, and grassed area.

The watershed area has been standardized between the two analyses to allow direct comparison of the impact of the proposed development. Both models include two design points that are used to analyze and compare stormwater flow rates and volumes.

- Design Point 1, or “DP-1” represents the wetlands to the west of the project site.
- Design Point 2, or “DP-2” represents outflow from the project site to the east, ultimately into Maple Swamp.

#### 4 MASSACHUSETTS DEPARTMENT OF ENVIRONMENTAL PROTECTION (MASSDEP) – STORMWATER MANAGEMENT STANDARDS

As demonstrated below, the proposed Project complies with the MassDEP Stormwater Management Standards (the Standards) to the maximum extent practicable. Under the Stormwater Management Standards, the Project is considered a new develop project because it involves the construction of a new drinking water treatment facility. The Project has been designed to meet the Stormwater Management Standards to the maximum extent practicable and to improve upon existing conditions.

##### 4.1 STANDARD 1: NO NEW UNTREATED DISCHARGES

*No new stormwater conveyance (e.g., outfalls) may discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth.*

No change:

The Project has been designed to comply with Standard 1. Under existing conditions, there are no existing outfalls within the project area and no best management practices in place; runoff currently flows overland directly from the site to the wetlands to the west, or to Maple Swamp to the east. Under proposed conditions, a portion of the stormwater originally destined to flow from the site to the western wetlands will be intercepted by a proposed swale and rerouted to the proposed infiltration basin. On the eastern portion of the site, a berm will redirect runoff toward the proposed basin. No untreated discharges are proposed.

- A stone gabion basket weir is proposed to create a sediment forebay within the proposed infiltration basin to provide the required pretreatment.
- The infiltration basin will provide primary water quality treatment for this development. The basin has been sized to accommodate the 100-year 24-hour storm event for areas that drain to it. An emergency overflow weir with riprap erosion protection is proposed as a precautionary measure.

#### 4.2 STANDARD 2: PEAK RATE ATTENUATION

*Stormwater management systems shall be designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates. This Standard may be waived for discharges to land subject to coastal storm flowage as defined in 310 CMR 10.04.*

**Standard Met:**

The Project has been designed to comply with Standard 2. The infiltration basin on the north side of the site will receive all the runoff from the impervious area added as a result of the development. The existing access road will be regraded near the proposed stormwater swale on the western side of the site to capture the maximum amount of runoff practicable. Areas that are not paved will be loamed and seeded at the end of construction.

A HydroCAD analysis was performed on both existing and proposed conditions, attached under **Appendix C**. A summary of this analysis in relation to standard 2 is below:

**TABLE 1: PEAK FLOWS AT DESIGN POINT 1**

Design Storm	Existing Peak Flow (cfs)	Proposed Peak Flow (cfs)
1-Year	0.62	0.41
2-Year	0.77	0.51
5-Year	1.02	0.67
10-Year	1.23	0.81
25-Year	1.51	1.01
100-Year	1.95	1.38

**TABLE 2: PEAK FLOWS AT DESIGN POINT 2**

Design Storm	Existing Peak Flow (cfs)	Proposed Peak Flow (cfs)
1-Year	0.00	0.00
2-Year	0.00	0.00
5-Year	0.00	0.00
10-Year	0.00	0.00
25-Year	0.01	0.00
100-Year	0.07	0.05

The post-development peak rates are equal to or less than the peak rates under existing conditions for all the analyzed storm events.



#### 4.3 STANDARD 3: STORMWATER RECHARGE

*Loss of annual recharge to groundwater shall be eliminated or minimized through the use of environmentally sensitive site design, low impact development techniques, stormwater management practices and good operation and maintenance. At a minimum, the annual recharge from the post-development site shall approximate the annual recharge from pre-development conditions based on soil types. This Standard is met when the stormwater management system is designed to infiltrate the required recharge volume as determined in accordance with the Massachusetts Stormwater Handbook.*

Standard Met:

The Project has been designed to comply with Standard 3. The proposed infiltration basin has 5,937 cubic feet of storage and can infiltrate the 100-year storm event for most of the project site. The required recharge volume calculation is included below.

**TABLE 3: IMPERVIOUS AREA SUMMARY FOR STANDARD 3**

<b>Existing Impervious Area (sq. ft)</b>	<b>Proposed Impervious Area (sq. ft)</b>	<b>Change (sq. ft)</b>
894	8,404	+7,510

The project site is surrounded by Hydrologic Soil Group A soils. Per the Massachusetts Stormwater Handbook, a recharge rate of 0.6 inches (0.05 feet) shall be used for all impervious area in areas with Hydrologic Soil Group A, the highest recharge rate outlined in the definition of Standard 3. When this rate is applied to the proposed additional impervious area of 0.18 acres or 7,753 square feet, the required recharge volume associated with this impervious area is calculated to 646 cubic feet. The proposed stormwater management system can store and infiltrate more than this required volume. See Appendix E for stormwater storage calculations.

#### 4.4 STANDARD 4: WATER QUALITY

*Stormwater management systems shall be designed to remove 80% of the average annual post-construction load of Total Suspended Solids (TSS). This Standard is met when:*

- a) Suitable practices for source control and pollution prevention are identified in a long-term pollution prevention plan, and thereafter are implemented and maintained.*
- b) Structural stormwater best management practices are sized to capture the required water quality volume determined in accordance with the Massachusetts Stormwater Handbook; and*
- c) Pretreatment is provided in accordance with the Massachusetts Stormwater Handbook.*

Standard Met:

The Project has been designed to comply with Standard 4. The project ultimately discharges to the Charles River (MA 72-05), a class 5 waterbody per Massachusetts 2022 Integrated List of Waters.

Table 3 shows the stormwater treatment provided for the proposed development. Water Quality Volumes were calculated for the first 1.0” of runoff per the Massachusetts Stormwater Handbook new development standards.

**TABLE 4: REQUIRED WATER QUALITY VOLUME (WQV) AT DESIGN POINT 1**

<b>Watershed</b>	<b>Area</b>	<b>Required WQV</b>	<b>Provided WQV</b>
Existing Total Impervious Area	894 sf	0 cf*	0 cf
Proposed New Impervious Area (in addition to existing)	-354 sf	0 cf	

\*To Max. Extent Practicable

**TABLE 5: REQUIRED WATER QUALITY VOLUME (WQV) AT DESIGN POINT 2**

<b>Watershed</b>	<b>Area</b>	<b>Required WQV</b>	<b>Provided WQV</b>
Existing Total Impervious Area	0 sf	0 cf*	3,348 cf
Proposed New Impervious Area (in addition to existing)	7,864 sf	655 cf	

\*To Max. Extent Practicable

A Long-Term Pollution Prevention Plan (LTPPP) and Operation & Maintenance Plan is included in Appendix D.

4.5 STANDARD 5: LAND USES WITH HIGHER POTENTIAL POLLUTANT LOADS (LUHPPLS)

*For Land Uses with Higher Potential Pollutant Loads (LUHPPLs), source control and pollution prevention shall be implemented in accordance with the Massachusetts Stormwater Handbook to eliminate or reduce the discharge of stormwater runoff from such land uses to the maximum extent practicable. If through source control and/or pollution prevention all LUHPPLs cannot be completely protected from exposure to rain, snow, snow melt, and stormwater runoff, the proponent shall use the specific structural stormwater BMPs determined by the Department to be suitable for such uses as provided in the Massachusetts Stormwater Handbook. Stormwater discharges from LUHPPLs shall also comply with the requirements of the Massachusetts Clean Waters Act, M.G.L. c. 21, §§ 26-53 and the regulations promulgated thereunder at 314 CMR 3.00, 314 CMR 4.00 and 314 CMR 5.00.*



No change:

Standard 5 does not apply to the Project. There are no Land Uses with Higher Potential Pollutant Loads within the project area.

4.6 STANDARD 6: CRITICAL AREAS

*Stormwater discharges within the Zone II or Interim Wellhead Protection Area of a public water supply and stormwater discharges near or to any other critical area require the use of the specific source control and pollution prevention measures and the specific structural stormwater best management practices determined by the Department to be suitable for managing discharges to such areas as provided in the Massachusetts Stormwater Handbook. A discharge is near a critical area if there is a strong likelihood of a significant impact occurring to said area, taking into account site-specific factors. Stormwater discharges to Outstanding Resource Waters and Special Resource Waters shall be removed and set back from the receiving water or wetland and receive the highest and best practical method of treatment. A “stormwater discharge” as defined in 314 CMR 3.04(2)(a)1 or (b), to an Outstanding Resource Water or Special Resource Water shall comply with 314 CMR 3.00 and 314 CMR 4.00. Stormwater discharges to a Zone I or Zone A are prohibited unless essential to the operation of a public water supply.*

Standard Met:

The project is within a Zone I Wellhead Protection Area. However, the proposed infiltration basin is sized to accommodate the 100-year 24-hour storm event without discharging to the surrounding area. An emergency overflow weir is provided as a precautionary measure but is not anticipated to see flow up to and including the 100-year storm event. Additionally, the project proposed is essential to the operation of a public water supply. Thus, Standard 6 is met.

4.7 STANDARD 7: REDEVELOPMENTS AND OTHER PROJECTS SUBJECT TO THE STANDARDS ONLY TO THE MAXIMUM EXTENT PRACTICABLE

*A redevelopment project is required to meet the following Stormwater Management Standards only to the maximum extent practicable: Standard 2, Standard 3, and the pretreatment and structural best management practice requirements of Standards 4, 5, and 6. Existing stormwater discharges shall comply with Standard 1 only to the maximum extent practicable. A redevelopment project shall also comply with all other requirements of the Stormwater Management Standards and improve existing conditions.*

No substantive change:

The Project is considered a new development and is subject to all Standards 1 through 10.

4.8 STANDARD 8: CONSTRUCTION PERIOD POLLUTION PREVENTION AND EROSION AND SEDIMENTATION CONTROLS

*A plan to control construction-related impacts, including erosion, sedimentation and other pollutant sources during construction and land disturbance activities (construction period erosion, sedimentation, and pollution prevention plan) shall be developed and implemented.*

Standard Met:

The site plans call for the installation of sediment control barriers around the perimeter of the site to prevent off-site sediment transport. A construction exit will be provided to reduce transport of sediment off-site via construction traffic. All stockpiles will be surrounded with straw wattle during the earthwork phase of construction. A SWPPP will be prepared by the contractor prior to the onset of construction.

During construction, the contractor will be required to address any erosion issues that appear as a result of land disturbance. This may include the installation of additional sediment barrier, temporary erosion control matting, or temporary seeding. Erosion control measures will be repaired as necessary during construction. The contractor will be required to install and maintain all erosion control measures in accordance with the Massachusetts Stormwater Handbook.

Stormwater controls must be maintained in good operating condition until all disturbed soils are permanently stabilized. To ensure this, the following areas will be inspected by the Contractor every week and after every rainfall event of 0.5 inches or greater:

The following standard maintenance practices will apply to the erosion and sedimentation controls for the project:

- All erosion and sediment control measures will be properly maintained. If repairs or other maintenance is necessary, it will be initiated by the Contractor within 24 hours of report;
- Straw Wattles will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground;
- Built up sediment will be removed from straw wattles when it has reached one-half the height of the fence and at end of the job;
- Erosion control measures will be maintained for disturbed areas of the site that have not been stabilized;
- Erosion control measures will be installed and maintained for the construction staging area, stockpiles, and material storage areas until those areas have been stabilized after construction; and,
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.

If the inspections reveal the need for additional control devices to prevent erosion and sedimentation, the Contractor will promptly install additional protection devices as required. Control devices in need of repair will be repaired promptly after identification. A stockpile of 100 linear feet of straw wattles will be maintained on the site and under cover for emergency repairs and routine maintenance.

The Owner (or their representative) will be responsible for preparing an inspection and maintenance report following each inspection and filing completed reports after maintenance action has taken place by the Contractor. The Contractor's superintendent will be responsible for maintenance and repair activities and completing and signing the maintenance action portion of inspection and maintenance reports.



#### 4.9 STANDARD 9: OPERATION AND MAINTENANCE PLAN

*A Long-Term Operation and Maintenance (O&M) Plan shall be developed and implemented to ensure that stormwater management systems function as designed.*

Standard Met:

An Operation & Maintenance Plan is referenced as Appendix D and is provided under separate cover.

#### 4.10 STANDARD 10: PROHIBITION OF ILLICIT DISCHARGES

*All illicit discharges to the stormwater management system are prohibited.*

No change

Illicit Discharge Statement The project's stormwater management system, as shown on the plans submitted with this report, have been designed in full compliance with Standard 10. The project area does not have any known illicit connections.



Attachments:

- Appendix A – Stormwater Checklist
- Appendix B – Drainage Figures
- Appendix C – HydroCAD Analysis
  - C.1 – Existing Conditions
  - C.2 – Proposed Conditions
- Appendix D – Stormwater Operation and Maintenance Plan
- Appendix E – Water Quality Calculation
- Appendix F – Project Data: NOAA Rainfall and NRCS Web Soil Survey
- Appendix G – Boring Log






Appendix A  
Stormwater Checklist Stormwater Checklist



# Checklist for Stormwater Report

## A. Introduction

**Important:** When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the [Massachusetts Stormwater Handbook](#). The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.<sup>1</sup> This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8<sup>2</sup>
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

<sup>1</sup> The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

<sup>2</sup> For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



# Checklist for Stormwater Report

---

## B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

*Note:* Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

---

### Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature

---

Signature and Date

---

## Checklist

**Project Type:** Is the application for new development, redevelopment, or a mix of new and redevelopment?

- New development
- Redevelopment
- Mix of New Development and Redevelopment





# Checklist for Stormwater Report

---

## Checklist (continued)

**LID Measures:** Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

- No disturbance to any Wetland Resource Areas
- Site Design Practices (e.g. clustered development, reduced frontage setbacks)
- Reduced Impervious Area (Redevelopment Only)
- Minimizing disturbance to existing trees and shrubs
- LID Site Design Credit Requested:
  - Credit 1
  - Credit 2
  - Credit 3
- Use of “country drainage” versus curb and gutter conveyance and pipe
- Bioretention Cells (includes Rain Gardens)
- Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
- Treebox Filter
- Water Quality Swale
- Grass Channel
- Green Roof
- Other (describe): Infiltration Basin

### Standard 1: No New Untreated Discharges

- No new untreated discharges
- Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 2: Peak Rate Attenuation

- Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
- Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

### Standard 3: Recharge

- Soil Analysis provided.
- Required Recharge Volume calculation provided.
- Required Recharge volume reduced through use of the LID site Design Credits.
- Sizing the infiltration, BMPs is based on the following method: Check the method used.
  - Static
  - Simple Dynamic
  - Dynamic Field<sup>1</sup>
- Runoff from all impervious areas at the site discharging to the infiltration BMP.
- Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
  - Site is comprised solely of C and D soils and/or bedrock at the land surface
  - M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
  - Solid Waste Landfill pursuant to 310 CMR 19.000
  - Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

---

<sup>1</sup> 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 3: Recharge (continued)

- The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
- Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

### Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
  - Provisions for storing materials and waste products inside or under cover;
  - Vehicle washing controls;
  - Requirements for routine inspections and maintenance of stormwater BMPs;
  - Spill prevention and response plans;
  - Provisions for maintenance of lawns, gardens, and other landscaped areas;
  - Requirements for storage and use of fertilizers, herbicides, and pesticides;
  - Pet waste management provisions;
  - Provisions for operation and management of septic systems;
  - Provisions for solid waste management;
  - Snow disposal and plowing plans relative to Wetland Resource Areas;
  - Winter Road Salt and/or Sand Use and Storage restrictions;
  - Street sweeping schedules;
  - Provisions for prevention of illicit discharges to the stormwater management system;
  - Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
  - Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
  - List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
  - Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
    - is within the Zone II or Interim Wellhead Protection Area
    - is near or to other critical areas
    - is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
    - involves runoff from land uses with higher potential pollutant loads.
  - The Required Water Quality Volume is reduced through use of the LID site Design Credits.
  - Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.





# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 4: Water Quality (continued)

- The BMP is sized (and calculations provided) based on:
  - The ½" or 1" Water Quality Volume or
  - The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

### Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- The NPDES Multi-Sector General Permit does **not** cover the land use.
- LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- All exposure has been eliminated.
- All exposure has **not** been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

### Standard 6: Critical Areas

- The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- Critical areas and BMPs are identified in the Stormwater Report.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
  - Limited Project
  - Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
  - Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
  - Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
  - Bike Path and/or Foot Path
  - Redevelopment Project
  - Redevelopment portion of mix of new and redevelopment.
- Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.
- The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

### Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
  - Construction Period Operation and Maintenance Plan;
  - Names of Persons or Entity Responsible for Plan Compliance;
  - Construction Period Pollution Prevention Measures;
  - Erosion and Sedimentation Control Plan Drawings;
  - Detail drawings and specifications for erosion control BMPs, including sizing calculations;
  - Vegetation Planning;
  - Site Development Plan;
  - Construction Sequencing Plan;
  - Sequencing of Erosion and Sedimentation Controls;
  - Operation and Maintenance of Erosion and Sedimentation Controls;
  - Inspection Schedule;
  - Maintenance Schedule;
  - Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has **not** been included in the Stormwater Report but will be submitted **before** land disturbance begins.
- The project is **not** covered by a NPDES Construction General Permit.
- The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

### Standard 9: Operation and Maintenance Plan

- The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
  - Name of the stormwater management system owners;
  - Party responsible for operation and maintenance;
  - Schedule for implementation of routine and non-routine maintenance tasks;
  - Plan showing the location of all stormwater BMPs maintenance access areas;
  - Description and delineation of public safety features;
  - Estimated operation and maintenance budget; and
  - Operation and Maintenance Log Form.
- The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
  - A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
  - A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

### Standard 10: Prohibition of Illicit Discharges

- The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- An Illicit Discharge Compliance Statement is attached;
- NO Illicit Discharge Compliance Statement is attached but will be submitted **prior to** the discharge of any stormwater to post-construction BMPs.





Appendix B  
Drainage Figures


Signed By: ---- # 12345

REVISIONS


REV	DESCRIPTION	DSN DWN	CHK APP	DATE

SCALE VERIFICATION

THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING



IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY



EXISTING DRAINAGE FIGURE

TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054


DRAINAGE DESIGN

PROJECT NO.	20233667.002A
ISSUE DATE	OCTOBER 2023
CURRENT REVISION	DRAFT
DESIGNED BY	MPS
DRAWN BY	MPS
CHECKED BY	GAA
APPROVED BY	GAA

D-101



**DRAFT**  
**NOT FOR CONSTRUCTION**



LEGEND:

- STORMWATER BEST MANAGEMENT PRACTICE (BMP)
- SUBCATCHMENT AREA
- DESIGN POINT
- FLOW ARROW

CAD FILE: G:\clients\Millis MA\2023\3667\002A\_Well 3 PRAS Final Design & Permitting\08\_Drawing\01 C-102\_Site Layout.dwg LAYOUT: D-101 PLOTTED: 10/25/2023 6:09 PM BY: matthew.stevens

Now or Formerly  
DOMENIC J. TIBERI et ux  
PARCEL 0028-0025-0000  
(Book 33903 Page 340)  
(Plan No. 519 of 1989, Lot 1)

EASEMENT  
(APPROX. LOC.)  
(BY OF 1973)

Now or Formerly  
J. WHELAN REALTY TRUST  
CEL 0028-0041-0000  
bk 11874 Page 403  
No. 142 of 1997, Lot 3)

OWNER:  
N/F TOWN OF MILLIS  
PARCEL 0028-0046-0000  
(NO DEED REF. FOUND)  
(PLAN NO. 377 OF 1973)

OWNER:  
N/F TOWN OF MILLIS  
PARCEL 0028-0046-0000  
(NO DEED REF. FOUND)  
(PLAN NO. 377 OF 1973)



REVISIONS				
REV	DESCRIPTION	DSN DWN	CHK APP	DATE

**SCALE VERIFICATION**  
THIS BAR IS 1 INCH IN LENGTH ON ORIGINAL DRAWING  
0 1"  
IF IT'S NOT 1 INCH ON THIS SHEET ADJUST YOUR SCALES ACCORDINGLY

0 20 40  
SCALE: 1" = 20' SCALE IN FEET  
ORIGINAL DRAWING SIZE IS 22 x 34

**PROPOSED DRAINAGE FIGURE**  
TOWN OF MILLIS, MASSACHUSETTS  
WELL 3 WATER TREATMENT FACILITY




TOWN OF MILLIS  
DEPARTMENT OF PUBLIC WORKS  
900 MAIN ST, MILLIS, MA 02054

**DRAINAGE DESIGN**

PROJECT NO.	20233667.002A
ISSUE DATE	OCTOBER 2023
CURRENT REVISION	DRAFT
DESIGNED BY	MPS
DRAWN BY	MPS
CHECKED BY	GAA
APPROVED BY	GAA

**D-102**



**DRAFT**  
**NOT FOR CONSTRUCTION**

0 20 40  
SCALE: 1" = 20' SCALE IN FEET

- LEGEND:**
- STORMWATER BEST MANAGEMENT PRACTICE (BMP)
  - SUBCATCHMENT AREA
  - DESIGN POINT
  - FLOW ARROW

CAD FILE: G:\clients\Millis\MA\2023\3667\002A\_Well 3 PRAS Final Design & Permitting\08 - Drawings\C-101 C-102\_Site Layout.dwg LAYOUT: D-102 PLOTTED: 10/25/2023 6:10 PM BY: matthew.stevens

Now or Formerly  
DOMENIC J. TIBERI et ux  
PARCEL 0028-0025-0000  
(Book 33903 Page 340)  
(Plan No. 519 of 1989, Lot 1)

Now or Formerly  
J. WHELAN REALTY TRUST  
CEL 0028-0041-0000  
(Book 11874 Page 403)  
(No. 142 of 1997, Lot 3)

OWNER:  
N/F TOWN OF MILLIS  
PARCEL 0028-0046-0000  
(NO DEED REF. FOUND)  
(PLAN NO. 377 OF 1973)

OWNER:  
N/F TOWN OF MILLIS  
PARCEL 0028-0046-0000  
(NO DEED REF. FOUND)  
(PLAN NO. 377 OF 1973)







Appendix C  
HydroCAD Analysis



Appendix C.1  
Existing Conditions


# Millis Well 3 Existing Conditions



Subcat



Reach



Pond



Link



## Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Printed 10/25/2023

Page 2

### Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	1-Year	Type III 24-hr		Default	24.00	1	2.76	2
2	2-Year	Type III 24-hr		Default	24.00	1	3.39	2
3	5-Year	Type III 24-hr		Default	24.00	1	4.42	2
4	10-Year	Type III 24-hr		Default	24.00	1	5.28	2
5	25-Year	Type III 24-hr		Default	24.00	1	6.45	2
6	100-Year	Type III 24-hr		Default	24.00	1	8.27	2

## Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Printed 10/25/2023

Page 3

### Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.226	96	Gravel surface, HSG A (SC-1)
0.021	98	Impervious, HSG A (SC-1)
0.766	30	Woods, Good, HSG A (SC-1, SC-2)
<b>1.013</b>	<b>46</b>	<b>TOTAL AREA</b>

**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.76"

Printed 10/25/2023

Page 4

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West**      Runoff Area=24,786 sf   3.61% Impervious   Runoff Depth=1.01"  
Tc=6.0 min   CN=WQ   Runoff=0.62 cfs   0.048 af

**SubcatchmentSC-2: Overland to East**      Runoff Area=19,349 sf   0.00% Impervious   Runoff Depth=0.00"  
Tc=6.0 min   CN=30   Runoff=0.00 cfs   0.000 af

**Link DP-1: West Wetlands**      Inflow=0.62 cfs   0.048 af  
Primary=0.62 cfs   0.048 af

**Link DP-2: East Low Point**      Inflow=0.00 cfs   0.000 af  
Primary=0.00 cfs   0.000 af

**Total Runoff Area = 1.013 ac   Runoff Volume = 0.048 af   Average Runoff Depth = 0.57"**  
**97.97% Pervious = 0.993 ac   2.03% Impervious = 0.021 ac**



**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.76"

Printed 10/25/2023

Page 5

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 0.62 cfs @ 12.09 hrs, Volume= 0.048 af, Depth= 1.01"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 1-Year Rainfall=2.76"

Area (sf)	CN	Description
14,031	30	Woods, Good, HSG A
9,861	96	Gravel surface, HSG A
* 894	98	Impervious, HSG A
24,786		Weighted Average
23,892	57	96.39% Pervious Area
894	98	3.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Tc Min</b>

**Summary for Subcatchment SC-2: Overland to East**

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 1-Year Rainfall=2.76"

Area (sf)	CN	Description
19,349	30	Woods, Good, HSG A
19,349	30	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Tc Min</b>

**Summary for Link DP-1: West Wetlands**

Inflow Area = 0.569 ac, 3.61% Impervious, Inflow Depth = 1.01" for 1-Year event  
 Inflow = 0.62 cfs @ 12.09 hrs, Volume= 0.048 af  
 Primary = 0.62 cfs @ 12.09 hrs, Volume= 0.048 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.76"

Printed 10/25/2023

Page 6

**Summary for Link DP-2: East Low Point**

Inflow Area = 0.444 ac, 0.00% Impervious, Inflow Depth = 0.00" for 1-Year event  
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.39"

Printed 10/25/2023

Page 7

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West**      Runoff Area=24,786 sf   3.61% Impervious   Runoff Depth=1.28"  
Tc=6.0 min   CN=WQ   Runoff=0.77 cfs   0.061 af

**SubcatchmentSC-2: Overland to East**      Runoff Area=19,349 sf   0.00% Impervious   Runoff Depth=0.00"  
Tc=6.0 min   CN=30   Runoff=0.00 cfs   0.000 af

**Link DP-1: West Wetlands**      Inflow=0.77 cfs   0.061 af  
Primary=0.77 cfs   0.061 af

**Link DP-2: East Low Point**      Inflow=0.00 cfs   0.000 af  
Primary=0.00 cfs   0.000 af

**Total Runoff Area = 1.013 ac   Runoff Volume = 0.061 af   Average Runoff Depth = 0.72"**  
**97.97% Pervious = 0.993 ac   2.03% Impervious = 0.021 ac**



**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.39"

Printed 10/25/2023

Page 8

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 0.77 cfs @ 12.09 hrs, Volume= 0.061 af, Depth= 1.28"  
Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-Year Rainfall=3.39"

Area (sf)	CN	Description
14,031	30	Woods, Good, HSG A
9,861	96	Gravel surface, HSG A
* 894	98	Impervious, HSG A
24,786		Weighted Average
23,892	57	96.39% Pervious Area
894	98	3.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to East**

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"  
Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-Year Rainfall=3.39"

Area (sf)	CN	Description
19,349	30	Woods, Good, HSG A
19,349	30	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Link DP-1: West Wetlands**

Inflow Area = 0.569 ac, 3.61% Impervious, Inflow Depth = 1.28" for 2-Year event  
Inflow = 0.77 cfs @ 12.09 hrs, Volume= 0.061 af  
Primary = 0.77 cfs @ 12.09 hrs, Volume= 0.061 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.39"

Printed 10/25/2023

Page 9

### Summary for Link DP-2: East Low Point

Inflow Area = 0.444 ac, 0.00% Impervious, Inflow Depth = 0.00" for 2-Year event  
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 10

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West**      Runoff Area=24,786 sf   3.61% Impervious   Runoff Depth=1.73"  
Tc=6.0 min   CN=WQ   Runoff=1.02 cfs   0.082 af

**SubcatchmentSC-2: Overland to East**      Runoff Area=19,349 sf   0.00% Impervious   Runoff Depth=0.00"  
Tc=6.0 min   CN=30   Runoff=0.00 cfs   0.000 af

**Link DP-1: West Wetlands**      Inflow=1.02 cfs   0.082 af  
Primary=1.02 cfs   0.082 af

**Link DP-2: East Low Point**      Inflow=0.00 cfs   0.000 af  
Primary=0.00 cfs   0.000 af

**Total Runoff Area = 1.013 ac   Runoff Volume = 0.082 af   Average Runoff Depth = 0.97"**  
**97.97% Pervious = 0.993 ac   2.03% Impervious = 0.021 ac**



**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 11

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 1.02 cfs @ 12.09 hrs, Volume= 0.082 af, Depth= 1.73"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 5-Year Rainfall=4.42"

Area (sf)	CN	Description
14,031	30	Woods, Good, HSG A
9,861	96	Gravel surface, HSG A
* 894	98	Impervious, HSG A
24,786		Weighted Average
23,892	57	96.39% Pervious Area
894	98	3.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to East**

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 5-Year Rainfall=4.42"

Area (sf)	CN	Description
19,349	30	Woods, Good, HSG A
19,349	30	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Link DP-1: West Wetlands**

Inflow Area = 0.569 ac, 3.61% Impervious, Inflow Depth = 1.73" for 5-Year event  
 Inflow = 1.02 cfs @ 12.09 hrs, Volume= 0.082 af  
 Primary = 1.02 cfs @ 12.09 hrs, Volume= 0.082 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 12

### Summary for Link DP-2: East Low Point

Inflow Area = 0.444 ac, 0.00% Impervious, Inflow Depth = 0.00" for 5-Year event  
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.28"

Printed 10/25/2023

Page 13

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West**      Runoff Area=24,786 sf   3.61% Impervious   Runoff Depth=2.10"  
Tc=6.0 min   CN=WQ   Runoff=1.23 cfs   0.100 af

**SubcatchmentSC-2: Overland to East**      Runoff Area=19,349 sf   0.00% Impervious   Runoff Depth=0.02"  
Tc=6.0 min   CN=30   Runoff=0.00 cfs   0.001 af

**Link DP-1: West Wetlands**      Inflow=1.23 cfs   0.100 af  
Primary=1.23 cfs   0.100 af

**Link DP-2: East Low Point**      Inflow=0.00 cfs   0.001 af  
Primary=0.00 cfs   0.001 af

**Total Runoff Area = 1.013 ac   Runoff Volume = 0.100 af   Average Runoff Depth = 1.19"**  
**97.97% Pervious = 0.993 ac   2.03% Impervious = 0.021 ac**



**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.28"

Printed 10/25/2023

Page 14

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 1.23 cfs @ 12.09 hrs, Volume= 0.100 af, Depth= 2.10"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Year Rainfall=5.28"

Area (sf)	CN	Description
14,031	30	Woods, Good, HSG A
9,861	96	Gravel surface, HSG A
* 894	98	Impervious, HSG A
24,786		Weighted Average
23,892	57	96.39% Pervious Area
894	98	3.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to East**

Runoff = 0.00 cfs @ 22.19 hrs, Volume= 0.001 af, Depth= 0.02"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Year Rainfall=5.28"

Area (sf)	CN	Description
19,349	30	Woods, Good, HSG A
19,349	30	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Link DP-1: West Wetlands**

Inflow Area = 0.569 ac, 3.61% Impervious, Inflow Depth = 2.10" for 10-Year event  
 Inflow = 1.23 cfs @ 12.09 hrs, Volume= 0.100 af  
 Primary = 1.23 cfs @ 12.09 hrs, Volume= 0.100 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.28"

Printed 10/25/2023

Page 15

### Summary for Link DP-2: East Low Point

Inflow Area = 0.444 ac, 0.00% Impervious, Inflow Depth = 0.02" for 10-Year event

Inflow = 0.00 cfs @ 22.19 hrs, Volume= 0.001 af

Primary = 0.00 cfs @ 22.19 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 16

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West**      Runoff Area=24,786 sf   3.61% Impervious   Runoff Depth=2.67"  
Tc=6.0 min   CN=WQ   Runoff=1.51 cfs   0.127 af

**SubcatchmentSC-2: Overland to East**      Runoff Area=19,349 sf   0.00% Impervious   Runoff Depth=0.13"  
Tc=6.0 min   CN=30   Runoff=0.01 cfs   0.005 af

**Link DP-1: West Wetlands**      Inflow=1.51 cfs   0.127 af  
Primary=1.51 cfs   0.127 af

**Link DP-2: East Low Point**      Inflow=0.01 cfs   0.005 af  
Primary=0.01 cfs   0.005 af

**Total Runoff Area = 1.013 ac   Runoff Volume = 0.131 af   Average Runoff Depth = 1.56"**  
**97.97% Pervious = 0.993 ac   2.03% Impervious = 0.021 ac**



### Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 17

### Summary for Subcatchment SC-1: Overland to West Wetland

Runoff = 1.51 cfs @ 12.09 hrs, Volume= 0.127 af, Depth= 2.67"  
Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-Year Rainfall=6.45"

Area (sf)	CN	Description
14,031	30	Woods, Good, HSG A
9,861	96	Gravel surface, HSG A
* 894	98	Impervious, HSG A
24,786		Weighted Average
23,892	57	96.39% Pervious Area
894	98	3.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Summary for Subcatchment SC-2: Overland to East

Runoff = 0.01 cfs @ 14.96 hrs, Volume= 0.005 af, Depth= 0.13"  
Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-Year Rainfall=6.45"

Area (sf)	CN	Description
19,349	30	Woods, Good, HSG A
19,349	30	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Summary for Link DP-1: West Wetlands

Inflow Area = 0.569 ac, 3.61% Impervious, Inflow Depth = 2.67" for 25-Year event  
Inflow = 1.51 cfs @ 12.09 hrs, Volume= 0.127 af  
Primary = 1.51 cfs @ 12.09 hrs, Volume= 0.127 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 18

### Summary for Link DP-2: East Low Point

Inflow Area = 0.444 ac, 0.00% Impervious, Inflow Depth = 0.13" for 25-Year event

Inflow = 0.01 cfs @ 14.96 hrs, Volume= 0.005 af

Primary = 0.01 cfs @ 14.96 hrs, Volume= 0.005 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Existing**

Type III 24-hr 100-Year Rainfall=8.27"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 19

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West**      Runoff Area=24,786 sf   3.61% Impervious   Runoff Depth=3.66"  
Tc=6.0 min   CN=WQ   Runoff=1.95 cfs   0.174 af

**SubcatchmentSC-2: Overland to East**      Runoff Area=19,349 sf   0.00% Impervious   Runoff Depth=0.48"  
Tc=6.0 min   CN=30   Runoff=0.07 cfs   0.018 af

**Link DP-1: West Wetlands**      Inflow=1.95 cfs   0.174 af  
Primary=1.95 cfs   0.174 af

**Link DP-2: East Low Point**      Inflow=0.07 cfs   0.018 af  
Primary=0.07 cfs   0.018 af

**Total Runoff Area = 1.013 ac   Runoff Volume = 0.191 af   Average Runoff Depth = 2.27"**  
**97.97% Pervious = 0.993 ac   2.03% Impervious = 0.021 ac**



**Millis Well 3 Existing**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.27"

Printed 10/25/2023

Page 20

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 1.95 cfs @ 12.09 hrs, Volume= 0.174 af, Depth= 3.66"  
Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-Year Rainfall=8.27"

Area (sf)	CN	Description
14,031	30	Woods, Good, HSG A
9,861	96	Gravel surface, HSG A
* 894	98	Impervious, HSG A
24,786		Weighted Average
23,892	57	96.39% Pervious Area
894	98	3.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to East**

Runoff = 0.07 cfs @ 12.40 hrs, Volume= 0.018 af, Depth= 0.48"  
Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-Year Rainfall=8.27"

Area (sf)	CN	Description
19,349	30	Woods, Good, HSG A
19,349	30	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Link DP-1: West Wetlands**

Inflow Area = 0.569 ac, 3.61% Impervious, Inflow Depth = 3.66" for 100-Year event  
Inflow = 1.95 cfs @ 12.09 hrs, Volume= 0.174 af  
Primary = 1.95 cfs @ 12.09 hrs, Volume= 0.174 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Millis Well 3 Existing

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.27"

Printed 10/25/2023

Page 21

### Summary for Link DP-2: East Low Point

Inflow Area = 0.444 ac, 0.00% Impervious, Inflow Depth = 0.48" for 100-Year event  
Inflow = 0.07 cfs @ 12.40 hrs, Volume= 0.018 af  
Primary = 0.07 cfs @ 12.40 hrs, Volume= 0.018 af, Atten= 0%, Lag= 0.0 min




Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs



Appendix C.2  
Proposed Conditions



**Millis Well 3 Proposed  
Conditions**



# Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Printed 10/25/2023

Page 2

## Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	1-Year	Type III 24-hr		Default	24.00	1	2.76	2
2	2-Year	Type III 24-hr		Default	24.00	1	3.39	2
3	5-Year	Type III 24-hr		Default	24.00	1	4.42	2
4	10-Year	Type III 24-hr		Default	24.00	1	5.28	2
5	25-Year	Type III 24-hr		Default	24.00	1	6.45	2
6	100-Year	Type III 24-hr		Default	24.00	1	8.27	2

## Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Printed 10/25/2023

Page 3

### Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.186	96	Gravel surface, HSG A (SC-1, SC-5)
0.012	98	Impervious, HSG A (SC-5)
0.404	39	Pasture/grassland/range, Good, HSG A (SC-1, SC-2, SC-3, SC-5)
0.183	98	Paved parking, HSG A (SC-1, SC-2)
0.055	98	Water Surface, 0% imp, HSG A (SC-3)
0.173	32	Woods/grass comb., Good, HSG A (SC-4)
<b>1.013</b>	<b>63</b>	<b>TOTAL AREA</b>



**Millis Well 3 Proposed**

Type III 24-hr 1-Year Rainfall=2.76"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 4

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West** Runoff Area=3,356 sf 15.85% Impervious Runoff Depth=1.48"  
Tc=6.0 min CN=WQ Runoff=0.12 cfs 0.010 af

**SubcatchmentSC-2: Overland to Forebay** Runoff Area=11,864 sf 62.53% Impervious Runoff Depth=1.58"  
Tc=6.0 min CN=WQ Runoff=0.44 cfs 0.036 af

**SubcatchmentSC-3: Overland to Basin** Runoff Area=9,595 sf 0.00% Impervious Runoff Depth=0.63"  
Tc=6.0 min CN=WQ Runoff=0.14 cfs 0.012 af

**SubcatchmentSC-4: Basin Berm and** Runoff Area=7,531 sf 0.00% Impervious Runoff Depth=0.00"  
Tc=6.0 min CN=32 Runoff=0.00 cfs 0.000 af

**SubcatchmentSC-5: Overland to West** Runoff Area=11,789 sf 4.58% Impervious Runoff Depth=1.40"  
Tc=6.0 min CN=WQ Runoff=0.41 cfs 0.032 af

**Pond P-1: Forebay** Peak Elev=123.38' Storage=107 cf Inflow=0.57 cfs 0.045 af  
Discarded=0.02 cfs 0.016 af Primary=0.49 cfs 0.029 af Outflow=0.51 cfs 0.045 af

**Pond P-2: Infiltration Basin** Peak Elev=122.28' Storage=594 cf Inflow=0.62 cfs 0.041 af  
Discarded=0.12 cfs 0.041 af Primary=0.00 cfs 0.000 af Outflow=0.12 cfs 0.041 af

**Link DP-1: West Wetlands** Inflow=0.41 cfs 0.032 af  
Primary=0.41 cfs 0.032 af

**Link DP-2: East Low Point** Inflow=0.00 cfs 0.000 af  
Primary=0.00 cfs 0.000 af

**Total Runoff Area = 1.013 ac Runoff Volume = 0.089 af Average Runoff Depth = 1.05"**  
**80.76% Pervious = 0.818 ac 19.24% Impervious = 0.195 ac**

### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.76"

Printed 10/25/2023

Page 5

### Summary for Subcatchment SC-1: Overland to West Wetland

Runoff = 0.12 cfs @ 12.09 hrs, Volume= 0.010 af, Depth= 1.48"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 1-Year Rainfall=2.76"

Area (sf)	CN	Description
532	98	Paved parking, HSG A
1,256	39	Pasture/grassland/range, Good, HSG A
1,568	96	Gravel surface, HSG A
3,356		Weighted Average
2,824	71	84.15% Pervious Area
532	98	15.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Summary for Subcatchment SC-2: Overland to Forebay

Runoff = 0.44 cfs @ 12.09 hrs, Volume= 0.036 af, Depth= 1.58"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 1-Year Rainfall=2.76"

Area (sf)	CN	Description
7,418	98	Paved parking, HSG A
4,446	39	Pasture/grassland/range, Good, HSG A
11,864		Weighted Average
4,446	39	37.47% Pervious Area
7,418	98	62.53% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Summary for Subcatchment SC-3: Overland to Basin

Runoff = 0.14 cfs @ 12.09 hrs, Volume= 0.012 af, Depth= 0.63"

Routed to Pond P-2 : Infiltration Basin

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 1-Year Rainfall=2.76"

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.76"

Printed 10/25/2023

Page 6

Area (sf)	CN	Description
2,407	98	Water Surface, 0% imp, HSG A
7,188	39	Pasture/grassland/range, Good, HSG A
9,595		Weighted Average
9,595	54	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-4: Basin Berm and Shoulder**

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 1-Year Rainfall=2.76"

Area (sf)	CN	Description
7,531	32	Woods/grass comb., Good, HSG A
7,531	32	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-5: Overland to West Wetland**

Runoff = 0.41 cfs @ 12.09 hrs, Volume= 0.032 af, Depth= 1.40"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 1-Year Rainfall=2.76"

Area (sf)	CN	Description
* 540	98	Impervious, HSG A
4,724	39	Pasture/grassland/range, Good, HSG A
6,525	96	Gravel surface, HSG A
11,789		Weighted Average
11,249	72	95.42% Pervious Area
540	98	4.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min



### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.76"

Printed 10/25/2023

Page 7

### Summary for Pond P-1: Forebay

Inflow Area = 0.349 ac, 52.23% Impervious, Inflow Depth = 1.56" for 1-Year event  
 Inflow = 0.57 cfs @ 12.09 hrs, Volume= 0.045 af  
 Outflow = 0.51 cfs @ 12.13 hrs, Volume= 0.045 af, Atten= 10%, Lag= 2.4 min  
 Discarded = 0.02 cfs @ 12.13 hrs, Volume= 0.016 af  
 Primary = 0.49 cfs @ 12.13 hrs, Volume= 0.029 af  
 Routed to Pond P-2 : Infiltration Basin

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 123.38' @ 12.13 hrs Surf.Area= 399 sf Storage= 107 cf

Plug-Flow detention time= 5.1 min calculated for 0.045 af (100% of inflow)  
 Center-of-Mass det. time= 5.1 min ( 767.5 - 762.5 )

Volume	Invert	Avail.Storage	Storage Description
#1	123.00'	472 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
123.00	165	0	0
124.00	779	472	472

Device	Routing	Invert	Outlet Devices
#1	Primary	123.00'	<b>12.0" Round Culvert</b> L= 69.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 123.00' / 122.50' S= 0.0072 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Discarded	123.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.02 cfs @ 12.13 hrs HW=123.38' (Free Discharge)  
 ↑**2=Exfiltration** (Exfiltration Controls 0.02 cfs)

**Primary OutFlow** Max=0.48 cfs @ 12.13 hrs HW=123.38' TW=122.15' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 0.48 cfs @ 2.62 fps)

### Summary for Pond P-2: Infiltration Basin

Inflow Area = 0.570 ac, 32.04% Impervious, Inflow Depth = 0.86" for 1-Year event  
 Inflow = 0.62 cfs @ 12.11 hrs, Volume= 0.041 af  
 Outflow = 0.12 cfs @ 12.57 hrs, Volume= 0.041 af, Atten= 80%, Lag= 27.1 min  
 Discarded = 0.12 cfs @ 12.57 hrs, Volume= 0.041 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Routed to Link DP-2 : East Low Point

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 122.28' @ 12.57 hrs Surf.Area= 2,235 sf Storage= 594 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 32.6 min ( 777.7 - 745.2 )

# Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.76"

Printed 10/25/2023

Page 8

Volume	Invert	Avail.Storage	Storage Description
#1	122.00'	5,937 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.00	1,944	0	0
124.00	3,993	5,937	5,937

Device	Routing	Invert	Outlet Devices
#1	Primary	123.99'	<b>15.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#2	Discarded	122.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.12 cfs @ 12.57 hrs HW=122.28' (Free Discharge)

↳ **2=Exfiltration** (Exfiltration Controls 0.12 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=122.00' TW=0.00' (Dynamic Tailwater)

↳ **1=Sharp-Crested Rectangular Weir**( Controls 0.00 cfs)

## Summary for Link DP-1: West Wetlands

Inflow Area = 0.271 ac, 4.58% Impervious, Inflow Depth = 1.40" for 1-Year event  
 Inflow = 0.41 cfs @ 12.09 hrs, Volume= 0.032 af  
 Primary = 0.41 cfs @ 12.09 hrs, Volume= 0.032 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Summary for Link DP-2: East Low Point

Inflow Area = 0.743 ac, 24.58% Impervious, Inflow Depth = 0.00" for 1-Year event  
 Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Proposed**

Type III 24-hr 2-Year Rainfall=3.39"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 9

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West** Runoff Area=3,356 sf 15.85% Impervious Runoff Depth=1.87"  
Tc=6.0 min CN=WQ Runoff=0.15 cfs 0.012 af

**SubcatchmentSC-2: Overland to Forebay** Runoff Area=11,864 sf 62.53% Impervious Runoff Depth=1.98"  
Tc=6.0 min CN=WQ Runoff=0.55 cfs 0.045 af

**SubcatchmentSC-3: Overland to Basin** Runoff Area=9,595 sf 0.00% Impervious Runoff Depth=0.80"  
Tc=6.0 min CN=WQ Runoff=0.18 cfs 0.015 af

**SubcatchmentSC-4: Basin Berm and** Runoff Area=7,531 sf 0.00% Impervious Runoff Depth=0.00"  
Tc=6.0 min CN=32 Runoff=0.00 cfs 0.000 af

**SubcatchmentSC-5: Overland to West** Runoff Area=11,789 sf 4.58% Impervious Runoff Depth=1.77"  
Tc=6.0 min CN=WQ Runoff=0.51 cfs 0.040 af

**Pond P-1: Forebay** Peak Elev=123.43' Storage=127 cf Inflow=0.70 cfs 0.057 af  
Discarded=0.02 cfs 0.018 af Primary=0.61 cfs 0.039 af Outflow=0.63 cfs 0.057 af

**Pond P-2: Infiltration Basin** Peak Elev=122.39' Storage=829 cf Inflow=0.78 cfs 0.054 af  
Discarded=0.13 cfs 0.054 af Primary=0.00 cfs 0.000 af Outflow=0.13 cfs 0.054 af

**Link DP-1: West Wetlands** Inflow=0.51 cfs 0.040 af  
Primary=0.51 cfs 0.040 af

**Link DP-2: East Low Point** Inflow=0.00 cfs 0.000 af  
Primary=0.00 cfs 0.000 af

**Total Runoff Area = 1.013 ac Runoff Volume = 0.111 af Average Runoff Depth = 1.32"**  
**80.76% Pervious = 0.818 ac 19.24% Impervious = 0.195 ac**



**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.39"

Printed 10/25/2023

Page 10

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 0.15 cfs @ 12.09 hrs, Volume= 0.012 af, Depth= 1.87"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-Year Rainfall=3.39"

Area (sf)	CN	Description
532	98	Paved parking, HSG A
1,256	39	Pasture/grassland/range, Good, HSG A
1,568	96	Gravel surface, HSG A
3,356		Weighted Average
2,824	71	84.15% Pervious Area
532	98	15.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to Forebay**

Runoff = 0.55 cfs @ 12.09 hrs, Volume= 0.045 af, Depth= 1.98"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-Year Rainfall=3.39"

Area (sf)	CN	Description
7,418	98	Paved parking, HSG A
4,446	39	Pasture/grassland/range, Good, HSG A
11,864		Weighted Average
4,446	39	37.47% Pervious Area
7,418	98	62.53% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-3: Overland to Basin**

Runoff = 0.18 cfs @ 12.09 hrs, Volume= 0.015 af, Depth= 0.80"

Routed to Pond P-2 : Infiltration Basin

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-Year Rainfall=3.39"

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.39"

Printed 10/25/2023

Page 11

Area (sf)	CN	Description
2,407	98	Water Surface, 0% imp, HSG A
7,188	39	Pasture/grassland/range, Good, HSG A
9,595		Weighted Average
9,595	54	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-4: Basin Berm and Shoulder**

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 2-Year Rainfall=3.39"

Area (sf)	CN	Description
7,531	32	Woods/grass comb., Good, HSG A
7,531	32	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-5: Overland to West Wetland**

Runoff = 0.51 cfs @ 12.09 hrs, Volume= 0.040 af, Depth= 1.77"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 2-Year Rainfall=3.39"

Area (sf)	CN	Description
* 540	98	Impervious, HSG A
4,724	39	Pasture/grassland/range, Good, HSG A
6,525	96	Gravel surface, HSG A
11,789		Weighted Average
11,249	72	95.42% Pervious Area
540	98	4.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.39"

Printed 10/25/2023

Page 12

### Summary for Pond P-1: Forebay

Inflow Area = 0.349 ac, 52.23% Impervious, Inflow Depth = 1.95" for 2-Year event  
 Inflow = 0.70 cfs @ 12.09 hrs, Volume= 0.057 af  
 Outflow = 0.63 cfs @ 12.13 hrs, Volume= 0.057 af, Atten= 10%, Lag= 2.3 min  
 Discarded = 0.02 cfs @ 12.13 hrs, Volume= 0.018 af  
 Primary = 0.61 cfs @ 12.13 hrs, Volume= 0.039 af  
 Routed to Pond P-2 : Infiltration Basin

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 123.43' @ 12.13 hrs Surf.Area= 428 sf Storage= 127 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 5.1 min ( 763.5 - 758.3 )

Volume	Invert	Avail.Storage	Storage Description
#1	123.00'	472 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
123.00	165	0	0
124.00	779	472	472

Device	Routing	Invert	Outlet Devices
#1	Primary	123.00'	<b>12.0" Round Culvert</b> L= 69.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 123.00' / 122.50' S= 0.0072 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Discarded	123.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.02 cfs @ 12.13 hrs HW=123.42' (Free Discharge)  
 ↑**2=Exfiltration** (Exfiltration Controls 0.02 cfs)

**Primary OutFlow** Max=0.60 cfs @ 12.13 hrs HW=123.42' TW=122.20' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 0.60 cfs @ 2.77 fps)

### Summary for Pond P-2: Infiltration Basin

Inflow Area = 0.570 ac, 32.04% Impervious, Inflow Depth = 1.13" for 2-Year event  
 Inflow = 0.78 cfs @ 12.11 hrs, Volume= 0.054 af  
 Outflow = 0.13 cfs @ 12.61 hrs, Volume= 0.054 af, Atten= 83%, Lag= 29.8 min  
 Discarded = 0.13 cfs @ 12.61 hrs, Volume= 0.054 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Routed to Link DP-2 : East Low Point

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 122.39' @ 12.61 hrs Surf.Area= 2,340 sf Storage= 829 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 45.2 min ( 790.0 - 744.8 )



# Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.39"

Printed 10/25/2023

Page 13

Volume	Invert	Avail.Storage	Storage Description
#1	122.00'	5,937 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.00	1,944	0	0
124.00	3,993	5,937	5,937

Device	Routing	Invert	Outlet Devices
#1	Primary	123.99'	<b>15.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#2	Discarded	122.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.13 cfs @ 12.61 hrs HW=122.39' (Free Discharge)  
 ↳ **2=Exfiltration** (Exfiltration Controls 0.13 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=122.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **1=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

## Summary for Link DP-1: West Wetlands

Inflow Area = 0.271 ac, 4.58% Impervious, Inflow Depth = 1.77" for 2-Year event  
 Inflow = 0.51 cfs @ 12.09 hrs, Volume= 0.040 af  
 Primary = 0.51 cfs @ 12.09 hrs, Volume= 0.040 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Summary for Link DP-2: East Low Point

Inflow Area = 0.743 ac, 24.58% Impervious, Inflow Depth = 0.00" for 2-Year event  
 Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 14

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West** Runoff Area=3,356 sf 15.85% Impervious Runoff Depth=2.55"  
Tc=6.0 min CN=WQ Runoff=0.20 cfs 0.016 af

**SubcatchmentSC-2: Overland to Forebay** Runoff Area=11,864 sf 62.53% Impervious Runoff Depth=2.65"  
Tc=6.0 min CN=WQ Runoff=0.72 cfs 0.060 af

**SubcatchmentSC-3: Overland to Basin** Runoff Area=9,595 sf 0.00% Impervious Runoff Depth=1.12"  
Tc=6.0 min CN=WQ Runoff=0.23 cfs 0.021 af

**SubcatchmentSC-4: Basin Berm and** Runoff Area=7,531 sf 0.00% Impervious Runoff Depth=0.00"  
Tc=6.0 min CN=32 Runoff=0.00 cfs 0.000 af

**SubcatchmentSC-5: Overland to West** Runoff Area=11,789 sf 4.58% Impervious Runoff Depth=2.42"  
Tc=6.0 min CN=WQ Runoff=0.67 cfs 0.055 af

**Pond P-1: Forebay** Peak Elev=123.50' Storage=160 cf Inflow=0.92 cfs 0.077 af  
Discarded=0.03 cfs 0.020 af Primary=0.81 cfs 0.056 af Outflow=0.83 cfs 0.077 af

**Pond P-2: Infiltration Basin** Peak Elev=122.55' Storage=1,229 cf Inflow=1.03 cfs 0.077 af  
Discarded=0.14 cfs 0.077 af Primary=0.00 cfs 0.000 af Outflow=0.14 cfs 0.077 af

**Link DP-1: West Wetlands** Inflow=0.67 cfs 0.055 af  
Primary=0.67 cfs 0.055 af

**Link DP-2: East Low Point** Inflow=0.00 cfs 0.000 af  
Primary=0.00 cfs 0.000 af

**Total Runoff Area = 1.013 ac Runoff Volume = 0.152 af Average Runoff Depth = 1.80"**  
**80.76% Pervious = 0.818 ac 19.24% Impervious = 0.195 ac**

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 15

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 0.20 cfs @ 12.09 hrs, Volume= 0.016 af, Depth= 2.55"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 5-Year Rainfall=4.42"

Area (sf)	CN	Description
532	98	Paved parking, HSG A
1,256	39	Pasture/grassland/range, Good, HSG A
1,568	96	Gravel surface, HSG A
3,356		Weighted Average
2,824	71	84.15% Pervious Area
532	98	15.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to Forebay**

Runoff = 0.72 cfs @ 12.09 hrs, Volume= 0.060 af, Depth= 2.65"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 5-Year Rainfall=4.42"

Area (sf)	CN	Description
7,418	98	Paved parking, HSG A
4,446	39	Pasture/grassland/range, Good, HSG A
11,864		Weighted Average
4,446	39	37.47% Pervious Area
7,418	98	62.53% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-3: Overland to Basin**

Runoff = 0.23 cfs @ 12.09 hrs, Volume= 0.021 af, Depth= 1.12"

Routed to Pond P-2 : Infiltration Basin

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 5-Year Rainfall=4.42"



**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 16

Area (sf)	CN	Description
2,407	98	Water Surface, 0% imp, HSG A
7,188	39	Pasture/grassland/range, Good, HSG A
9,595		Weighted Average
9,595	54	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-4: Basin Berm and Shoulder**

Runoff = 0.00 cfs @ 24.00 hrs, Volume= 0.000 af, Depth= 0.00"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 5-Year Rainfall=4.42"

Area (sf)	CN	Description
7,531	32	Woods/grass comb., Good, HSG A
7,531	32	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-5: Overland to West Wetland**

Runoff = 0.67 cfs @ 12.09 hrs, Volume= 0.055 af, Depth= 2.42"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 5-Year Rainfall=4.42"

Area (sf)	CN	Description
* 540	98	Impervious, HSG A
4,724	39	Pasture/grassland/range, Good, HSG A
6,525	96	Gravel surface, HSG A
11,789		Weighted Average
11,249	72	95.42% Pervious Area
540	98	4.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 17

### Summary for Pond P-1: Forebay

Inflow Area = 0.349 ac, 52.23% Impervious, Inflow Depth = 2.63" for 5-Year event  
 Inflow = 0.92 cfs @ 12.09 hrs, Volume= 0.077 af  
 Outflow = 0.83 cfs @ 12.12 hrs, Volume= 0.077 af, Atten= 9%, Lag= 2.3 min  
 Discarded = 0.03 cfs @ 12.12 hrs, Volume= 0.020 af  
 Primary = 0.81 cfs @ 12.12 hrs, Volume= 0.056 af  
 Routed to Pond P-2 : Infiltration Basin

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 123.50' @ 12.12 hrs Surf.Area= 473 sf Storage= 160 cf

Plug-Flow detention time= 5.3 min calculated for 0.077 af (100% of inflow)  
 Center-of-Mass det. time= 5.3 min ( 762.2 - 756.9 )

Volume	Invert	Avail.Storage	Storage Description
#1	123.00'	472 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
123.00	165	0	0
124.00	779	472	472

Device	Routing	Invert	Outlet Devices
#1	Primary	123.00'	<b>12.0" Round Culvert</b> L= 69.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 123.00' / 122.50' S= 0.0072 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Discarded	123.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.03 cfs @ 12.12 hrs HW=123.49' (Free Discharge)  
 ↑**2=Exfiltration** (Exfiltration Controls 0.03 cfs)

**Primary OutFlow** Max=0.79 cfs @ 12.12 hrs HW=123.49' TW=122.30' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 0.79 cfs @ 2.97 fps)

### Summary for Pond P-2: Infiltration Basin

Inflow Area = 0.570 ac, 32.04% Impervious, Inflow Depth = 1.62" for 5-Year event  
 Inflow = 1.03 cfs @ 12.11 hrs, Volume= 0.077 af  
 Outflow = 0.14 cfs @ 12.68 hrs, Volume= 0.077 af, Atten= 86%, Lag= 33.8 min  
 Discarded = 0.14 cfs @ 12.68 hrs, Volume= 0.077 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Routed to Link DP-2 : East Low Point

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 122.55' @ 12.68 hrs Surf.Area= 2,510 sf Storage= 1,229 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 65.4 min ( 819.0 - 753.6 )

# Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.42"

Printed 10/25/2023

Page 18

Volume	Invert	Avail.Storage	Storage Description
#1	122.00'	5,937 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.00	1,944	0	0
124.00	3,993	5,937	5,937

Device	Routing	Invert	Outlet Devices
#1	Primary	123.99'	<b>15.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#2	Discarded	122.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.14 cfs @ 12.68 hrs HW=122.55' (Free Discharge)

↳ **2=Exfiltration** (Exfiltration Controls 0.14 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=122.00' TW=0.00' (Dynamic Tailwater)

↳ **1=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)

## Summary for Link DP-1: West Wetlands

Inflow Area = 0.271 ac, 4.58% Impervious, Inflow Depth = 2.42" for 5-Year event  
Inflow = 0.67 cfs @ 12.09 hrs, Volume= 0.055 af  
Primary = 0.67 cfs @ 12.09 hrs, Volume= 0.055 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Summary for Link DP-2: East Low Point

Inflow Area = 0.743 ac, 24.58% Impervious, Inflow Depth = 0.00" for 5-Year event  
Inflow = 0.00 cfs @ 24.00 hrs, Volume= 0.000 af  
Primary = 0.00 cfs @ 24.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs



**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.28"

Printed 10/25/2023

Page 19

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West** Runoff Area=3,356 sf 15.85% Impervious Runoff Depth=3.14"  
Tc=6.0 min CN=WQ Runoff=0.24 cfs 0.020 af

**SubcatchmentSC-2: Overland to Forebay** Runoff Area=11,864 sf 62.53% Impervious Runoff Depth=3.25"  
Tc=6.0 min CN=WQ Runoff=0.86 cfs 0.074 af

**SubcatchmentSC-3: Overland to Basin** Runoff Area=9,595 sf 0.00% Impervious Runoff Depth=1.46"  
Tc=6.0 min CN=WQ Runoff=0.28 cfs 0.027 af

**SubcatchmentSC-4: Basin Berm and** Runoff Area=7,531 sf 0.00% Impervious Runoff Depth=0.05"  
Tc=6.0 min CN=32 Runoff=0.00 cfs 0.001 af

**SubcatchmentSC-5: Overland to West** Runoff Area=11,789 sf 4.58% Impervious Runoff Depth=3.00"  
Tc=6.0 min CN=WQ Runoff=0.81 cfs 0.068 af

**Pond P-1: Forebay** Peak Elev=123.56' Storage=188 cf Inflow=1.10 cfs 0.094 af  
Discarded=0.03 cfs 0.022 af Primary=0.97 cfs 0.072 af Outflow=1.00 cfs 0.094 af

**Pond P-2: Infiltration Basin** Peak Elev=122.70' Storage=1,612 cf Inflow=1.23 cfs 0.099 af  
Discarded=0.15 cfs 0.099 af Primary=0.00 cfs 0.000 af Outflow=0.15 cfs 0.099 af

**Link DP-1: West Wetlands** Inflow=0.81 cfs 0.068 af  
Primary=0.81 cfs 0.068 af

**Link DP-2: East Low Point** Inflow=0.00 cfs 0.001 af  
Primary=0.00 cfs 0.001 af

**Total Runoff Area = 1.013 ac Runoff Volume = 0.189 af Average Runoff Depth = 2.24"**  
**80.76% Pervious = 0.818 ac 19.24% Impervious = 0.195 ac**

### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.28"

Printed 10/25/2023

Page 20

### Summary for Subcatchment SC-1: Overland to West Wetland

Runoff = 0.24 cfs @ 12.09 hrs, Volume= 0.020 af, Depth= 3.14"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Year Rainfall=5.28"

Area (sf)	CN	Description
532	98	Paved parking, HSG A
1,256	39	Pasture/grassland/range, Good, HSG A
1,568	96	Gravel surface, HSG A
3,356		Weighted Average
2,824	71	84.15% Pervious Area
532	98	15.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Summary for Subcatchment SC-2: Overland to Forebay

Runoff = 0.86 cfs @ 12.09 hrs, Volume= 0.074 af, Depth= 3.25"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Year Rainfall=5.28"

Area (sf)	CN	Description
7,418	98	Paved parking, HSG A
4,446	39	Pasture/grassland/range, Good, HSG A
11,864		Weighted Average
4,446	39	37.47% Pervious Area
7,418	98	62.53% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Summary for Subcatchment SC-3: Overland to Basin

Runoff = 0.28 cfs @ 12.09 hrs, Volume= 0.027 af, Depth= 1.46"

Routed to Pond P-2 : Infiltration Basin

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Year Rainfall=5.28"

**Millis Well 3 Proposed**

Type III 24-hr 10-Year Rainfall=5.28"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 21

Area (sf)	CN	Description
2,407	98	Water Surface, 0% imp, HSG A
7,188	39	Pasture/grassland/range, Good, HSG A
9,595		Weighted Average
9,595	54	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-4: Basin Berm and Shoulder**

Runoff = 0.00 cfs @ 16.79 hrs, Volume= 0.001 af, Depth= 0.05"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Year Rainfall=5.28"

Area (sf)	CN	Description
7,531	32	Woods/grass comb., Good, HSG A
7,531	32	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-5: Overland to West Wetland**

Runoff = 0.81 cfs @ 12.09 hrs, Volume= 0.068 af, Depth= 3.00"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Year Rainfall=5.28"

Area (sf)	CN	Description
* 540	98	Impervious, HSG A
4,724	39	Pasture/grassland/range, Good, HSG A
6,525	96	Gravel surface, HSG A
11,789		Weighted Average
11,249	72	95.42% Pervious Area
540	98	4.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min



### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.28"

Printed 10/25/2023

Page 22

### Summary for Pond P-1: Forebay

Inflow Area = 0.349 ac, 52.23% Impervious, Inflow Depth = 3.23" for 10-Year event  
 Inflow = 1.10 cfs @ 12.09 hrs, Volume= 0.094 af  
 Outflow = 1.00 cfs @ 12.12 hrs, Volume= 0.094 af, Atten= 9%, Lag= 2.3 min  
 Discarded = 0.03 cfs @ 12.12 hrs, Volume= 0.022 af  
 Primary = 0.97 cfs @ 12.12 hrs, Volume= 0.072 af  
 Routed to Pond P-2 : Infiltration Basin

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 123.56' @ 12.12 hrs Surf.Area= 508 sf Storage= 188 cf

Plug-Flow detention time= 5.3 min calculated for 0.094 af (100% of inflow)  
 Center-of-Mass det. time= 5.4 min ( 762.1 - 756.7 )

Volume	Invert	Avail.Storage	Storage Description
#1	123.00'	472 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
123.00	165	0	0
124.00	779	472	472

Device	Routing	Invert	Outlet Devices
#1	Primary	123.00'	<b>12.0" Round Culvert</b> L= 69.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 123.00' / 122.50' S= 0.0072 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Discarded	123.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.03 cfs @ 12.12 hrs HW=123.55' (Free Discharge)  
 ↑**2=Exfiltration** (Exfiltration Controls 0.03 cfs)

**Primary OutFlow** Max=0.95 cfs @ 12.12 hrs HW=123.55' TW=122.38' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 0.95 cfs @ 3.10 fps)

### Summary for Pond P-2: Infiltration Basin

Inflow Area = 0.570 ac, 32.04% Impervious, Inflow Depth = 2.09" for 10-Year event  
 Inflow = 1.23 cfs @ 12.11 hrs, Volume= 0.099 af  
 Outflow = 0.15 cfs @ 12.81 hrs, Volume= 0.099 af, Atten= 88%, Lag= 41.9 min  
 Discarded = 0.15 cfs @ 12.81 hrs, Volume= 0.099 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Routed to Link DP-2 : East Low Point

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 122.70' @ 12.81 hrs Surf.Area= 2,661 sf Storage= 1,612 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 85.2 min ( 845.4 - 760.2 )

# Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.28"

Printed 10/25/2023

Page 23

Volume	Invert	Avail.Storage	Storage Description
#1	122.00'	5,937 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.00	1,944	0	0
124.00	3,993	5,937	5,937

Device	Routing	Invert	Outlet Devices
#1	Primary	123.99'	<b>15.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#2	Discarded	122.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.15 cfs @ 12.81 hrs HW=122.70' (Free Discharge)

↳ **2=Exfiltration** (Exfiltration Controls 0.15 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=122.00' TW=0.00' (Dynamic Tailwater)

↳ **1=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)

## Summary for Link DP-1: West Wetlands

Inflow Area = 0.271 ac, 4.58% Impervious, Inflow Depth = 3.00" for 10-Year event  
Inflow = 0.81 cfs @ 12.09 hrs, Volume= 0.068 af  
Primary = 0.81 cfs @ 12.09 hrs, Volume= 0.068 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Summary for Link DP-2: East Low Point

Inflow Area = 0.743 ac, 24.58% Impervious, Inflow Depth = 0.01" for 10-Year event  
Inflow = 0.00 cfs @ 16.79 hrs, Volume= 0.001 af  
Primary = 0.00 cfs @ 16.79 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 24

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West** Runoff Area=3,356 sf 15.85% Impervious Runoff Depth=3.99"  
Tc=6.0 min CN=WQ Runoff=0.30 cfs 0.026 af

**SubcatchmentSC-2: Overland to Forebay** Runoff Area=11,864 sf 62.53% Impervious Runoff Depth=4.10"  
Tc=6.0 min CN=WQ Runoff=1.06 cfs 0.093 af

**SubcatchmentSC-3: Overland to Basin** Runoff Area=9,595 sf 0.00% Impervious Runoff Depth=1.99"  
Tc=6.0 min CN=WQ Runoff=0.36 cfs 0.037 af

**SubcatchmentSC-4: Basin Berm and** Runoff Area=7,531 sf 0.00% Impervious Runoff Depth=0.21"  
Tc=6.0 min CN=32 Runoff=0.00 cfs 0.003 af

**SubcatchmentSC-5: Overland to West** Runoff Area=11,789 sf 4.58% Impervious Runoff Depth=3.83"  
Tc=6.0 min CN=WQ Runoff=1.01 cfs 0.086 af

**Pond P-1: Forebay** Peak Elev=123.63' Storage=227 cf Inflow=1.36 cfs 0.119 af  
Discarded=0.03 cfs 0.023 af Primary=1.20 cfs 0.095 af Outflow=1.23 cfs 0.119 af

**Pond P-2: Infiltration Basin** Peak Elev=122.93' Storage=2,241 cf Inflow=1.55 cfs 0.132 af  
Discarded=0.16 cfs 0.132 af Primary=0.00 cfs 0.000 af Outflow=0.16 cfs 0.132 af

**Link DP-1: West Wetlands** Inflow=1.01 cfs 0.086 af  
Primary=1.01 cfs 0.086 af

**Link DP-2: East Low Point** Inflow=0.00 cfs 0.003 af  
Primary=0.00 cfs 0.003 af

**Total Runoff Area = 1.013 ac Runoff Volume = 0.245 af Average Runoff Depth = 2.90"**  
**80.76% Pervious = 0.818 ac 19.24% Impervious = 0.195 ac**

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 25

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 0.30 cfs @ 12.09 hrs, Volume= 0.026 af, Depth= 3.99"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-Year Rainfall=6.45"

Area (sf)	CN	Description
532	98	Paved parking, HSG A
1,256	39	Pasture/grassland/range, Good, HSG A
1,568	96	Gravel surface, HSG A
3,356		Weighted Average
2,824	71	84.15% Pervious Area
532	98	15.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to Forebay**

Runoff = 1.06 cfs @ 12.09 hrs, Volume= 0.093 af, Depth= 4.10"

Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-Year Rainfall=6.45"

Area (sf)	CN	Description
7,418	98	Paved parking, HSG A
4,446	39	Pasture/grassland/range, Good, HSG A
11,864		Weighted Average
4,446	39	37.47% Pervious Area
7,418	98	62.53% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-3: Overland to Basin**

Runoff = 0.36 cfs @ 12.10 hrs, Volume= 0.037 af, Depth= 1.99"

Routed to Pond P-2 : Infiltration Basin

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-Year Rainfall=6.45"



**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 26

Area (sf)	CN	Description
2,407	98	Water Surface, 0% imp, HSG A
7,188	39	Pasture/grassland/range, Good, HSG A
9,595		Weighted Average
9,595	54	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-4: Basin Berm and Shoulder**

Runoff = 0.00 cfs @ 13.72 hrs, Volume= 0.003 af, Depth= 0.21"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 25-Year Rainfall=6.45"

Area (sf)	CN	Description
7,531	32	Woods/grass comb., Good, HSG A
7,531	32	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-5: Overland to West Wetland**

Runoff = 1.01 cfs @ 12.09 hrs, Volume= 0.086 af, Depth= 3.83"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 25-Year Rainfall=6.45"

Area (sf)	CN	Description
* 540	98	Impervious, HSG A
4,724	39	Pasture/grassland/range, Good, HSG A
6,525	96	Gravel surface, HSG A
11,789		Weighted Average
11,249	72	95.42% Pervious Area
540	98	4.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 27

### Summary for Pond P-1: Forebay

Inflow Area = 0.349 ac, 52.23% Impervious, Inflow Depth = 4.08" for 25-Year event  
 Inflow = 1.36 cfs @ 12.09 hrs, Volume= 0.119 af  
 Outflow = 1.23 cfs @ 12.13 hrs, Volume= 0.119 af, Atten= 10%, Lag= 2.4 min  
 Discarded = 0.03 cfs @ 12.13 hrs, Volume= 0.023 af  
 Primary = 1.20 cfs @ 12.13 hrs, Volume= 0.095 af  
 Routed to Pond P-2 : Infiltration Basin

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 123.63' @ 12.13 hrs Surf.Area= 553 sf Storage= 227 cf

Plug-Flow detention time= 5.4 min calculated for 0.119 af (100% of inflow)  
 Center-of-Mass det. time= 5.5 min ( 762.2 - 756.7 )

Volume	Invert	Avail.Storage	Storage Description
#1	123.00'	472 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
123.00	165	0	0
124.00	779	472	472

Device	Routing	Invert	Outlet Devices
#1	Primary	123.00'	<b>12.0" Round Culvert</b> L= 69.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 123.00' / 122.50' S= 0.0072 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Discarded	123.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.03 cfs @ 12.13 hrs HW=123.62' (Free Discharge)  
 ↑**2=Exfiltration** (Exfiltration Controls 0.03 cfs)

**Primary OutFlow** Max=1.17 cfs @ 12.13 hrs HW=123.62' TW=122.51' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 1.17 cfs @ 3.25 fps)

### Summary for Pond P-2: Infiltration Basin

Inflow Area = 0.570 ac, 32.04% Impervious, Inflow Depth = 2.78" for 25-Year event  
 Inflow = 1.55 cfs @ 12.12 hrs, Volume= 0.132 af  
 Outflow = 0.16 cfs @ 13.02 hrs, Volume= 0.132 af, Atten= 90%, Lag= 54.2 min  
 Discarded = 0.16 cfs @ 13.02 hrs, Volume= 0.132 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Routed to Link DP-2 : East Low Point

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 122.93' @ 13.02 hrs Surf.Area= 2,893 sf Storage= 2,241 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 117.0 min ( 882.8 - 765.8 )

# Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.45"

Printed 10/25/2023

Page 28

Volume	Invert	Avail.Storage	Storage Description
#1	122.00'	5,937 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.00	1,944	0	0
124.00	3,993	5,937	5,937

Device	Routing	Invert	Outlet Devices
#1	Primary	123.99'	<b>15.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#2	Discarded	122.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.16 cfs @ 13.02 hrs HW=122.93' (Free Discharge)

↳ **2=Exfiltration** (Exfiltration Controls 0.16 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=122.00' TW=0.00' (Dynamic Tailwater)

↳ **1=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)

## Summary for Link DP-1: West Wetlands

Inflow Area = 0.271 ac, 4.58% Impervious, Inflow Depth = 3.83" for 25-Year event  
Inflow = 1.01 cfs @ 12.09 hrs, Volume= 0.086 af  
Primary = 1.01 cfs @ 12.09 hrs, Volume= 0.086 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Summary for Link DP-2: East Low Point

Inflow Area = 0.743 ac, 24.58% Impervious, Inflow Depth = 0.05" for 25-Year event  
Inflow = 0.00 cfs @ 13.72 hrs, Volume= 0.003 af  
Primary = 0.00 cfs @ 13.72 hrs, Volume= 0.003 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

**Millis Well 3 Proposed**

Type III 24-hr 100-Year Rainfall=8.27"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 29

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**SubcatchmentSC-1: Overland to West** Runoff Area=3,356 sf 15.85% Impervious Runoff Depth=5.39"  
Tc=6.0 min CN=WQ Runoff=0.41 cfs 0.035 af

**SubcatchmentSC-2: Overland to Forebay** Runoff Area=11,864 sf 62.53% Impervious Runoff Depth=5.50"  
Tc=6.0 min CN=WQ Runoff=1.45 cfs 0.125 af

**SubcatchmentSC-3: Overland to Basin** Runoff Area=9,595 sf 0.00% Impervious Runoff Depth=2.97"  
Tc=6.0 min CN=WQ Runoff=0.60 cfs 0.054 af

**SubcatchmentSC-4: Basin Berm and** Runoff Area=7,531 sf 0.00% Impervious Runoff Depth=0.64"  
Tc=6.0 min CN=32 Runoff=0.05 cfs 0.009 af

**SubcatchmentSC-5: Overland to West** Runoff Area=11,789 sf 4.58% Impervious Runoff Depth=5.19"  
Tc=6.0 min CN=WQ Runoff=1.38 cfs 0.117 af

**Pond P-1: Forebay** Peak Elev=123.76' Storage=304 cf Inflow=1.85 cfs 0.159 af  
Discarded=0.04 cfs 0.027 af Primary=1.62 cfs 0.133 af Outflow=1.66 cfs 0.159 af

**Pond P-2: Infiltration Basin** Peak Elev=123.31' Storage=3,415 cf Inflow=2.19 cfs 0.187 af  
Discarded=0.18 cfs 0.187 af Primary=0.00 cfs 0.000 af Outflow=0.18 cfs 0.187 af

**Link DP-1: West Wetlands** Inflow=1.38 cfs 0.117 af  
Primary=1.38 cfs 0.117 af

**Link DP-2: East Low Point** Inflow=0.05 cfs 0.009 af  
Primary=0.05 cfs 0.009 af

**Total Runoff Area = 1.013 ac Runoff Volume = 0.340 af Average Runoff Depth = 4.03"**  
**80.76% Pervious = 0.818 ac 19.24% Impervious = 0.195 ac**



**Millis Well 3 Proposed**

Type III 24-hr 100-Year Rainfall=8.27"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 30

**Summary for Subcatchment SC-1: Overland to West Wetland**

Runoff = 0.41 cfs @ 12.09 hrs, Volume= 0.035 af, Depth= 5.39"  
 Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 100-Year Rainfall=8.27"

Area (sf)	CN	Description
532	98	Paved parking, HSG A
1,256	39	Pasture/grassland/range, Good, HSG A
1,568	96	Gravel surface, HSG A
3,356		Weighted Average
2,824	71	84.15% Pervious Area
532	98	15.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-2: Overland to Forebay**

Runoff = 1.45 cfs @ 12.09 hrs, Volume= 0.125 af, Depth= 5.50"  
 Routed to Pond P-1 : Forebay

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 100-Year Rainfall=8.27"

Area (sf)	CN	Description
7,418	98	Paved parking, HSG A
4,446	39	Pasture/grassland/range, Good, HSG A
11,864		Weighted Average
4,446	39	37.47% Pervious Area
7,418	98	62.53% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Tc Min

**Summary for Subcatchment SC-3: Overland to Basin**

Runoff = 0.60 cfs @ 12.10 hrs, Volume= 0.054 af, Depth= 2.97"  
 Routed to Pond P-2 : Infiltration Basin

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 100-Year Rainfall=8.27"

**Millis Well 3 Proposed**

Type III 24-hr 100-Year Rainfall=8.27"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 31

Area (sf)	CN	Description
2,407	98	Water Surface, 0% imp, HSG A
7,188	39	Pasture/grassland/range, Good, HSG A
9,595		Weighted Average
9,595	54	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Tc Min</b>

**Summary for Subcatchment SC-4: Basin Berm and Shoulder**

Runoff = 0.05 cfs @ 12.34 hrs, Volume= 0.009 af, Depth= 0.64"  
 Routed to Link DP-2 : East Low Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 100-Year Rainfall=8.27"

Area (sf)	CN	Description
7,531	32	Woods/grass comb., Good, HSG A
7,531	32	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Tc Min</b>

**Summary for Subcatchment SC-5: Overland to West Wetland**

Runoff = 1.38 cfs @ 12.09 hrs, Volume= 0.117 af, Depth= 5.19"  
 Routed to Link DP-1 : West Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 100-Year Rainfall=8.27"

Area (sf)	CN	Description
* 540	98	Impervious, HSG A
4,724	39	Pasture/grassland/range, Good, HSG A
6,525	96	Gravel surface, HSG A
11,789		Weighted Average
11,249	72	95.42% Pervious Area
540	98	4.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Tc Min</b>

### Millis Well 3 Proposed

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.27"

Printed 10/25/2023

Page 32

### Summary for Pond P-1: Forebay

Inflow Area = 0.349 ac, 52.23% Impervious, Inflow Depth = 5.47" for 100-Year event  
 Inflow = 1.85 cfs @ 12.09 hrs, Volume= 0.159 af  
 Outflow = 1.66 cfs @ 12.13 hrs, Volume= 0.159 af, Atten= 11%, Lag= 2.5 min  
 Discarded = 0.04 cfs @ 12.13 hrs, Volume= 0.027 af  
 Primary = 1.62 cfs @ 12.13 hrs, Volume= 0.133 af  
 Routed to Pond P-2 : Infiltration Basin

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 123.76' @ 12.13 hrs Surf.Area= 633 sf Storage= 304 cf

Plug-Flow detention time= 6.5 min calculated for 0.159 af (100% of inflow)  
 Center-of-Mass det. time= 6.6 min ( 763.5 - 757.0 )

Volume	Invert	Avail.Storage	Storage Description
#1	123.00'	472 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
123.00	165	0	0
124.00	779	472	472

Device	Routing	Invert	Outlet Devices
#1	Primary	123.00'	<b>12.0" Round Culvert</b> L= 69.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 123.00' / 122.50' S= 0.0072 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Discarded	123.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.03 cfs @ 12.13 hrs HW=123.75' (Free Discharge)  
 ↑**2=Exfiltration** (Exfiltration Controls 0.03 cfs)

**Primary OutFlow** Max=1.59 cfs @ 12.13 hrs HW=123.75' TW=122.74' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 1.59 cfs @ 3.48 fps)

### Summary for Pond P-2: Infiltration Basin

Inflow Area = 0.570 ac, 32.04% Impervious, Inflow Depth = 3.95" for 100-Year event  
 Inflow = 2.19 cfs @ 12.12 hrs, Volume= 0.187 af  
 Outflow = 0.18 cfs @ 13.37 hrs, Volume= 0.187 af, Atten= 92%, Lag= 75.3 min  
 Discarded = 0.18 cfs @ 13.37 hrs, Volume= 0.187 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af  
 Routed to Link DP-2 : East Low Point

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 123.31' @ 13.37 hrs Surf.Area= 3,283 sf Storage= 3,415 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 171.8 min ( 942.3 - 770.5 )

# Millis Well 3 Proposed

Type III 24-hr 100-Year Rainfall=8.27"

Prepared by Kleinfelder

Printed 10/25/2023

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Page 33

Volume	Invert	Avail.Storage	Storage Description
#1	122.00'	5,937 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.00	1,944	0	0
124.00	3,993	5,937	5,937

Device	Routing	Invert	Outlet Devices
#1	Primary	123.99'	<b>15.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#2	Discarded	122.00'	<b>2.410 in/hr Exfiltration over Surface area</b>

**Discarded OutFlow** Max=0.18 cfs @ 13.37 hrs HW=123.31' (Free Discharge)

↑**2=Exfiltration** (Exfiltration Controls 0.18 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=122.00' TW=0.00' (Dynamic Tailwater)

↑**1=Sharp-Crested Rectangular Weir**( Controls 0.00 cfs)

## Summary for Link DP-1: West Wetlands

Inflow Area = 0.271 ac, 4.58% Impervious, Inflow Depth = 5.19" for 100-Year event  
 Inflow = 1.38 cfs @ 12.09 hrs, Volume= 0.117 af  
 Primary = 1.38 cfs @ 12.09 hrs, Volume= 0.117 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Summary for Link DP-2: East Low Point

Inflow Area = 0.743 ac, 24.58% Impervious, Inflow Depth = 0.15" for 100-Year event  
 Inflow = 0.05 cfs @ 12.34 hrs, Volume= 0.009 af  
 Primary = 0.05 cfs @ 12.34 hrs, Volume= 0.009 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs





Appendix D  
Stormwater Operation and Maintenance Plan

# STORMWATER OPERATION AND MAINTANENCE PLAN (O&M)

Owner/

Operator: Town of Millis  
Public Works/ Highway Department  
900 Main Street, Room 204  
Millis, MA 02054

Prepared by: Kleinfelder  
1 Beacon Street, Suite 8100  
Boston, MA 02118

The following operation and maintenance practices will be performed on the proposed stormwater system by the Owner (Town of Millis).

**Table OM-1** Summary of Stormwater System Operation & Maintenance Tasks Listed By Item

Item <i>location on site</i>	Frequency	What to do
Infiltration Basin	<p><u>1<sup>st</sup> &amp; 2<sup>nd</sup> Year Post Construction</u> Every 6 months, and after a major storm</p> <p>Inspection frequency can be reduced to annual following 2<sup>nd</sup> year post-construction monitoring.</p>	<p>Inspections should focus on:</p> <p>Checking the infiltration basin surface for standing water or accumulated sediments.</p> <p>Checking the sedimentation chamber or forebay for sediment accumulation, trash, and debris.</p> <p>Inspect to be certain the sedimentation forebay drains within 24 to 72 hrs.</p> <p>Checking inlets, outlets, and overflow spillway for blockage, structural integrity, and evidence of erosion.</p> <p>Removal of decaying vegetation, litter, and debris.</p>
Paved surfaces	Every Six Months or as needed	Sweep and remove sediment from paved wearing surfaces at the site.

**Table OM-1 – Continued**

Riprap Apron at Pressure Relief Outlet and Overflow Weir	Every Six Months, and after major storms	Inspect apron for excessive sediment accumulation, eroding slopes, rilling or gullyng, repair and clean as necessary.
	Once every 4 years	The apron should be cleaned of vegetation.
Rip rap aprons <i>At pipe outlets</i>	Annually, and after major storms	Inspect aprons after major storm events or at a minimum annually. Repair as necessary.
	Annually	Cleaning and remove debris from apron. Repair as necessary.
Water Conveyance Swales	Semi-annually, and after major storms	Inspect swales after major storm event. Clean debris, and repair as necessary
	Annually	Cleaning and remove debris from swales. Repair as necessary.

**Table OM-2** Annual Checklist of Stormwater System Operation & Maintenance Tasks Listed By Frequency.

Frequency	Item <i>location on site</i>	What to do	Date completed	Notes
Every Six Months	Paved surfaces	Sweep and remove sediment from paved surfaces on a semi-annual basis.		
	Riprap Aprons at Pressure Relief Outlet, Drain Outlet, and Overflow Weir	Inspect riprap aprons and Overflow Weir for excessive sediment accumulation, eroding slopes, rilling or gullyng, repair and clean as necessary		
	Water Conveyance Swale	Inspect and remove all accumulated sediment and debris.		

◆◆◆ These inspections should also be performed after all major storms (more than 3.5 inches of rain in a 24-hour period).



**Table OM-2 - Continued**

Frequency	Item location on site	What to do	Date completed	Notes
Every six months	Infiltration Basin	<p>☘☘☘  <u>1<sup>st</sup> &amp; 2<sup>nd</sup> Year Post Construction</u>                      Every 6 months, and after a major storm</p> <p>Inspection frequency can be reduced to annual following 1<sup>st</sup> and 2<sup>nd</sup> year post-construction monitoring.</p> <p>Remove any accumulated sediment deposits. Use light equipment to remove top layer without compacting underlying area.</p> <p>Mow the area around the detention basin. Remove all clippings after mowing.</p>		<p>Inspections should focus on:</p> <p>Checking the detention basin surface for standing water and accumulated sediments.</p> <p>Checking the sedimentation chamber or forebay for sediment accumulation, trash, and debris.</p> <p>Inspect to be certain the sedimentation forebay drains within 24 to 72 hrs.</p> <p>Checking inlets, outlets, and overflow spillway for blockage, structural integrity, and evidence of erosion.</p> <p>Removal of decaying vegetation, litter, and debris.</p>

☘☘☘ These inspections should also be performed after all major storms (more than 3.5 inches of rain in a 24-hour period).

# STORMWATER MANAGEMENT LONG TERM POLLUTION PREVENTION PLAN (LTPPP)

Owner/

Operators: Town of Millis Public Works/Highway Department  
900 Main Street, Room 204  
Millis, MA 02054

Prepared by: Kleinfelder  
1 Beacon Street, Suite 8100  
Boston, MA 02118

## **A. MATERIALS MANAGEMENT PRACTICES**

The following are the material management practices that will be used to reduce the risk of spills or other accidental exposure of materials and substances to stormwater runoff. The Owner and Operator will be responsible for ensuring that these procedures are followed:

### 1. Good Housekeeping

The following good housekeeping practices will be followed onsite:

- a) An effort will be made to store only enough products required to do the job.
- b) All materials stored onsite will be stored in a neat, orderly manner and, if possible, under a roof or in a containment area. At a minimum, all containers will be stored with their lids on when not in use. Drip pans shall be provided under all dispensers.
- c) Products will be kept in their original containers with the original manufacturer's label in legible condition.
- d) Substances will not be mixed with one another unless recommended by the manufacturer.
- e) Whenever possible, all of a product will be used up before disposing of the container.
- f) Manufacturer's recommendations for proper use and disposal will be followed.
- g) The Operator will be responsible for daily inspections for windblown litter and to ensure proper use and disposal of materials. Collection of all windblown litter will be deposited in an appropriate solid waste container.
- h) The Operator will be responsible for periodic street sweeping on an as need basis for all paved wearing surfaces on site. At a minimum sweeping shall be performed on a quarterly basis.

## 2. Hazardous Substances

These practices will be used to reduce the risks associated with Hazardous Substances. Material Safety Data Sheets (MSDS's) for each product with hazardous properties that is used at the Site will be obtained and used for the proper management of potential wastes that may result from these products. An MSDS will be posted in the immediate area where such product is stored and/or used and another copy of each MSDS will be maintained in the operations office at the Site. Each employee who must handle a Hazardous Substance will be instructed on the use of MSDS sheets for the product he/she is using, particularly regarding spill control techniques.

- a) Products will be kept in original containers with the original labels in legible condition.
- b) Original labels and MSDS's will be procured and used for each product.
- c) If surplus product must be disposed manufacturer's and local/state/federal required methods for proper disposal must be followed.

## 3. Hazardous Waste

It is imperative that all Hazardous Waste be properly identified and handled in accordance with all applicable Hazardous Waste Standards, including the storage, transport and disposal of the Hazardous Wastes. There are significant penalties for the improper handling of Hazardous Wastes. It is important that the Owner/Operator seeks appropriate assistance in making the determination of whether a substance or material is a Hazardous Waste. For example, Hazardous Waste may include certain Hazardous Substances, as well as pesticides, paints, paint solvents, cleaning solvents, pesticides, contaminated soils, and other materials, substances or chemicals that have been discarded (or are to be discarded) as being out-of-date, contaminated, or otherwise unusable, and can include the containers for those substances; other materials and substances can also be or become Hazardous Wastes, however. The Owner/Operator is also responsible for ensuring that all site personnel are instructed as to these Hazardous Waste requirements and also that the requirements are being followed.

## 4. Product Specific Practices

The following product specific practices will be followed on the site:

### Petroleum Products

All onsite vehicles will be monitored for leaks and receive regular preventative maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled. Drip pans shall be provided for all dispensers. Any asphalt substances used onsite will be applied according to the manufacturer's recommendations.

## Fertilizers

Fertilizers will be applied only in the minimum amounts recommended by the manufacturer. Fertilizer will not be stored on-site on a long-term basis. All temporary storage of fertilizer will be in a covered container. The contents of any partially used bags of fertilizer will be transferred to a sealable plastic bin to avoid spills.

## Paints, Paint Solvents, and Cleaning Solvents.

All containers will be tightly sealed and stored when not in use. Excess paint and solvents will not be discharged to the storm sewer system but will be properly disposed of according to manufacturer's instructions or federal, state, and local regulations.

## 5. Solid Wastes

All waste materials will be collected and stored in a covered or enclosed containers and/or securely contained metal dumpsters or compactors. The containers will comply with all local and state solid waste management regulations.

## **B. SPILL PREVENTION**

The Owner will train all personnel in the proper handling and cleanup of spilled Hazardous Substances or Oil. No spilled Hazardous Substances or Oil will be allowed to come in contact with stormwater discharges. If such contact occurs, the storm water discharge will be contained on site until appropriate measures in compliance with state and federal regulations are taken to dispose of such contaminated stormwater. It shall be the responsibility of the Owner to be properly trained, and to train all personnel in spill prevention and clean up procedures.

In order to prevent or minimize the potential for a spill of Hazardous Substances or Oil to come into contact with stormwater, the following steps will be implemented:

- a) All Hazardous Substances or Oil (such as pesticides, petroleum products, fertilizers, detergents, construction chemicals, acids, paints, paint solvents, and cleaning solvents, etc.) will be stored in a secure location, with their lids on, preferably under cover, when not in use.
- b) The minimum practical quantity of all such materials will be kept at the site.
- c) A spill control and containment kit (containing, for example, absorbent materials, acid neutralizing powder, brooms, dust pans, mops, rags, gloves, goggles, plastic and metal trash containers, etc.) will be provided at the storage site.
- d) Manufacturer's recommended methods for spill cleanup will be clearly posted and site personnel will be trained regarding these procedures and the location of the information and cleanup supplies.
- e) It is the Operators responsibility to ensure that all Hazardous Waste discovered or generated at the site is disposed of properly by a licensed hazardous material disposal company. The Operator is responsible for not exceeding Hazardous Waste storage requirements mandated by the EPA or state and local authority.



## **C. SNOW MANAGEMENT**

Snow management will be performed by the Millis Public Works/Highway Department. Snow will be placed and mounded on the side of River Road, as necessary. Melting snow will be allowed to percolate through the vegetated surface. In the spring, when all the snow has melted, all accumulated sediment, and debris remaining shall be cleaned and removed from the site.



Appendix E  
Water Quality Calculations

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.27"

Printed 10/25/2023

Page 1

**Stage-Area-Storage for Pond P-1: Forebay**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
123.00	165	0	123.52	484	169
123.01	171	2	123.53	490	174
123.02	177	3	123.54	497	179
123.03	183	5	123.55	503	184
123.04	190	7	123.56	509	189
123.05	196	9	123.57	515	194
123.06	202	11	123.58	521	199
123.07	208	13	123.59	527	204
123.08	214	15	123.60	533	210
123.09	220	17	123.61	540	215
123.10	226	20	123.62	546	220
123.11	233	22	123.63	552	226
123.12	239	24	123.64	558	231
123.13	245	27	123.65	564	237
123.14	251	29	123.66	570	243
123.15	257	32	123.67	576	248
123.16	263	34	123.68	583	254
123.17	269	37	123.69	589	260
123.18	276	40	123.70	595	266
123.19	282	42	123.71	601	272
123.20	288	45	123.72	607	278
123.21	294	48	123.73	613	284
123.22	300	51	123.74	619	290
123.23	306	54	123.75	626	296
123.24	312	57	123.76	632	303
123.25	319	60	123.77	638	309
123.26	325	64	123.78	644	315
123.27	331	67	123.79	650	322
123.28	337	70	123.80	656	328
123.29	343	74	123.81	662	335
123.30	349	77	123.82	668	342
123.31	355	81	123.83	675	348
123.32	361	84	123.84	681	355
123.33	368	88	123.85	687	362
123.34	374	92	123.86	693	369
123.35	380	95	123.87	699	376
123.36	386	99	123.88	705	383
123.37	392	103	123.89	711	390
123.38	398	107	123.90	718	397
123.39	404	111	123.91	724	404
123.40	411	115	123.92	730	412
123.41	417	119	123.93	736	419
123.42	423	123	123.94	742	426
123.43	429	128	123.95	748	434
123.44	435	132	123.96	754	441
123.45	441	136	123.97	761	449
123.46	447	141	123.98	767	457
123.47	454	145	123.99	773	464
123.48	460	150	124.00	<b>779</b>	<b>472</b>
123.49	466	155			
123.50	472	159			
123.51	478	164			

WQV requirement of 655 cf storage is met

**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.27"

Printed 10/25/2023

Page 2

**Stage-Area-Storage for Pond P-2: Infiltration Basin**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
122.00	1,944	0	122.52	2,477	1,149
122.01	1,954	19	122.53	2,487	1,174
122.02	1,964	39	122.54	2,497	1,199
122.03	1,975	59	122.55	2,507	1,224
122.04	1,985	79	122.56	2,518	1,249
122.05	1,995	98	122.57	2,528	1,275
122.06	2,005	118	122.58	2,538	1,300
122.07	2,016	139	122.59	2,548	1,325
122.08	2,026	159	122.60	2,559	1,351
122.09	2,036	179	122.61	2,569	1,376
122.10	2,046	200	122.62	2,579	1,402
122.11	2,057	220	122.63	2,589	1,428
122.12	2,067	241	122.64	2,600	1,454
122.13	2,077	261	122.65	2,610	1,480
122.14	2,087	282	122.66	2,620	1,506
122.15	2,098	303	122.67	2,630	1,532
122.16	2,108	324	122.68	2,641	1,559
122.17	2,118	345	122.69	2,651	1,585
122.18	2,128	367	122.70	2,661	1,612
122.19	2,139	388	122.71	2,671	1,638
122.20	2,149	409	122.72	2,682	1,665
122.21	2,159	431	122.73	2,692	1,692
122.22	2,169	452	122.74	2,702	1,719
122.23	2,180	474	122.75	2,712	1,746
122.24	2,190	496	122.76	2,723	1,773
122.25	2,200	518	122.77	2,733	1,801
122.26	2,210	540	122.78	2,743	1,828
122.27	2,221	562	122.79	2,753	1,855
122.28	2,231	584	122.80	2,764	1,883
122.29	2,241	607	122.81	2,774	1,911
122.30	2,251	629	122.82	2,784	1,939
122.31	2,262	652	122.83	2,794	1,966
122.32	2,272	675	122.84	2,805	1,994
122.33	2,282	697	122.85	2,815	2,023
122.34	2,292	720	122.86	2,825	2,051
122.35	2,303	743	122.87	2,835	2,079
122.36	2,313	766	122.88	2,846	2,107
122.37	2,323	789	122.89	2,856	2,136
122.38	2,333	813	122.90	2,866	2,165
122.39	2,344	836	122.91	2,876	2,193
122.40	2,354	860	122.92	2,887	2,222
122.41	2,364	883	122.93	2,897	2,251
122.42	2,374	907	122.94	2,907	2,280
122.43	2,385	931	122.95	2,917	2,309
122.44	2,395	955	122.96	2,928	2,338
122.45	2,405	979	122.97	2,938	2,368
122.46	2,415	1,003	122.98	2,948	2,397
122.47	2,426	1,027	122.99	2,958	2,427
122.48	2,436	1,051	123.00	2,969	2,456
122.49	2,446	1,076	123.01	2,979	2,486
122.50	2,456	1,100	123.02	2,989	2,516
122.51	2,466	1,125	123.03	2,999	2,546



**Millis Well 3 Proposed**

Prepared by Kleinfelder

HydroCAD® 10.20-2f s/n 00759 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.27"

Printed 10/25/2023

Page 3

**Stage-Area-Storage for Pond P-2: Infiltration Basin (continued)**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
123.04	3,009	2,576	123.56	3,542	4,279
123.05	3,020	2,606	123.57	3,552	4,315
123.06	3,030	2,636	123.58	3,563	4,350
123.07	3,040	2,667	123.59	3,573	4,386
123.08	3,050	2,697	123.60	3,583	4,422
123.09	3,061	2,728	123.61	3,593	4,458
123.10	3,071	2,758	123.62	3,604	4,494
123.11	3,081	2,789	123.63	3,614	4,530
123.12	3,091	2,820	123.64	3,624	4,566
123.13	3,102	2,851	123.65	3,634	4,602
123.14	3,112	2,882	123.66	3,645	4,639
123.15	3,122	2,913	123.67	3,655	4,675
123.16	3,132	2,944	123.68	3,665	4,712
123.17	3,143	2,976	123.69	3,675	4,748
123.18	3,153	3,007	123.70	3,686	4,785
123.19	3,163	3,039	123.71	3,696	4,822
123.20	3,173	3,070	123.72	3,706	4,859
123.21	3,184	3,102	123.73	3,716	4,896
123.22	3,194	3,134	123.74	3,727	4,933
123.23	3,204	3,166	123.75	3,737	4,971
123.24	3,214	3,198	123.76	3,747	5,008
123.25	3,225	3,230	123.77	3,757	5,046
123.26	3,235	3,263	123.78	3,768	5,083
123.27	3,245	3,295	123.79	3,778	5,121
123.28	3,255	3,328	123.80	3,788	5,159
123.29	3,266	3,360	123.81	3,798	5,197
123.30	3,276	3,393	123.82	3,809	5,235
123.31	3,286	3,426	123.83	3,819	5,273
123.32	3,296	3,459	123.84	3,829	5,311
123.33	3,307	3,492	123.85	3,839	5,350
123.34	3,317	3,525	123.86	3,850	5,388
123.35	3,327	3,558	123.87	3,860	5,427
123.36	3,337	3,591	123.88	3,870	5,465
123.37	3,348	3,625	123.89	3,880	5,504
123.38	3,358	3,658	123.90	3,891	5,543
123.39	3,368	3,692	123.91	3,901	5,582
123.40	3,378	3,726	123.92	3,911	5,621
123.41	3,389	3,759	123.93	3,921	5,660
123.42	3,399	3,793	123.94	3,932	5,699
123.43	3,409	3,827	123.95	3,942	5,739
123.44	3,419	3,862	123.96	3,952	5,778
123.45	3,430	3,896	123.97	3,962	5,818
123.46	3,440	3,930	123.98	3,973	5,857
123.47	3,450	3,965	123.99	3,983	5,897
123.48	3,460	3,999	124.00	<b>3,993</b>	<b>5,937</b>
123.49	3,471	4,034			
<b>123.50</b>	<b>3,481</b>	<b>4,069</b>			
123.51	3,491	4,103			
123.52	3,501	4,138			
123.53	3,511	4,173			
123.54	3,522	4,209			
123.55	3,532	4,244			

Elevation 123.50 is the top elevation of the overflow spillway. Water stored below this elevation will be infiltrated.

**INSTRUCTIONS:**

1. In BMP Column, click on Blue Cell to Activate Drop Down Menu
2. Select BMP from Drop Down Menu
3. After BMP is selected, TSS Removal and other Columns are automatically completed.

Version 1, Automated: Mar. 4, 2008

Location:

	B	C	D	E	F
	BMP <sup>1</sup>	TSS Removal Rate <sup>1</sup>	Starting TSS Load*	Amount Removed (C*D)	Remaining Load (D-E)
<b>TSS Removal Calculation Worksheet</b>	Sediment Forebay	0.25	1.00	0.25	0.75
	Infiltration Basin	0.80	0.75	0.60	0.15
		0.00	0.15	0.00	0.15
		0.00	0.15	0.00	0.15
		0.00	0.15	0.00	0.15

**Total TSS Removal =**

**Separate Form Needs to be Completed for Each Outlet or BMP Train**

Project:   
 Prepared By:   
 Date:

\*Equals remaining load from previous BMP (E) which enters the BMP

Non-automated TSS Calculation Sheet must be used if Proprietary BMP Proposed  
 1. From MassDEP Stormwater Handbook Vol. 1



Appendix F  
Project Data: NOAA Rainfall and NRCS Web Soil Survey



**POINT PRECIPITATION FREQUENCY ESTIMATES**

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

**PF tabular**

<b>PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)<sup>1</sup></b>										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.323 (0.250-0.413)	0.392 (0.303-0.502)	0.505 (0.389-0.649)	0.599 (0.459-0.774)	0.728 (0.541-0.987)	0.825 (0.601-1.14)	0.927 (0.658-1.34)	1.04 (0.701-1.54)	1.21 (0.786-1.86)	1.36 (0.858-2.12)
10-min	0.458 (0.354-0.585)	0.556 (0.429-0.712)	0.716 (0.551-0.920)	0.849 (0.650-1.10)	1.03 (0.767-1.40)	1.17 (0.852-1.62)	1.31 (0.932-1.90)	1.48 (0.993-2.18)	1.72 (1.11-2.63)	1.92 (1.22-3.00)
15-min	0.539 (0.417-0.689)	0.654 (0.505-0.837)	0.842 (0.649-1.08)	0.999 (0.765-1.29)	1.21 (0.902-1.65)	1.38 (1.00-1.91)	1.54 (1.10-2.23)	1.74 (1.17-2.57)	2.02 (1.31-3.10)	2.26 (1.43-3.53)
30-min	0.738 (0.571-0.944)	0.898 (0.694-1.15)	1.16 (0.892-1.49)	1.38 (1.06-1.78)	1.67 (1.24-2.27)	1.90 (1.38-2.63)	2.13 (1.51-3.08)	2.40 (1.61-3.55)	2.80 (1.81-4.28)	3.12 (1.98-4.88)
60-min	0.937 (0.725-1.20)	1.14 (0.882-1.46)	1.48 (1.14-1.90)	1.75 (1.34-2.27)	2.13 (1.59-2.89)	2.42 (1.76-3.36)	2.72 (1.93-3.93)	3.07 (2.06-4.53)	3.57 (2.31-5.47)	3.98 (2.52-6.23)
2-hr	1.20 (0.931-1.52)	1.47 (1.14-1.87)	1.92 (1.49-2.46)	2.30 (1.77-2.96)	2.82 (2.11-3.81)	3.20 (2.35-4.43)	3.61 (2.59-5.23)	4.11 (2.77-6.03)	4.86 (3.16-7.40)	5.51 (3.50-8.55)
3-hr	1.38 (1.08-1.75)	1.71 (1.33-2.16)	2.24 (1.74-2.85)	2.68 (2.07-3.42)	3.28 (2.47-4.43)	3.73 (2.75-5.16)	4.22 (3.04-6.09)	4.81 (3.25-7.03)	5.73 (3.72-8.67)	6.52 (4.14-10.1)
6-hr	1.79 (1.40-2.25)	2.20 (1.72-2.77)	2.87 (2.24-3.62)	3.43 (2.66-4.35)	4.19 (3.17-5.62)	4.76 (3.53-6.54)	5.38 (3.90-7.72)	6.14 (4.16-8.90)	7.31 (4.77-11.0)	8.33 (5.31-12.8)
12-hr	2.29 (1.81-2.86)	2.79 (2.20-3.49)	3.62 (2.85-4.54)	4.30 (3.37-5.43)	5.25 (3.99-6.97)	5.94 (4.43-8.09)	6.70 (4.88-9.53)	7.62 (5.19-11.0)	9.04 (5.92-13.5)	10.3 (6.56-15.6)
24-hr	2.76 (2.19-3.42)	3.39 (2.69-4.20)	4.42 (3.50-5.51)	5.28 (4.15-6.61)	6.45 (4.93-8.52)	7.32 (5.49-9.91)	8.27 (6.06-11.7)	9.44 (6.45-13.5)	11.3 (7.39-16.6)	12.8 (8.23-19.3)
2-day	3.13 (2.50-3.85)	3.91 (3.13-4.82)	5.20 (4.14-6.43)	6.26 (4.96-7.80)	7.73 (5.95-10.2)	8.80 (6.66-11.9)	9.99 (7.39-14.1)	11.5 (7.88-16.3)	13.9 (9.17-20.4)	16.1 (10.3-24.0)
3-day	3.41 (2.74-4.19)	4.26 (3.42-5.23)	5.64 (4.51-6.96)	6.79 (5.40-8.42)	8.38 (6.47-11.0)	9.53 (7.23-12.8)	10.8 (8.03-15.2)	12.5 (8.55-17.6)	15.1 (9.96-22.1)	17.4 (11.2-25.9)
4-day	3.68 (2.96-4.50)	4.56 (3.66-5.58)	5.99 (4.80-7.36)	7.18 (5.72-8.87)	8.82 (6.82-11.5)	10.0 (7.61-13.4)	11.3 (8.43-15.9)	13.0 (8.97-18.3)	15.8 (10.4-22.9)	18.2 (11.7-26.9)
7-day	4.43 (3.58-5.39)	5.35 (4.32-6.52)	6.86 (5.52-8.38)	8.10 (6.48-9.96)	9.82 (7.62-12.7)	11.1 (8.44-14.7)	12.5 (9.26-17.3)	14.2 (9.81-19.8)	17.0 (11.2-24.5)	19.3 (12.5-28.5)
10-day	5.14 (4.17-6.23)	6.09 (4.93-7.39)	7.63 (6.16-9.30)	8.92 (7.16-10.9)	10.7 (8.31-13.7)	12.0 (9.14-15.8)	13.4 (9.94-18.4)	15.1 (10.5-21.0)	17.8 (11.8-25.6)	20.1 (13.1-29.5)
20-day	7.23 (5.90-8.71)	8.25 (6.72-9.94)	9.91 (8.05-12.0)	11.3 (9.11-13.7)	13.2 (10.3-16.7)	14.6 (11.1-18.9)	16.1 (11.9-21.6)	17.8 (12.4-24.5)	20.2 (13.5-28.7)	22.1 (14.4-32.2)
30-day	8.96 (7.34-10.7)	10.0 (8.21-12.0)	11.8 (9.59-14.2)	13.2 (10.7-16.0)	15.2 (11.9-19.1)	16.7 (12.7-21.4)	18.3 (13.4-24.2)	19.9 (13.9-27.2)	22.0 (14.8-31.2)	23.7 (15.5-34.3)
45-day	11.1 (9.14-13.3)	12.2 (10.0-14.6)	14.1 (11.5-16.9)	15.6 (12.7-18.8)	17.7 (13.8-22.0)	19.3 (14.7-24.5)	20.9 (15.3-27.3)	22.4 (15.7-30.4)	24.3 (16.3-34.2)	25.7 (16.8-37.0)
60-day	12.9 (10.7-15.4)	14.1 (11.6-16.8)	16.0 (13.1-19.1)	17.5 (14.3-21.1)	19.7 (15.4-24.4)	21.4 (16.3-27.0)	23.0 (16.8-29.8)	24.5 (17.2-33.1)	26.2 (17.6-36.7)	27.3 (17.9-39.2)

<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.





[Back to Top](#)

**PF graphical**



PDS-based depth-duration-frequency (DDF) curves


Latitude: 42.1662°, Longitude: -71.3406°



[Back to Top](#)

**Maps & aeriels**


**Small scale terrain**




Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)


---

[US Department of Commerce](#)  
[National Oceanic and Atmospheric Administration](#)  
[National Weather Service](#)  
[National Water Center](#)  
1325 East West Highway  
Silver Spring, MD 20910  
Questions?: [HDSC.Questions@noaa.gov](mailto:HDSC.Questions@noaa.gov)

[Disclaimer](#)



Hydrologic Soil Group—Norfolk and Suffolk Counties, Massachusetts  
(Millis Well 3 HSG Map)



Map Scale: 1:3,530 if printed on A portrait (8.5" x 11") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84



Natural Resources  
Conservation Service


Web Soil Survey  
National Cooperative Soil Survey

8/10/2023  
Page 1 of 4



## MAP LEGEND

### Area of Interest (AOI)









 Area of Interest (AOI)

### Soils

#### Soil Rating Polygons





 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Lines


 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Points






 A  
 A/D  
 B  
 B/D

 C  
 C/D  
 D  
 Not rated or not available


### Water Features

 Streams and Canals

### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads  
 Local Roads

### Background

 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:25,000.

**Warning:** Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Norfolk and Suffolk Counties, Massachusetts  
 Survey Area Data: Version 18, Sep 9, 2022

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 22, 2022—Jun 5, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
1	Water		0.6	1.1%
10	Scarboro and Birdsall soils, 0 to 3 percent slopes	A/D	1.8	3.0%
31A	Walpole sandy loam, 0 to 3 percent slopes	B/D	2.0	3.4%
51	Swansea muck, 0 to 1 percent slopes	B/D	19.0	32.5%
223B	Scio very fine sandy loam, 2 to 5 percent slopes	B/D	9.3	15.9%
245B	Hinckley loamy sand, 3 to 8 percent slopes	A	6.2	10.6%
245C	Hinckley loamy sand, 8 to 15 percent slopes	A	0.5	0.9%
254B	Merrimac fine sandy loam, 3 to 8 percent slopes	A	3.1	5.2%
260B	Sudbury fine sandy loam, 2 to 8 percent slopes	B	3.1	5.3%
600	Pits, sand and gravel		4.9	8.5%
653	Udorthents, sandy	A	8.0	13.7%
<b>Totals for Area of Interest</b>			<b>58.4</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified


*Tie-break Rule:* Higher







Appendix G  
Boring Logs



**DRILLING METHOD/SAMPLER TYPE GRAPHICS**

 STANDARD PENETRATION SPLIT SPOON SAMPLER (2 in. (50.8 mm.) outer diameter and 1-3/8 in. (34.9 mm.) inner diameter)

**GROUND WATER GRAPHICS**

-  WATER LEVEL (level where first observed)
-  WATER LEVEL (level after stabilizing period)
-  WATER LEVEL (additional levels after exploration)
-  OBSERVED SEEPAGE

**NOTES**

- The report and graphics key are an integral part of these logs. All data and interpretations in this log are subject to the explanations and limitations stated in the report.
- Solid lines separating strata on the logs represent approximate boundaries only, dashed lines are inferred or extrapolated boundaries. Actual transitions may be gradual or differ from those represented.
- No warranty is provided as to the continuity of soil or rock conditions between individual sample locations.
- Logs represent general soil or rock conditions observed at the point of exploration on the date indicated.
- In general, Unified Soil Classification System (ASTM D2488/D2487) designations presented on the logs were based on visual classification in the field and were modified where appropriate based on gradation and index property testing.
- Fine grained soils that plot within the hatched area on the Plasticity Chart, and coarse grained soils with between 5% and 12% passing the No. 200 sieve require dual USCS symbols, i.e., CL-ML, GW-GM, GP-GM, GW-GC, GP-GC, GC-GM, SW-SM, SP-SM, SW-SC, SP-SC, SC-SM.
- If sampler is not able to be driven at least 6 inches then 50/X indicates number of blows required to drive the identified sampler X inches with a 140 pound hammer falling 30 inches.


**ABBREVIATIONS**

**WOH** - Weight of Hammer  
**WOR** - Weight of Rod


**REFERENCES**

1. American Society for Materials and Testing (ASTM), 2011, ASTM D2487: Classification of Soils for Engineering Purposes (Unified Soil Classification System).

**UNIFIED SOIL CLASSIFICATION SYSTEM<sup>1</sup>**


GRAVELS (More than 50% of coarse fraction retained on No. 200 Sieve)	CLEAN GRAVEL WITH <5% FINES		GW	WELL-GRADED GRAVEL, WELL-GRADED GRAVEL WITH SAND
			GP	POORLY GRADED GRAVEL, POORLY GRADED GRAVEL WITH SAND
	GRAVELS WITH 5% TO 12% FINES		GW-GM	WELL-GRADED GRAVEL WITH SILT, WELL-GRADED GRAVEL WITH SILT AND SAND
			GW-GC	WELL-GRADED GRAVEL WITH CLAY (OR SILTY CLAY), WELL-GRADED GRAVEL WITH CLAY AND SAND (OR SILT CLAY AND SAND)
			GP-GM	POORLY GRADED GRAVEL WITH SILT, POORLY GRADED GRAVEL WITH SILT AND SAND
			GP-GC	POORLY GRADED GRAVEL WITH CLAY (OR SILTY CLAY), POORLY GRADED GRAVEL WITH CLAY AND (OR SILTY CLAY AND SAND)
COARSE GRAINED SOILS (More than 50% retained on No. 200 Sieve)	CLEAN SANDS WITH <5% FINES		SW	WELL-GRADED SAND, WELL-GRADED SAND WITH GRAVEL
			SP	POORLY GRADED SAND, POORLY GRADED SAND WITH GRAVEL
	SANDS WITH 5% TO 12% FINES		SW-SM	WELL-GRADED SAND WITH SILT, WELL-GRADED SAND WITH SILT AND GRAVEL
			SW-SC	WELL-GRADED SAND WITH CLAY (OR SILTY CLAY), WELL-GRADED SAND WITH CLAY AND GRAVEL (OR SILTY CLAY AND GRAVEL)
			SP-SM	POORLY GRADED SAND WITH SILT, POORLY GRADED SAND WITH SILT AND GRAVEL
			SP-SC	POORLY GRADED SAND WITH CLAY, POORLY GRADED SAND WITH CLAY AND GRAVEL (OR SILTY CLAY AND GRAVEL)
SANDS WITH > 12% FINES		SM	SILTY SAND, SILTY SAND WITH GRAVEL	
		SC	CLAYEY SAND, CLAYEY SAND WITH GRAVEL	
		SC-SM	SILTY, CLAYEY SAND, SILTY, CLAYEY SAND WITH GRAVEL	
FINE GRAINED SOILS (50% or more passes the No. #200 sieve)	SILTS AND CLAYS (Liquid Limit less than 50)		ML	SILT, SILT WITH SAND, SILT WITH GRAVEL
			CL	LEAN CLAY, LEAN CLAY WITH SAND, LEAN CLAY WITH GRAVEL
			CL-ML	SILTY CLAY, SILTY CLAY WITH SAND, SILTY CLAY WITH GRAVEL
	SILTS AND CLAYS (Liquid Limit 50 or greater)		OL	ORGANIC CLAY, ORGANIC CLAY WITH SAND, ORGANIC CLAY WITH GRAVEL, ORGANIC SILT, ORGANIC SILT WITH SAND, ORGANIC SILT WITH GRAVEL
			MH	ELASTIC SILT, ELASTIC SILT WITH SAND, ELASTIC SILT WITH GRAVEL
			CH	FAT CLAY, FAT CLAY WITH SAND, FAT CLAY WITH GRAVEL
	OH	ORGANIC CLAY, ORGANIC CLAY WITH SAND, ORGANIC CLAY WITH GRAVEL, ORGANIC SILT, ORGANIC SILT WITH SAND, ORGANIC SILT WITH GRAVEL		

**NOTE: USE MATERIAL DESCRIPTION ON THE LOG TO DEFINE A GRAPHIC THAT MAY NOT BE PROVIDED ON THIS LEGEND.**

 <b>KLEINFELDER</b> <i>Bright People. Right Solutions.</i>	PROJECT NO.: 20233667.001A	<b>GRAPHICS KEY</b>  Well 3 PFAS Piloting and Preliminary Design 25 Birch Street Millis, MA
	DRAWN BY: AD CHECKED BY: MR DATE: 3/17/2023	

**GRAIN SIZE**

DESCRIPTION	SIEVE SIZE	GRAIN SIZE	APPROXIMATE SIZE
Boulders	>12 in. (304.8 mm.)	>12 in. (304.8 mm.)	Larger than basketball-sized
Cobbles	3 - 12 in. (76.2 - 304.8 mm.)	3 - 12 in. (76.2 - 304.8 mm.)	Fist-sized to basketball-sized
Gravel	coarse 3/4 - 3 in. (19 - 76.2 mm.)	3/4 - 3 in. (19 - 76.2 mm.)	Thumb-sized to fist-sized
	fine #4 - 3/4 in. (#4 - 19 mm.)	0.19 - 0.75 in. (4.8 - 19 mm.)	Pea-sized to thumb-sized
Sand	coarse #10 - #4	0.079 - 0.19 in. (2 - 4.9 mm.)	Rock salt-sized to pea-sized
	medium #40 - #10	0.017 - 0.079 in. (0.43 - 2 mm.)	Sugar-sized to rock salt-sized
	fine #200 - #40	0.0029 - 0.017 in. (0.07 - 0.43 mm.)	Flour-sized to sugar-sized
Fines	Passing #200	<0.0029 in. (<0.07 mm.)	Flour-sized and smaller



**SECONDARY CONSTITUENT**

Term of Use	AMOUNT	
	Secondary Constituent is Fine Grained	Secondary Constituent is Coarse Grained
Trace	<5%	<15%
With	≥5 to <15%	≥15 to <30%
Modifier	≥15%	≥30%

**MOISTURE CONTENT**

DESCRIPTION	FIELD TEST
Dry	Absence of moisture, dusty, dry to the touch
Moist	Damp but no visible water
Wet	Visible free water, usually soil is below water table

**CEMENTATION**

DESCRIPTION	FIELD TEST
Weakly	Crumbles or breaks with handling or slight finger pressure
Moderately	Crumbles or breaks with considerable finger pressure
Strongly	Will not crumble or break with finger pressure

**CONSISTENCY - FINE-GRAINED SOIL**

CONSISTENCY	TCP VALUES	FIELD IDENTIFICATION
Very Soft	0 - 8	Core (height twice diameter) sags under own weight
Soft	8 - 20	Core can be pinched or imprinted easily with finger
Stiff	20 - 40	Core can be imprinted with considerable pressure
Very Stiff	40 - 80	Core can be imprinted only slightly with fingers
Hard	80 - 5 in./100	Core cannot be imprinted with fingers but can be penetrated with pencil
Very Hard	0 in. - 5 in. /100	Core cannot be penetrated with pencil

**REACTION WITH HYDROCHLORIC ACID**

DESCRIPTION	FIELD TEST
None	No visible reaction
Weak	Some reaction, with bubbles forming slowly
Strong	Violent reaction, with bubbles forming immediately

**APPARENT / RELATIVE DENSITY - COARSE-GRAINED SOIL**

APPARENT DENSITY	TCP VALUES
Very Loose	0 - 8
Loose	8 - 20
Slightly Compact	20 - 40
Compact	40 - 80
Dense	80 - 5 in. /100
Very Dense	0 in. / 5 in. 100

**PLASTICITY**

DESCRIPTION	LL	FIELD TEST
Non-plastic	NP	A 1/8-in. (3 mm.) thread cannot be rolled at any water content.
Low (L)	< 30	The thread can barely be rolled and the lump or thread cannot be formed when drier than the plastic limit.
Medium (M)	30 - 50	The thread is easy to roll and not much time is required to reach the plastic limit. The thread cannot be rerolled after reaching the plastic limit. The lump or thread crumbles when drier than the plastic limit.
High (H)	> 50	It takes considerable time rolling and kneading to reach the plastic limit. The thread can be rerolled several times after reaching the plastic limit. The lump or thread can be formed without crumbling when drier than the plastic limit.

**STRUCTURE**

DESCRIPTION	CRITERIA
Stratified	Alternating layers of varying material or color with layers at least 1/4-in. thick, note thickness.
Laminated	Alternating layers of varying material or color with the layer less than 1/4-in. thick, note thickness.
Fissured	Breaks along definite planes of fracture with little resistance to fracturing.
Slickensided	Fracture planes appear polished or glossy, sometimes striated.
Blocky	Cohesive soil that can be broken down into small angular lumps which resist further breakdown.
Lensed	Inclusion of small pockets of different soils, such as small lenses of sand scattered through a mass of clay; note thickness.

**ANGULARITY**

DESCRIPTION	CRITERIA
Angular	Particles have sharp edges and relatively plane sides with unpolished surfaces.
Subangular	Particles are similar to angular description but have rounded edges.
Subrounded	Particles have nearly plane sides but have well-rounded corners and edges.
Rounded	Particles have smoothly curved sides and no edges.



PROJECT NO.:  
20233667.001A  
  
 DRAWN BY: AD  
 CHECKED BY: MR  
 DATE: 3/17/2023


**SOIL DESCRIPTION KEY**

Well 3 PFAS Piloting and Preliminary Design  
 25 Birch Street  
 Millis, MA

PLOTTED: 03/17/2023 04:16 PM BY: ADarajat  
 PROJECT NUMBER: 20233667.001A  
 OFFICE FILTER: BOSTON  
 GINT LIBRARY: 2023.GLB [ KLF\_BORING/TEST PIT SOIL LOG ]  
 GINT FILE: KLF\_gint\_master\_2023  
 GINT TEMPLATE: E:KLF\_STANDARD\_GINT\_LIBRARY\_2023.GLB

<b>Date Begin - End:</b> 1/26/2023	<b>Drilling Company:</b> New England Boring Contractors	<b>BORING LOG B-W3-101</b>
<b>Logged By:</b> A. Darajat	<b>Drill Crew:</b> M. Misiaszek	
<b>Hor.-Vert. Datum:</b> NAD83 - NAVD88	<b>Drilling Equipment:</b> D-53	<b>Hammer Type - Drop:</b> 140 lb. Auto - 30 in.
<b>Plunge:</b> -90 degrees	<b>Drilling Method:</b> Drive and Wash with Casing	
<b>Weather:</b> Cloudy 40s	<b>Exploration Diameter:</b> 4 in. I.D.	

Elevation (feet) Depth (feet)	Graphical Log	FIELD EXPLORATION					LABORATORY RESULTS								
		Ground Surface Elevation (ft.): 126.90 Surface Condition: Bare Earth and Grass		Sample Number	Sample Type	Blow Counts(BC)= Uncorr. Blows/6 in.	Recovery (NR=No Recovery)	USCS Symbol	Water Content (%)	Dry Unit Wt. (pcf)	Passing #4 (%)	Passing #200 (%)	Liquid Limit	Plasticity Index (NP=NonPlastic)	Additional Tests/ Remarks
		Lithologic Description													
	6" Topsoil	S-1	BC=1 1 1	12"											
125	Brown, very loose, fine to coarse SAND, little silt, trace gravel, trace roots (subsoil)														
	Top (A): Brown, fine to coarse SAND, little silt, trace gravel (subsoil)	S-2A	BC=WOH 1	12"											
	Bottom (B): Gray/brown, fine to coarse SAND, some gravel, little silt	S-2B	BC=3 12	8"											
5	Gray/brown, very dense, fine to coarse SAND, some gravel, little silt	S-3	BC=4 20 42 45	17"					77	10					
120	Gray/brown, very dense, fine to coarse SAND and GRAVEL, trace silt	S-4	BC=30 29 32 40	10"										Hard casing penetration from 4.5 to 8 ft bgs. 300 lb hammer was introduced to drive casing.	
	Brown, dense, fine to coarse SAND and GRAVEL, trace silt	S-5	BC=16 17 17 22	12"											
115	Brown, dense, GRAVEL, some fine to coarse SAND, little clayey silt	S-6	BC=15 20 18 18	10"					46	12					
110	Brown/gray, medium dense, fine to coarse SAND and GRAVEL, trace silt	S-7	BC=8 9 10 13	8"											
105	Brown, medium dense, fine to coarse SAND, some gravel, trace silt	S-8	BC=11 10	4"											

 <p><b>KLEINFELDER</b> Bright People. Right Solutions.</p>	PROJECT NO.: 20233667.001A	<b>BORING LOG B-W3-101</b>
	DRAWN BY: AD CHECKED BY: MR DATE: 3/17/2023	Well 3 PFAS Piloting and Preliminary Design 25 Birch Street Millis, MA

PLOTTED: 03/17/2023 04:16 PM BY: ADarajat

**Date Begin - End:** 1/26/2023 **Drilling Company:** New England Boring Contractors **BORING LOG B-W3-101**  
**Logged By:** A. Darajat **Drill Crew:** M. Misiaszek  
**Hor.-Vert. Datum:** NAD83 - NAVD88 **Drilling Equipment:** D-53 **Hammer Type - Drop:** 140 lb. Auto - 30 in.  
**Plunge:** -90 degrees **Drilling Method:** Drive and Wash with Casing  
**Weather:** Cloudy 40s **Exploration Diameter:** 4 in. I.D.

Elevation (feet) Depth (feet)	Graphical Log	FIELD EXPLORATION				LABORATORY RESULTS								
		Ground Surface Elevation (ft.): 126.90 Surface Condition: Bare Earth and Grass	Sample Number	Sample Type	Blow Counts(BC)= Uncorr. Blows/6 in.	Recovery (NR=No Recovery)	USCS Symbol	Water Content (%)	Dry Unit Wt. (pcf)	Passing #4 (%)	Passing #200 (%)	Liquid Limit	Plasticity Index (NP=NonPlastic)	Additional Tests/ Remarks
100		S-8 (cont.)	▲	8 15	4" (cont.)									
30		Brown, medium dense, fine to coarse SAND and GRAVEL, trace silt		S-9	BC=9 8 8 8	6"								
95														
35		Gray/brown, medium dense, fine to coarse SAND, trace gravel, trace silt	S-10	▲	BC=8 7 7 9	7"			91	7.6				
90														
40		Gray/brown, medium dense, fine to coarse SAND and GRAVEL, trace silt	S-11	▲	BC=7 9 8 6	6"								
85														
45		Gray/brown, medium dense, fine to coarse SAND and GRAVEL, trace silt	S-12	▲	BC=6 5 6 5	5"								
80														
		Gray/brown, medium dense, fine to coarse SAND and GRAVEL, trace silt	S-13	▲	BC=11 10	6"			53	5.1				

PROJECT NUMBER: 20233667.001A OFFICE FILTER: BOSTON  
 GINT LIBRARY: 2023.GLB [ KLF\_BORING/TEST PIT SOIL LOG ]  
 GINT TEMPLATE: E:KLF\_STANDARD\_GINT\_LIBRARY\_2023.GLB



PROJECT NO.:  
20233667.001A  
  
 DRAWN BY: AD  
 CHECKED BY: MR  
 DATE: 3/17/2023

**BORING LOG B-W3-101**  
  
 Well 3 PFAS Piloting and Preliminary Design  
 25 Birch Street  
 Millis, MA




PLOTTED: 03/17/2023 04:16 PM BY: ADarajat

<b>Date Begin - End:</b> 1/26/2023	<b>Drilling Company:</b> New England Boring Contractors	<b>BORING LOG B-W3-101</b>
<b>Logged By:</b> A. Darajat	<b>Drill Crew:</b> M. Misiaszek	
<b>Hor.-Vert. Datum:</b> NAD83 - NAVD88	<b>Drilling Equipment:</b> D-53	<b>Hammer Type - Drop:</b> 140 lb. Auto - 30 in.
<b>Plunge:</b> -90 degrees	<b>Drilling Method:</b> Drive and Wash with Casing	
<b>Weather:</b> Cloudy 40s	<b>Exploration Diameter:</b> 4 in. I.D.	

Elevation (feet)	Depth (feet)	Graphical Log	FIELD EXPLORATION					LABORATORY RESULTS						
			Ground Surface Elevation (ft.): 126.90 Surface Condition: Bare Earth and Grass	Sample Number	Sample Type	Blow Counts(BC)= Uncorr. Blows/6 in.	Recovery (NR=No Recovery)	USCS Symbol	Water Content (%)	Dry Unit Wt. (pcf)	Passing #4 (%)	Passing #200 (%)	Liquid Limit	Plasticity Index (NP=NonPlastic)
		Lithologic Description	S-13 (cont.)	14 14	6" (cont.)									
75		75.9	<p>The boring was terminated at approximately 51 ft. below ground surface. The boring was backfilled with drill cuttings on January 26, 2023.</p>					<p><b>GROUNDWATER LEVEL INFORMATION:</b>  <input checked="" type="checkbox"/> Groundwater was observed at approximately 8.5 ft. below ground surface during drilling.</p> <p><b>GENERAL NOTES:</b>                      1. Ground Surface Elevation based on drawing titled "Well 3 site plan" prepared by Kleinfelder, dated October 2022.                      2. Where strata breaks are not observed in the split spoon samples, strata breaks are inferred based on observation of drill rig behavior (rig bouncing and chattering), change in auger/rollerbit penetration resistance, drill cuttings and changes in drilling water color.</p>						

PROJECT NUMBER: 20233667.001A OFFICE FILTER: BOSTON  
 GINT LIBRARY: E:\KLF\_STANDARD\_GINT\_LIBRARY\_2023.GLB [ KLF\_BORING/TEST PIT SOIL LOG ]

	PROJECT NO.: 20233667.001A	<b>BORING LOG B-W3-101</b>
	DRAWN BY: AD CHECKED BY: MR DATE: 3/17/2023	Well 3 PFAS Piloting and Preliminary Design 25 Birch Street Millis, MA